



AGNICO EAGLE

MELIADINE GOLD PROJECT

Water Management Plan

**AUGUST 2020
VERSION 10
6513-MPS-11**

EXECUTIVE SUMMARY (ENGLISH)

Agnico Eagle Mines Limited (Agnico Eagle) is developing the Meliadine Gold Project (the Mine), located approximately 25 kilometres (km) north of Rankin Inlet, and 80 km southwest of Chesterfield Inlet in the Kivalliq Region of Nunavut. The Mine Plan proposes open pit and underground mining methods for the development of the Tiriganiaq gold deposit, with two open pits (Tiriganiaq Pit 1 and Tiriganiaq Pit 2) and one Underground Mine.

The water management objectives are to minimize potential impacts to the quantity and quality of surface water at the Mine. Water management structures (surface ponds, water retention dikes/berms, water diversion channels and culverts) are in place and will be constructed as needed to contain and manage the contact water from the areas affected by the Mine or mining activities. The major water management infrastructure includes: water containment ponds, water retention dikes, berms, channels, a potable Water Treatment Plant (WTP), a Sewage Treatment Plant (STP), a Saline Water Treatment Plant (SWTP), a Reverse Osmosis (RO) Plant, an Effluent Water Treatment Plant (EWTP), and a Saline Effluent Treatment Plant (SETP).

During mine Construction and Operations, contact water originating from affected areas on surface will be intercepted, diverted and collected within the various containment ponds. The collected water at the Mine will be eventually pumped and stored in Containment Pond 1 (CP1), where the contact water will be treated by the EWTP for removal of Total Suspended Solids (TSS) prior to discharge to the outside environment or as make-up water by the Process Plant. Contact water from the Underground Mine will be collected in underground storage stopes and sumps. Some water from Underground will be reused for underground operations. Excess saline contact water will be pumped to and stored in surface saline ponds, and subsequently treated at the SWTP or SETP for discharge to the sea.

The long-term, post-closure water quality in the containment ponds and in the flooded open pit lakes will meet Metal and Diamond Mining Effluent Regulations (MDMER), Canadian Council of Ministers of the Environment Water Quality Guidelines (CCME-WQG) for the protection of aquatic life and/or the Site Specific Water Quality Objectives (SSWQO's) developed for the Mine.

During mine closure, the water management infrastructure on site will remain in place until mine closure activities are completed and monitoring demonstrates that the water quality is acceptable for environmental discharge without treatment.

ደብዳቤ ማረጋገጫ

ቅድመ ስጦት ለውጭ አካባቢ ጥገና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ፣ 25 ደብዳቤ ለውጭ አካባቢ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ፣ 25 ደብዳቤ ለውጭ አካባቢ ጥገና ስልጠና ለማድረግ...

ለውጭ አካባቢ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ፣ 25 ደብዳቤ ለውጭ አካባቢ ጥገና ስልጠና ለማድረግ... (ውሃ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ...)

ውጭ አካባቢ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ... (ውጭ አካባቢ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ...)

የውጭ አካባቢ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ... (ውጭ አካባቢ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ...)

ውጭ አካባቢ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ... (ውጭ አካባቢ ጥገና ስልጠና ለማድረግ የሚያስፈልገውን የውሃ ጥገና ስልጠና ለማድረግ...)



TABLE OF CONTENTS

Executive Summary (English)	i
ᑭᐱᑦ ᑭᐱᑦᐱᑦ	ii
Table of Contents	iii
List of figures	vi
LIST OF TABLES	vii
Document Control	i
Acronyms	iv
Units	v
Section 1 • Introduction	6
1.1 Water Management Objectives	6
1.2 Management and Execution of the Water Management Plan	6
Section 2 • Background	8
2.1 Site Conditions	8
2.1.1 Local Hydrology	8
2.1.2 Ice and Winter Flows	8
2.1.3 Spring Melt (freshet) and Freeze-up Conditions	9
2.1.4 Permafrost	9
2.1.5 Local Hydrogeology	9
2.2 Mine Development Plan	9
Section 3 • Water Management Controls and Structures	11
3.1 Water Management Systems	11
3.2 Water Management Structures Design Criteria	14
3.3 Water Containment ponds	16
3.4 P-Area Containment Ponds	16
3.5 Saline Ponds	17
3.6 Water Diversion Channels, Dikes and Berms	18

3.6.1	Water Diversion Channels	18
3.6.2	Water Retention Dikes and Berms	19
3.6.2.1	Thermal Monitoring	20
3.7	Evaporators	20
3.8	Freshwater Intake	21
3.9	Water Treatment	21
3.9.1	Freshwater Treatment Plant (WTP)	21
3.9.2	Sewage Treatment Plant (STP)	21
3.9.3	Saline Water Treatment Plant (SWTP)	22
3.9.4	Effluent Water Treatment Plant (EWTP)	22
3.9.5	Saline Effluent Treatment Plant (SETP)	23
3.9.6	Oil Separators	23
3.10	Meliadine Lake Discharge Diffuser	24
3.11	Saline Water Discharge to Sea	24
3.12	Water Management Structure Monitoring	24
3.12.1	Culvert and Water Crossing Inspections	24
3.12.2	Containment Pond Inspections	25
3.12.3	Dike and Thermal Berm Inspections	25
3.12.4	Water Diversion Channel and Berm Inspections	26
Section 4 • Water Management Strategy		27
4.1	Key Water Management Activities	28
4.1.1	Pond Dewatering and Displacement	30
4.1.2	Underground Water Management	31
4.1.3	Water Management for Haul Road	32
4.1.4	Water Management for Landfarm and Landfill	32
4.1.5	Water Management for Emulsion Plant Area	33
4.1.6	Water Management for the Wash Bay	33
4.2	Freshwater and Sewage Management	33
4.2.1	Freshwater Management	33
4.2.2	Sewage Management	33
4.2.3	Process Water Management	34

4.3	Meliadine Lake Diffuser Effluent Flow Rates.....	34
Section 5 • Water Balance		36
5.1	Global Water Balance.....	36
5.2	Waterbody Inventory	36
Section 6 • Water Quality.....		38
6.1	Summary of Regulatory Guidelines	38
6.2	Water Quality Monitoring - Licence Amendment No. 1	39
6.3	Water Quality Modelling and Forecasts.....	39
6.4	Post-Closure.....	39
Section 7 • Water Management During Closure		40
7.1	Open Pits Flooding.....	40
7.2	Underground Mine Flooding	41
7.3	Containment Ponds, Dikes and Berms.....	41
7.4	Channels and Sumps	42
References.....		43
Figures.....		46
Appendix A • Meliadine Groundwater Management Plan		52
Appendix B • Freshet Management Plan.....		53
Appendix C • Water balance and water quality forecast (Golder, 2020)		54
Appendix D • Sediment and Erosion Management Plan.....		55
Appendix E • Water Quality and Flow Monitoring Plan		56

LIST OF FIGURES

<i>Figure 1 : General Mine Site Location Plan</i>	46
<i>Figure 2: General Mine Site Plan Layout</i>	47
<i>Figure 3: P-Area Plan View</i>	47
<i>Figure 4: Location and design of Saline Pond 4 (SP4) within Tiriganiaq Pit 1</i>	48
<i>Figure 5: Watersheds and Waterbodies in Proximity of Mine Site</i>	48
<i>Figure 6: Water Quality Monitoring Locations on Site</i>	49
<i>Figure 7: Water Quality Monitoring Locations at Itivia</i>	49
<i>Figure 8: Mine Site Layout for Water Management During Closure from Feasibility Level Study. (TetraTech, 2014).</i>	50
<i>Figure 9: Mine Site Layout After Closure from Feasibility Level Study. (TetraTech, 2014).</i>	51

LIST OF TABLES

Table 1: Water Management Control Structures	13
Table 2: As-Built Parameters for CP1 and CP5	15
Table 3: Design Parameters for CP2, CP3, CP4, and CP6	15
Table 4: Location of Containment Pond and Required Operation Periods	16
Table 5: As-Built Capacity for P-Area Ponds	17
Table 6: Storage Capacities for Saline Pond 1 and Saline Pond 4	18
Table 7: As-Built and Design Parameters for Channels	19
Table 8: As-Built and Design Parameters for Water Retention Dike/Berm	20
Table 9: Overall Site Surface Contact Water Management Plan	28
Table 10: Key Water Management Activities	28
Table 11: Estimated Pond Dewatering Schedule	31
Table 12: Predicted Groundwater Inflow to the Underground Mine (2017 to 2032)	32
Table 13: Estimated Effluent Flow Rates over Mine Operating Life	35
Table 14: Inventory of Waterbodies Impacted by Mining Activities	37
Table 15: Key Water Management Activities during Mine Closure	40
Table 16: Pit and Underground Flooding	41

DOCUMENT CONTROL

Version	Date	Section	Page	Revision	Author
6	March 2019	All	All	Update is to fulfill annual review requirement (NWB)	Environment Department
		1	4	Update to Mine Development Plan information	
		3.1	8-12	Updated Version 6 changes	
		3.2	11-12	Updated existing water management control structures	
				Revised structure design semantics; corrections to culvert design; updated CP3, CP4 design parameters and naming convention; removed incorrect artifact pertaining to culvert 1 flow handling	
		3.3	12-14	Handling	
		3.6	15	Addition of SP3; updates to SP2 design	
		3.8, 3.9	17-21	Included as-built parameter values; updated berm and dike naming convention, thermistor information	
				Updated freshwater intake design information; updates to SWTP system; RO management; EWTP monitoring; removed incorrect information pertaining to Freshwater intake	
		3.11	21-22	Updated management of saline discharge to sea; revised information proposed in initial design	
		4.1, 4.2	25-31	Updated key management activities schedule to include discharge to sea; updated regarding underground inflow management; revised haul road management; revised wash bay management; updated process water quantities	
				Updated impacted waterbodies status	
		4.6	35	Revised semantics regarding flow paths	
		6.3	37	Included additional information regarding July 23 rd exceedance	
7	40	Updated Layout to most recent General Mine Site Plan			
7	August 2019	Figure 1.2	Updated Layout with monitoring stations to most recent General Mine Site Plan		
		Figure 6.1, 6.2	Specified plan layouts are from feasibility level study		
		Figure 7.1a	Updated Layout with monitoring stations to most recent General Mine Site Plan		
		3.9.4	20	Updated EWTP trigger limit to account for variance introduced by TSS-turbidity correlation strength	
4.1	26	Updated Key Activities (Table 10) to reflect changes to H19/H20 dewatering schedule			
		Revised H19/H20 dewatering plan with requirements for advancement in dewatering schedule; Updated dewatering schedule (Table 11)			

8	November 2019	3.5	15-16	Updated Saline Pond section to include current existence of SP2 and plans for construction of SP4.
		Figure 3.2	55	Figure changed from planned location of SP2 to planned location of SP4.
9	March 2020	All	All	Update is to fulfill annual review requirement (NWB)
		Exec. Summary		Updated to include SETP, excess saline contact water management
		3.1	9	Updated existing water management systems (saline ponds, SETP, discharge to sea)
		3.2	12	Updated Table 2 and Table 3
		3.3	13	Updated to include CP4 as existing structure and modified CP6 construction date
		3.4	15	Update to Section
		3.5	15	Updated to Section
		3.6	16-17	Updated Table 7
		3.9	19-21	Update to SWTP and EWTP systems, addition of SETP
		3.11	22	Updated management of saline water discharge to sea
		3.12	23	Update to Section
		4.1	26-30	Updated Table 10 and Section
		4.2	31	Updated process water management
		4.3	32-33	Updated Meliadine Lake diffuser effluent flow rates and EWTP sludge disposal options
		5	33-34	Update to Section
		7	40	Update to Section. Removed information already presented in annual report (i.e., MEL-14 and MEL-SR results).
		Figure 1.1		Updated Layout to most recent General Mine Site Location Plan
Figure 1.2		Updated Layout to most recent General Mine Site Plan		
10	July 2020	All	All	Updated to support Water Licence Amendment
		3	11-22	Updated to include CP2, CP2-Berm, Channel 9 and 10, and decommissioning of SP2
		3.1	13	Updated Table 1 and section
		3.2	15	Updated Table 3 and section
		3.3	16	Updated Table 4 and section
		3.5	18	Removed SP2 and updated Table 6 and section
		3.6	18-20	Updated Table 7 and 8 and section
		3.9.4	25	Update to EWTP system
		4	27-35	Updated to add CP2 and update Table 9 and 10
		4.3	34-35	Update EWTP discharge rate and Table 13
5	36-38	Water Balance update, moved section of Water Balance results and table into appendix C		
6	40-41	Water Quality update		

7	42	ICRP 2020 update and Table 16 to include CP2
Figure 2		Updated layout to most recent General Mine Site
Figure 4		Updated following decommissioning of SP2
Figure 6		Updated to include CP2 monitoring
Figure 8		Updated layout to most recent General Mine Site during closure
Figure 9		Updated layout to most recent General Mine Site after closure

ACRONYMS

Agnico Eagle	Agnico Eagle Mines Limited
AWAR	All Weather Access Road
CCME-WQG	Canadian Council of Ministers of the Environment Water Quality Guidelines
CIRNAC	Crown-Indigenous Relations and Northern Affairs Canada
CP	Containment Pond
ECCC	Environment and Climate Change Canada
EMPP	Environmental Management and Protection Plan
EWTP	Effluent Water Treatment Plant
GWMP	Groundwater Management Plan
IDF	Inflow Design Flood
Licence	Type A Water Licence 2AM-MEL1631
MDMER	Metal and Diamond Mining Effluent Regulations
NWB	Nunavut Water Board
Mine	Meliadine Gold Project
SD	Support Document
SSWQO	Site Specific Water Quality Objectives
STP	Sewage Treatment Plant
SWTP	Saline Water Treatment Plant
TDS	Total Dissolved Solids
TSF	Tailings Storage Facility
TSS	Total Suspended Solids
WMP	Water Management Plan
WRSF	Waste Rock Storage Facility
WTP	Water Treatment plant

UNITS

%	percent
°C	degrees Celsius
°C/m	degrees Celsius per metre
mg/L	milligram per litre
km	kilometer(s)
km ²	kilo square meter(s)
m	metre
mm	millimetre
m ³	cubic metre(s)
m ³ /day	cubic metre per day
m ³ /s	cubic metre per second
m ³ /hour	cubic metre per hour
m ³ /year	cubic metre per year
Mm ³ /year	million cubic metre (s) per year
Mm ³	million cubic metre(s)
masl	metres above sea level
Mt	million tonne(s)

SECTION 1 • INTRODUCTION

Agnico Eagle Mines Ltd. (Agnico Eagle) operates the Meliadine Gold Project (the Mine) located approximately 25 kilometres (km) north of Rankin Inlet (Figure 1), Nunavut, and 80 km southwest of Chesterfield Inlet in the Kivalliq Region of Nunavut. The Mine is subject to the terms and conditions of both the amended Project Certificate issued by the Nunavut Impact Review Board (NIRB) in accordance with the Nunavut Land Claims Agreement Article 12.5.12 on February 26, 2019 (NIRB, 2019) and Type A Water Licence No. 2AM-MEL1631 (the Licence), issued by the Nunavut Water Board (NWB) on April 1, 2016 (NWB, 2016).

Agnico Eagle is planning to apply for amendments to the Water Licence to incorporate changes required for mine operation. This document presents an updated version of the Water Management Plan (WMP), which encompasses the changes to the water management in support of the Water Licence Amendment application. The major change to the WMP is that waste rock and overburden originally planned to be stored in WRSF2 will be placed within an increased footprint of the WRSF3. This extension will necessitate the construction of additional water management infrastructure (i.e., Channel 9, Channel 10, CP2, and CP2 thermal protection berm). The previous designated footprint for WRSF2 will be used for further expansion of the ore stockpile and construction of infrastructure to support open pit mining operations. In addition, an update to the water balance and the water quality was carried out by Golder (2020b) in support of the Water License Amendment application, including the incorporation of CP2.

1.1 Water Management Objectives

The water management objectives are to minimize potential impacts to the quantity and quality of surface water at the Mine and surrounding waterbodies. The purpose of the WMP is to provide information to applicable mine departments (Environment, Engineering, Mine, Energy and Infrastructure, etc.) for sound water management practices, proposed and existing infrastructure, the water balance model, water quality predictions, and for the water quality monitoring plan for the Mine.

Water management structures (culverts, sumps, pipelines, water diversion channels and water retention dikes/berms) are utilized to contain and manage contact water from areas affected by mining activities. Measures have been implemented for the Mine Construction and Mine Operation phases.

1.2 Management and Execution of the Water Management Plan

Revisions of the WMP can be initiated by changes in the Mine Development Plan (Mine Plan), operational performance, personnel or organizational structure, regulatory or social considerations,

and/ or design philosophy. The WMP will be reviewed annually by Agnico Eagle and updated as necessary.

SECTION 2 • BACKGROUND

2.1 Site Conditions

The Mine is located in an area of poorly drained lowlands near the northwest coast of Hudson Bay. The dominant terrain in the area consists of glacial landforms such as drumlins (glacial till), eskers (gravel and sand), and many small lakes. The topography is gently rolling with a mean elevation of 65 metres above sea level (masl) and a maximum relief of 20 meters.

The local overburden consists of a thin layer of topsoil overlying silty gravelly sandy glacial till. Cobbles and boulders are present throughout the region at various depths. Bedrock at the Mine site area consists of a stratigraphic sequence of clastic sediments, oxide iron formation, siltstones, graphitic argillite, and mafic volcanic flows (Snowden, 2008; Golder, 2009).

The climate is extreme in the area, with long cold winters and short cool summers, and mean air temperatures of 12°C in July and -31°C in January. The mean annual air temperature at the Mine site is approximately -10.4 °C (Golder, 2012a). Strong winds blow from the north and north-northwest direction more than 30 percent of the time.

The mean annual precipitation in the area is approximately 412 mm and is typically equally split between rainfall and snowfall.

2.1.1 Local Hydrology

The Mine is located within the Meliadine Lake watershed. Meliadine Lake has a water surface area of approximately 107 square kilometres (km²), a maximum length of 31 km, features a highly convoluted shoreline of 465 km, and has over 200 islands. Unlike most lakes, it has two outflows that drain into Hudson Bay through two separate river systems. It has a drainage area of 560 km² upstream of its two outflows. Most drainage occurs via the Meliadine River, which originates at the southwest end of the lake. The Meliadine River flows for a total stream distance of 39 km. The Meliadine River flows through a series of waterbodies, until it reaches Little Meliadine Lake and then continues into Hudson Bay. A second, smaller outflow from the west basin of Meliadine Lake drains into Peter Lake, which discharges into Hudson Bay through the Diana River system (a stream distance of 70 km). At its mouth, the Diana River has a drainage area of 1,460 km².

Watersheds in the Mine area are comprised of an extensive network of waterbodies, and interconnecting streams. The hydrology of these watersheds is dominated by lake storage and evaporation.

2.1.2 Ice and Winter Flows

Late-winter ice thicknesses on freshwater lakes in the Mine area range between 1.0 to 2.3 m with an average thickness of 1.7 m. Ice covers usually appear by the end of October and are completely

formed in early November. The spring ice melt (freshet) typically begins in mid-June and is complete by early July (Golder, 2012b).

2.1.3 Spring Melt (freshet) and Freeze-up Conditions

With the exception of the main outlet of Meliadine Lake, which has been observed to flow continuously throughout the year, outlets of waterbodies near the Mine typically start flowing late May or early June, followed by freshet flows in mid-to-late-June. Flows steadily decrease in July and low flows are ongoing from August to the end of October, prior to winter freeze.

2.1.4 Permafrost

The Mine is located in an area of continuous permafrost. The depth of permafrost is estimated to be in the order of 360 to 495 m. The depth of the active layer ranges from about 1 m in areas with shallow overburden, up to 3 m adjacent to the lakes. The typical permafrost ground temperatures at the depths of zero annual amplitude (typically at the depth of below 15 m) are in the range of -5.0 to -7.5 °C in the areas away from lakes and streams. The geothermal gradient ranges from 0.012 to 0.02 °C/m (Golder, 2012b).

2.1.5 Local Hydrogeology

Groundwater characteristics at areas of continuous permafrost that are generally present in the Mine area include the following flow regimes:

- A shallow flow regime located in an active layer (seasonally thawed) near the ground surface and above permafrost; and,
- A deep groundwater flow regime beneath the base of the permafrost.

From late spring to early autumn, when temperatures are above 0 °C, the shallow active layer thaws. Within the active layer, the water table is projected to be a subdued replica of topography. Groundwater in the active layer flows to local depressions and ponds that drain to larger waterbodies. The talik beneath large waterbodies will be open. The open talik will connect to the deep groundwater flow regime beneath the permafrost.

Elongated waterbodies with terraces and a width of 340 to 460 m or greater are expected to have open taliks extending to the deep groundwater flow regime at the Mine. Meliadine Lake and Lake B7 are likely to have open taliks connected to the deep groundwater flow regime (Golder, 2012a). No impact is expected to Lake B7 by mine activities.

2.2 Mine Development Plan

The Mine Plan and key mine development activities, including mine waste management are currently used concurrently with the WMP.

The Mine Plan includes one underground mine (Tiriganiaq Underground Mine) and two open pits (Tiriganiaq Open Pit 1 and Tiriganiaq Open Pit 2) for the development of the Tiriganiaq gold deposit.

The Mine is expected to produce approximately 15.4 million tonnes (Mt) of ore, 31.4 Mt of waste rock, 7.0 Mt of overburden waste, and 15.4 Mt of tailings. The following phased approach is proposed for the development of the Tiriganiaq gold deposit;

- Phase 1: 3.5 years for Mine Construction (Q4 Year -5 to Q2 Year -1);
- Phase 2: 8.5 years for Mine Operations, beginning in 2019 (Q2 Year -1 to Year 8);
- Phase 3: 3 years Mine Closure (Year 9 to Year 11); and;
- Phase 4: Post-Closure (Year 11 forward).

Mining facilities on surface will include a plant site and accommodation buildings, two ore stockpiles, a temporary overburden stockpile, a tailings storage facility (TSF), two waste rock storage facilities (WRSFs), a water management system that includes containment ponds, water diversion channels, retention dikes/berms, and a series of water treatment plants. The general mine site layout plan is shown on Figure 2.

SECTION 3 • WATER MANAGEMENT CONTROLS AND STRUCTURES

A network of berms, dikes, containment ponds, channels, culverts and sumps are in place and maintained to facilitate water management. Design Reports and As-Built Reports have been submitted and approved for the water management structures discussed in this section, as applicable. This section is included to summarize design and as-built information.

As mentioned, Agnico Eagle is planning to apply for amendments to the Water Licence to incorporate changes required for mine operation. These changes include the removal of WRSF2; the waste rock and overburden originally planned to be stored in WRSF2 will be placed within an increased footprint of the WRSF3. This extension will necessitate the construction of additional water management infrastructure: Channel 9, Channel 10, CP2, and CP2 thermal protection berm. The design of these infrastructures has been developed at a prefeasibility level and is presented in the following sub-sections. The updated detailed design for WRSF3 and associated water management infrastructure will be carried out once Agnico Eagle obtains the approval of the Water Licence Amendment. The detailed design report and construction drawings will be submitted to the NWB for approval prior to construction as per Water Licence Conditions.

3.1 Water Management Systems

The water management systems, as shown in Figure 2 and Figure 3, include the following components:

- Six water containment ponds (CP1, CP2, CP3, CP4, CP5, and CP6) and their associated dikes or thermal berms (D-CP1, Berm CP2, Berm CP3, Berm CP4, D-CP5, and Berm CP6)
- Three P-Area containment ponds (P1, P2, and P3) and four containment berms (DP1-A, DP1-B, DP2-A, and DP3-A)
- Three surface Saline Ponds (SP1, SP3, and SP4)
- Three diversion berms (Berm 1, Berm 2, and Berm 3)
- Ten water diversion channels (Channel 1 to Channel 10)
- Sixteen water passage culverts to convey water (Culverts 1 to 8, 10, 11, 13, 14 to 16, 18, 19 and 20)
- Five evaporators
- A reverse osmosis (RO) treatment plant
- An effluent water treatment plant (EWTP)
- A saline water treatment plant (SWTP)
- A saline effluent treatment plant (SETP)
- A sewage treatment plant (STP)
- A potable water treatment plant (WTP)
- A network of surface pumps and pipelines

- A freshwater intake
- Two jetties and pumping infrastructure (CP1 and CP5)
- An effluent diffuser located in Meliadine Lake
- An effluent diffuser located in Melvin Bay

The status of construction and planned construction dates of the above are listed in Table 1.

Surface contact water is intercepted, diverted and contained within various containment ponds prior to passive evaporation, treatment and/or discharge. Water collected in CP3 and CP4 is discharged upstream of Culvert 2 where it flows to CP1. Water collected in CP5 is either treated by an RO treatment plant prior to discharging to CP1 or discharged to CP1 directly, depending on the in situ CP5 water quality. Water collected in CP6 is discharged directly to CP1. Runoff and direct precipitation collected in the P-area is pumped to CP5 (prior to RO treatment, as applicable) and discharged to CP1. At CP1, the water is treated for total suspended solids (TSS) at the EWTP and discharged through the diffuser located in Meliadine Lake.

Contact water from the Underground Mine is collected in underground sumps, transported to a clarification system, and subsequently recirculated for use in various underground operations. Excess underground contact water is stored in temporarily inactive underground developments, and on surface in Saline Pond 1 (SP1) and Saline Pond 4 (SP4). Saline Pond 2 was decommissioned in Q2 2020 and was replaced by Saline Pond 4 (SP4). Underground contact water that is not used for operations is treated at the Salt Water Treatment Plant (SWTP) or Saline Effluent Treatment Plant (SETP) for discharge (Section 3.9).

As part of the strategy to manage excess groundwater infiltration of saline water within the underground portion of the mine, Agnico Eagle received approval from the Nunavut Impact Review Board to discharge saline water to sea (Melvin Bay, Rankin Inlet) with the amended Project Certificate on February 26, 2019. An overview of management around discharge to sea is found in Section 3.11. Further details are found in Appendix A.

During the mine closure, the water management infrastructure will remain in place until closure activities are completed and monitoring demonstrates that water quality is acceptable for discharge to the environment without treatment.

A list of the water management control structures is presented in Table 1 with each respective construction status. Figure 2 shows the location of the respective structures over the development stages (Year – 5 to Year 8) of the mine life. Final design details of these structures will be provided to the Regulators for approval at least 30 days prior to construction, as per the Licence.

Table 1: Water Management Control Structures

Mine Phase	Infrastructure Name	Construction Status
Pre-Production Construction (Y-5 to Y 1)	Channel 1	Constructed
	Channel 2	Constructed
	Channel 3	Constructed
	Channel 4	Constructed
	Channel 5	Constructed
	Channel 6	TBD*
	Channel 7	Constructed
	Channel 8	Constructed
	Culvert 1	Constructed
	Culvert 2	Constructed
	Culvert 3	Constructed
	Culvert 4	Constructed
	Culvert 5	TBD*
	Culvert 6	TBD
	Culvert 7	Constructed
	Culvert 8	Constructed
	Culvert 10	Constructed
	Culvert 11	Constructed
	Culvert 13	Constructed
	Culvert 14	TBD
	Culvert 15	Constructed
	Culvert 16	Constructed
	Culvert 18	Constructed
	Culvert 19	TBD
	Culvert 20	Constructed
	CP1	Constructed
	CP3	Constructed
	CP4	Constructed
	CP5	Constructed
	D-CP1	Constructed
	Berm CP3	Constructed
	Berm CP4	Constructed
	D-CP5	Constructed
	CP1 Jetty	Constructed
CP5 Jetty	Constructed	
Saline Pond (SP1)	Constructed	
Saline Pond 2 (SP2)	Constructed	
Saline Pond 3 (SP3)	Constructed	

Mine Phase	Infrastructure Name	Construction Status
	Saline Pond 4 (SP4)	Constructed
	Berm 1	Constructed
	Berm 2	Constructed
	Berm 3	Constructed
	Freshwater Intake Causeway & Pump Station	Constructed
	Submerged Diffuser	Constructed
	WTP Intake	Constructed
Sustaining Construction during Mine Operation (Y1 to Y8)	CP6 and Berm CP6	Constructed
	CP2 and Berm CP2	TBD*
	Channel 9	TBD*
	Channel 10	TBD*

* Construction tentative based on future water management strategies

3.2 Water Management Structures Design Criteria

The water management systems meet the following criteria:

- Water quality will meet regulatory criteria of the Licence (described in Appendix E).
- Design capacity of the EWTP is sufficient to ensure that D-CP1 and CP1 is able to manage the surface contact water from the entire site for a 1:100 wet year spring freshet, or a 1:2 mean year spring freshet in combination with a 1:1000 return 24-hour extreme rainfall.
- D-CP5 and CP5 is able to manage the water from its catchment area for 3/7 of a 1:100 wet year spring freshet or a 1:1000 return 24-hour extreme rainfall. This design is based on an allowable 3-day delay in initiation of pumping during a 7-day, 1:100 year freshet. Design capacity of pumping from CP5 to CP1 is sufficient to ensure that remaining freshet inflows to CP5 are managed via pumping to CP1.
- Storage capacity of each of the other water management ponds (CP2, CP3, CP4, and CP6,) is able to manage the water from their respective catchment area for 3/7 of a 1:100 wet year spring freshet or a 1:1000 return 24-hour extreme rainfall.
- The daily pumping rate for each of the ponds (CP2 to CP6) is designed to have sufficient pumping capacity to handle the runoff water, which would result from one day (24.4 mm) of a 1:100 return wet spring freshet plus a 1:2 return one-hour rainfall (9.8 mm).

Channel 2 to Channel 4 are in place to pass an extreme intensity flow under a 5-minute 1:100 return rainfall of 9.2 mm. Channels 9 and 10 were designed to pass an extreme intensity flow under a 5-minute 1:100 return rainfall of 5.0 mm. Channel 1 and Channel 5 to Channel 8 in place or designed as internal channels where any water overflowing the channels will remain within the catchment areas of various containment ponds. Hydraulic analyses indicated that very wide channels are required to pass an extreme intensity flow under a 5-minute 1:100 return rainfall of 9.2 mm. As a result, these channels were designed to have a reasonable bottom width to pass a flow with lesser intensity, but

the water overflowing the channels can be safely managed by berms or temporarily stored in a lower basin nearby. For example, water overflowing Channel 5 can be contained by Berm 3. Water overflowing Channel 7 and Channel 8 can be stored in the lower basin in the drained Pond H13, and Berm 1 combined with a mass till backfill protects the Portal No.2 entrance from flooding. Furthermore, the MULTI-PLATE at Portal No. 2 is protected by compacted, engineered structural fill. Water overflowing Channel 1 will flow through the flat ground between Ore Pad 2 (OP2) and future WRSF2 into CP1. Table 2 presents the design parameters for CP1 and CP5.

Table 2: As-Built Parameters for CP1 and CP5

Pond	CP1	CP5
Pond Volume at Maximum Operating Elevation under Normal Operating Conditions and Mean Precipitation Years (m ³)	742,075	46,674
Maximum Operating Water Elevation (m)	66.2	66.0
Maximum Water Elevation during IDF (m)	66.6	66.3
Estimated Pond Volume for Water Elevation at Maximum Operating Water Elevation during IDF (m ³)	855,245	70,000
Dike for Pond	D-CP1	D-CP5
As-Built Crest Elevation of Dike Containment Element (liner system) (m)	67.37	66.72

CP2, CP3, CP4 and CP6 are established through excavation of the original ground to increase water storage capacity and help ensure water levels do not reach the thermal protection berms. The key design parameters for CP2, CP3, CP4 and CP6 are provided in Table 3 and are discussed in further detail within Tetra Tech (2018a) and Tetra Tech (2020a). Design parameters presented in this table for CP2 are based on the prefeasibility design by Tetra Tech (2020b).

Table 3: Design Parameters for CP2, CP3, CP4, and CP6

Pond	CP2	CP3	CP4	CP6
Elevated Pond Bottom Elevation (m)	45.0	56.0	56.0	54.0
Estimated Maximum Water Elevation during IDF (m)	52.0	63.0	63.0	60.0
Pond Volume for Water Elevation at Estimated Maximum Water Elevation during IDF (m ³)	64,000	28,800	35,093	32,757
Pond Surface Area at Estimated Maximum Water Elevation during IDF (m ²)	17,004	6,583	8,805	8,602
Thermal Berm for Pond	Berm-CP2	Berm-CP3	Berm-CP4	Berm-CP6

3.3 Water Containment ponds

Five water containment ponds (CP1, CP3, CP4, CP5 and CP6) have been constructed to date as part of the water management infrastructure. Table 4 presents the locations and the required operational period of the containment ponds. The locations of the six water containment ponds are shown on Figure 2.

Table 4: Location of Containment Pond and Required Operation Periods

Containment Pond	Relative Location	Required Operation Period
CP1	Pond H17 and H6	Year 2017 to Mine closure
CP3	North of Lake B7 and southwest of TSF	Year 2019 to Mine closure
CP4	Southeast of Lake B7 and south of WRSF1	Year 2019 to Mine closure
CP5	North of Tiriganiaq Pit 2	Year 2017 to Mine closure
CP6	Pond H19 and north of WRSF3	Year 2020 to Mine closure
CP2	East of WRSF3	Year 2024 to Mine closure

3.4 P-Area Containment Ponds

The P-area consists of three storage ponds and four water containment berms. Over 2016 to 2018, the P-Area was applied as a component of saline water management system, specifically as a storage unit for excess saline groundwater. In an effort to begin decommissioning of the P-area, no inputs of saline groundwater occurred in 2019 and have not been occurring in 2020. Currently, inputs to the P-area solely include runoff from within the P-Area catchment and direct precipitation.

The total storage capacity of the P-Area ponds is 46,041 m³. P1, P2 and P3 are contained by berms DP1-A, DP1-B, DP2-A, and DP3-A. Five evaporators have been installed on DP1-B. P1 is divided by a berm, producing P1-A (6,131.8 m³) as the southern section of P1, and P1-B (14,649 m³) as the northern section. P2 is adjacent and located south of P1-A. P3 was constructed east of the existing south access road, with the primary purpose of collecting seepage originating from the P2 confining berm and its abutments. Water which accumulates in P3 is pumped to either P1 or CP5, depending on water quality within P3 and the operation status of the RO in CP5. Table 5 summarizes the as-built capacities for the P-Area ponds and Figure 3 illustrates the P-Area plan view.

In Q2 of 2019, SP3 was installed within the southwestern portion of P3. SP3 is lined with a polyethylene geomembrane to prevent any seepage into or out of the containment structure, and acts as the final effluent storage pond for saline water that is to be discharged to sea (Section 3.11). After construction of SP3, the usable P3 containment volume was decreased by approximately 84%, due to a reduced footprint from the portion occupied by SP3, and a reduced water elevation to preserve the integrity of the SP3 liner.

A contaminated snow cell used to store snow containing hydrocarbons (i.e. snow on which spills occur) is located in the northwest corner of P1. The contaminated snow cell was constructed in 2017 (Agnico Eagle, 2017a) and is currently in place as a contingency measure for contaminated snow storage over the winter (Freshet Management Plan in Appendix B). Upon snowmelt, water within the contaminated snow cell is transferred to the Landfarm for treatment at the oil-water separator (Section 3.9.6).

The snow cell is lined with a polyethylene liner to avoid seepage of melting snow into the surrounding environment. The cell is designed to contain a volume of 1500 m³ of snow and to contain 930 m³ of water at a water surface elevation of 69.5 m.

Table 5: As-Built Capacity for P-Area Ponds

Pond	P1	P2	P3
As-built Capacity (m ³)	20,781	6,828	2,912*
Maximum Design Water Elevation (m)	68.5	67.5	66.22*
Total P-Area Capacity (m ³)	30,521		

*Former as-built volume reduced from 18,432 m³ due to construction of SP3 within the P3 footprint.

Water monitoring protocols for the P-Area have been implemented to include water quality and transfer data, such as locations and flow volumes for water pumped to and from the containment ponds. This is discussed further in Appendix E.

Following the decommissioning of the P-Area, Agnico Eagle will keep the five evaporators available if required.

3.5 Saline Ponds

Saline Pond 1 (SP1) was constructed in Q3 2016 to accommodate excess saline water from the Underground Mine. SP1 is located east of P3 and north of CP5 (Figure 2). Table 6 summarizes the Saline Pond capacity for storage and maximum designed operating water levels. The maximum saline water capacity is the volume that can be stored in SP1 prior to winter freeze. Approximately 7,500 m³ capacity should be available to accommodate precipitation that may accumulate throughout winter and at freshet.

Saline Pond 2 (SP2) was constructed in Q2 2019 as a temporary saline water storage pond on site, with the purpose of further accommodating excess saline water from the Underground Mine until treatment and discharge to sea performance is sufficient to dewater surface saline storage (Section 3.11; Appendix A). SP2 was constructed in bedrock within the footprint of Tiriganiaq Pit 2. SP2 was constructed to have a maximum storage volume of 78,000 m³, of which 10,000 m³ is reserved for precipitation accumulation over winter and runoff at freshet. SP2 was decommissioned and replaced

by Saline Pond 4 (SP4) in Q2 2020. The addition of SP4 has two purposes. First, to replace SP2 and allow the mining of Tiriganiaq Pit 2, and second, to supply additional storage for saline water on site. The additional storage is required due to continued groundwater infiltration to the underground workings and finite existing surface storage capacity. Following the completion of SP4, the water contained within SP2 was transferred to SP4.

Saline Pond 4 (SP4) was constructed in bedrock within the footprint of Tiriganiaq Pit 1 (Figure 4). A total of 249,708 m³ of overburden was removed during construction, with this material transported and placed within WRSF1. The excavation of SP4 also generated approximately 305,393 m³ (bank volume) of waste rock, a portion of which is temporarily stockpiled between the footprints of Tiriganiaq Pit 1 and Tiriganiaq Pit 2. This material was used as thermal protection of the overburden slopes during mining of Tiriganiaq Pit 2. The remainder of the rock from the SP4 excavation will be placed as overburden protection on WRSF1, used for general construction purposes and crushed for aggregates.

Groundwater will be pumped to SP4 where it will remain in storage until it is treated at the SWTP (desalination; Section 3.9.3) or at the SETP for discharge to sea (Section 3.11; Appendix A). Inputs to SP4 will be similar in chemical nature to SP1, mainly originating from the underground water storage system. SP4 is designed to have a minimum storage volume of 233,000 m³; allowing for 1.5 m of freeboard in bedrock. October to June precipitation runoff volumes to SP4 are preliminarily estimated to be 19,300 m³ for a mean climate year and 31,700 m³ for a 1:100 wet climate year. These values include June precipitation occurring during the snowmelt period. To ensure the capability to store runoff from a 1:100 wet climate year freshet, stored volume in SP4 prior to freshet will be maintained with a reserve of 31,700 m³.

Table 6: Storage Capacities for Saline Pond 1 and Saline Pond 4

Item	Saline Pond 1	Saline Pond 4
Maximum Design Water Elevation (m)	62.9	56.0
Maximum Water Capacity (m ³)	32,686*	233,122 [†]

* Tetra Tech (2017)

§ Maximum storage in bedrock to allow 0.3 m freeboard

† Minimum volume based on design to included 1.5 m freeboard

3.6 Water Diversion Channels, Dikes and Berms

3.6.1 Water Diversion Channels

Seven water diversion channels (Channels 1 to 5, 7 and 8) have been constructed and form part of the water management infrastructure. Construction of Channel 6 is tentative based on future water management strategies downstream of the P-area. Construction of Channels 9 and 10 is tentative based on the detailed design of these infrastructures. The as-built and design parameters for the

water diversion channels are presented in Table 7. Design parameters presented in this table for Channels 9 and 10 are based on the prefeasibility design by Tetra Tech (2020b).

Table 7: As-Built and Design Parameters for Channels

Channel	Approximate Total Length (m)	Bottom Width (m)	Side Slopes	Rip-rap Thickness (m)	Minimum Bottom Slope Gradient (%)	
1 (As-built)	528	3	3(H):1(V)**	0.3 to 0.5	0.2	
2 (As-built)	269.5	1.257	1.82(H):1(V)	0.277	0.30†	
3 (As-built)	656	1.2 to 2.4 or 0.8 to 3.3*	1.8(H):1.0(V) to 3.5(H):1.0(V)	0.3†	5.3 (upper)	0.4 (lower)
4 (As-built)	930	1.0 to 1.7 or 0.8 to 4.5*	1.8(H):1.0(V) to 5.0(H):1.0(V)	0.37	2.1 to 5.3 (upper)	0.1 to 4.2 (lower)
5 (As-built)	429†	2.3 to 2.9	1.9(H):1(V)	0.2	0.17†	
6	69	1	3(H):1(V)	0.3	0.44	
7 (As-built)	240	2	3(H):1(V)	0.59	0.8 (Avg.)	
8 (As-built)	114	2.4	3(H):1(V)	0.3	1.4 (Avg.)	
9	660	2.0	2.5(H):1(V)	0.3	0.3	
10	220	2.0	2.5(H):1(V)	0.3	1.3	

* 1 m bottom width for first 100 m upstream section, and 2 m bottom wide for the remaining channel section

** Except from Sta. 0+050 to 0+130: 2(H):1(V)

† As-built parameter values not available; value displayed is from design

3.6.2 Water Retention Dikes and Berms

In general terms, “dikes” were constructed with impervious liner systems and “berms” are constructed with entirely till cores. At the end of Mine closure, when the water quality in the corresponding pond meets direct discharge criteria, each of the dikes and berms on site (except for Berm 2) will be breached to restore the original natural drainage paths. Berm 2 will remain in place to prevent non-contact water from flowing into the TSF.

Water retention dikes D-CP1 and D-CP5 have been designed as a zoned earth fill dams with a geomembrane liner keyed into the permafrost foundation to limit the seepage through the dike and its foundation. The characteristics of the dikes and berms required for the WMP are summarized in Table 8. Design parameters presented in this table for Berm-CP2 are based on the prefeasibility design by Tetra Tech (2020b).

Table 8: As-Built and Design Parameters for Water Retention Dike/Berm

Dike/Berm	Approximate Maximum Height (m)	Maximum Elevation (m)	Maximum Head of Water Retained (m)
D-CP1	6.6	68.5	3.6
Berm-CP2	3.0	57.0	0
Berm-CP3	4.9	69.9	0
Berm-CP4	5.0	69.1	0
D-CP5	3.3	67.3	1.4
Berm-CP6	6.0	68.0	0
DP1-A	3.7	70.5	68.5
DP1-B	3.4	70.7	68.7
DP2-A	4.0	69.5	67.5
DP3-A	3.4	69.0	67
Berm1	2.6	69.0	0
Berm2	1.5	varies	0
Berm3	2.76	67.37	0

3.6.2.1 Thermal Monitoring

Horizontal Ground Temperature Cables (GTCs) are installed along the key trenches of D-CP1 and D-CP5 at a depth of approximately 3 m below the original ground level. These installations are in place to verify that the foundations remain frozen and dike integrity is not compromised. D-CP1 and D-CP5 also contain vertical GTCs installed to an approximate depth of 15 m below the crest of each dike. Thermal Berms CP2, CP3, CP4 and CP6 will similarly contain vertical GTSs installed to a minimum of 7 m below original ground elevation. Thermal records collected from these sensors provide temporal analysis of vertical temperature profiles to assess whether the structures are performing as designed.

D-CP1 and D-CP5 readings are obtained, recorded, and assessed weekly during open water season and monthly after freeze-up. Data loggers are set to record temperatures in the dikes every 12-hours. Reading frequency at the thermal berms is generally monthly during the first year following construction and quarterly thereafter. The measured readings are analyzed by an Agnico Eagle geotechnical engineer and are reported in the annual geotechnical inspection report.

In addition to thermal monitoring, visual geotechnical inspections of water management structures are currently performed, as described in Section 3.12 below.

3.7 Evaporators

In 2016, three evaporators were installed on jetties constructed at DP1-B. In 2018, two additional evaporators were similarly installed. Over 2016 to 2019, the evaporators were applied to reduce

volumes of water contained within the P-area through active evaporation. As groundwater inputs to the P-area have now ceased, the evaporators have not been operating throughout 2020. Operation of the evaporators will not resume in 2020 and are no longer considered a component of the site water management strategy. Nevertheless, Agnico Eagle will keep the five evaporators available if required.

3.8 Freshwater Intake

Freshwater usage at the Mine includes potable uses, fire suppression, make-up water for the mill, and other operational requirements, such as drilling water, dust suppression, paste backfill production, and use at the washbay. The main freshwater intake is located northeast of the industrial pad in Meliadine Lake, as shown on Figure 2. The intakes consist of vertical filtration wells fitted with vertical turbine pumps that supply water on demand. Both intake pipes are fitted with a screen of an appropriate mesh size to ensure that fish will not be entrained and shall withdraw water at a rate such that fish do not become impinged on the screen (NWB, 2016).

3.9 Water Treatment

Contact water will be treated (if necessary) to meet Licence requirements prior to being discharged to the environment. TSS mitigation techniques (i.e., attenuation ponds, silt screens, etc.), oil separation treatment, the STP, the SWTP, the SETP, the RO Plant, and the EWTP are used accordingly at various locations at the Mine prior to water being transferred to containment ponds and/or as effluent discharge to Meliadine Lake or Melvin Bay. Water quality criteria is discussed in Section 6 and Appendix E.

3.9.1 Freshwater Treatment Plant (WTP)

Freshwater from Meliadine Lake will be treated in the WTP before being directed to the camp areas for potable (domestic) water uses. The design flow rate for freshwater for the main camp and accommodations is 216 m³/day. In the WTP, freshwater will be pumped through cartridge filters, then pumped through ultraviolet units, and finally treated with sodium hypochlorite (chlorine). The treated water will be stored within a potable water tank. Potable water will be monitored according to the Nunavut Health Regulations for total and residual chlorine and microbiological parameters. Operation and maintenance details for the WTP can be reviewed in the Process and Control Narrative (H2O Innovation, 2016).

3.9.2 Sewage Treatment Plant (STP)

Wastewater from the accommodation complex and from satellite sewage tanks will be treated in the STP before being directed to CP1. Operation and maintenance details for the STP can be reviewed in the Operational & Maintenance Manual – Sewage Treatment Plant (Agnico Eagle, 2017b).

3.9.3 Saline Water Treatment Plant (SWTP)

The SWTP is used to treat saline water stored in the Underground Mine and Saline Ponds. The SWTP removes excessive total suspended solids (TSS), calcium chloride (CaCl_2), sodium chloride (NaCl), metals, phosphorous (P), and nitrogen compounds from the influent saline water. The influent and effluent from the SWTP are monitored every 12 hours (night shift and day shift) for pH and TDS, and bi-weekly for chloride (Cl), ammonia (NH_4), nitrite (NO_2), nitrate (NO_3), TDS, TSS, total phosphorus (P), total cyanide (Cn), total metals and total mercury (Hg).

Effluent from the SWTP is intended to be discharged to CP1. In February 2019, the discharge point was moved, temporarily directing effluent to CP5. Over the open water season of 2020, the discharge point will be reverted back to CP1.

The SWTP consists of two parallel units. Each unit can be operated to produce brine or solid by-product. In 2020, the SWTP will operate in solid-mode. Solid-mode of one unit within the SWTP is designed with an operational rate of $60 \text{ m}^3/\text{day}$ at an expected operational availability of 95%. Further specifications of the SWTP can be found within the SWTP Design Report (Agnico Eagle 2018) and the SWTP As-Built Report (Agnico Eagle 2019a).

EWTP effluent discharge to Meliadine Lake was performed in 2019 in accordance with the conditions outlined in Part F, Item 3 of the Water Licence. Discharge to Meliadine Lake, including the treated groundwater, will remain within the permitted discharge criteria defined in the License, be non-acutely lethal, and meet the Canadian federal end-of-pipe discharge criteria (per the amended MDMER; GC 2017). Additionally, SSWQOs for EWTP effluent (including treated groundwater) will be met at the edge of the mixing zone in Meliadine Lake. Further details regarding the EWTP are provided in Section 3.9.4 and Section 4.3.

SWTP effluent and CP1 water quality will continue to be monitored according to the SWTP Design Report to identify future exceedances and potential impacts to CP1.

Discussion on realized SWTP treatment rates over 2019 in relation to the groundwater management strategy can be found in the Groundwater Management Plan (Appendix A). Also, this plan provides an understanding of the long-term groundwater management strategy on site.

3.9.4 Effluent Water Treatment Plant (EWTP)

The purpose of the EWTP (Actiflo[®] model ACP-700R) is to reduce Total Suspended Solids (TSS) to a maximum concentration of 15 mg/L from the influent water pumped from CP1 prior to its discharge through the diffuser into Meliadine Lake. Throughout operation of the EWTP in 2018 and 2019, the maximum capacity (nominal flow) of the discharge system was $520 \text{ m}^3/\text{h}$. In Q2 2020, the system underwent upgrades to improve discharge capacity to $916 \text{ m}^3/\text{h}$, which is within the range of the predicted discharge rates to Meliadine Lake over the Life of Mine. Further information regarding

EWTP operation can be found in the EWTP As-Built (Tetra Tech 2018b). Forecasted monthly averages requiring treatment at the EWTP are provided in Table 13 and Appendix C.

Trigger limits are in place at the EWTP as a component of TSS and TDS exceedance mitigation during periods of discharge. These trigger limits are based on rating curves developed with simple linear regressions to predict TSS concentration as a function of turbidity and TDS as a function of specific conductivity. The regressions are developed with *in situ* specific conductivity and turbidity readings paired with corresponding MEL-14 sample lab results as a means to produce a relationship (rating curve) between field readings and corresponding lab results. Rating curves are then be applied to continuous *in situ* specific conductivity and turbidity readings taken from internal probes within the EWTP prior to discharge to approximate TDS and TSS, respectively.

Agnico will continue to gather calibration/confirmatory paired samples in the future to actively increase the number of data points and strengthen the turbidity-TSS and conductivity-TDS correlations. Thus, the rating curves used will be maintained internally and available for review upon request.

3.9.5 Saline Effluent Treatment Plant (SETP)

Prior to discharge of saline effluent to sea at Melvin Bay (Section 3.11; Appendix A), excess saline contact water stored on site is treated at the SETP for ammonia and total suspended solids. The main feed source to the SETP will be from the saline ponds (SP1 and SP4). Treated saline water will meet MDMER end-of-pipe discharge criteria. Initial treatment will include a clarification unit for TSS removal. Next, break-point chlorination treatment will be applied to remove elevated ammonia levels, which are inferred to be the result of the use of explosives and washing of development faces/muck underground. Excess free chlorine will be removed with activated carbon filters. Following treatment, saline water will be pumped to Saline Pond 3 (SP3) for final settling and storage. The SETP will be designed for 2020 to treat 1,600 m³/day of saline water for TSS and ammonia. Further information on the SETP design can be found in Agnico Eagle (2019b).

Prior to haulage of saline water from the Meliadine Site to Itivia for discharge to sea over the open water season, Agnico Eagle will measure pH, turbidity, specific conductivity, and temperature of the effluent as a means to continually advise discharge operations and help ensure discharge parameters are met. Samples will be analyzed for the full suite and Group 3 (MDMER) parameters as listed in the Water License and the Water Quality and Flow Monitoring Management Plan (Appendix E).

3.9.6 Oil Separators

An oil separation treatment system was installed in 2018 at the Maintenance Shop to collect and separate oil from water used for washing mining equipment. A second oil-water separator is installed at the Landfarm. The oil-water separator located at the Landfarm is used to treat both direct precipitation to the landfarm footprint and melt from snow containing hydrocarbons (i.e. snow on

which spills occur) that is stored in the landfarm and contaminated snow cell over winter (Section 3.4). Treated water is analyzed for BTEX, lead, and oil and grease prior to discharge to CP1 or used on the windrows to increase moisture content, as required. Water accumulating in the landfarm will not be discharged directly to the receiving environment.

3.10 Meliadine Lake Discharge Diffuser

The discharge diffuser is the final surface contact water effluent discharge location for the Mine. The overall purpose of the diffuser is to discharge water from CP1 (at sampling station MEL-14) to Meliadine Lake while providing minimal environmental impacts to the Lake. The effluent mixing will be dependent on ambient currents in Meliadine Lake, driven by wind during the open water period. The diffuser modelling was initially conducted by Golder Associates Ltd. (Golder, 2015) and updated design progress was reported by Tetra Tech EBA (Tetra Tech EBA, 2016).

3.11 Saline Water Discharge to Sea

Based on the current standing of saline water stored on site, the rate at which the SWTP can treat saline water (Section 3.9.3), and the forecasted inflows (Appendix A), it was anticipated that a second discharge location was required for long-term groundwater management. Following an application to the NIRB in 2018, Agnico Eagle received approval for discharge of saline water to a marine environment (Melvin Bay, Rankin Inlet) along with an amended Mine Project Certificate from the NIRB on February 26, 2019. Detailed information regarding treatment and discharge criteria are provided in the Groundwater Management Plan (Appendix A).

3.12 Water Management Structure Monitoring

Pursuant to Part E, Item 15 of the Licence, Agnico Eagle will carry out weekly inspections of all Water management structures during periods of flow and monthly thereafter. The records will be maintained for review upon request of an Inspector. More frequent inspections may be required at the request of an Inspector. Inspections will focus on structures and conditions in Sections 3.12.1 to 3.12.4 to follow. The associated inspection template can be found in Appendix G.

3.12.1 Culvert and Water Crossing Inspections

Culverts listed in Section 3.1, as well as culverts and water crossings along the AWAR, Bypass Road, and at the Itivia site will be inspected for the following conditions. These inspections also satisfy the monitoring procedures outlined in the Sediment and Erosion Management Plan (Appendix D):

- Damage to the inlet or outlet of the culvert which may impede flow capacity;
- Bed erosion upstream and downstream of watercourse crossing structures;
- Scour under bridge abutments and abutment foundations;

- Erosion along cutslopes and fillslopes of embankments (rill and gully erosion);
- Blockages within the culvert including snow, ice, debris; and
- Snow cover or snow piles which would prevent routing of water towards the inlet of the culvert (only applicable prior to freshet).

In the case that any of the above conditions are observed, corrective actions will be taken to optimize culvert/water crossing function and integrity.

3.12.2 Containment Pond Inspections

Water containment ponds discussed in Section 3.3 and P-Area containment ponds discussed in Section 3.4 will be inspected for the following conditions:

- Laboratory water quality results as a trigger to implement mitigation actions;
- Unplanned inputs via surface runoff which are not part of the water management system; and
- Water level elevation above the operating manual maximum (OMM).

In the case that any of the above conditions are observed, corrective actions will be taken to prevent unaccounted for losses of available water capacity or potential compromise to dike integrity.

3.12.3 Dike and Thermal Berm Inspections

Dikes and thermal berms discussed in Section 3.6.2 are inspected in order to track natural (expected) movement of the structure. Pertaining to dikes, a ‘master’ sketch of all the issues that were documented in the past is maintained as a means to spot any changes/new issues. Inspections focus on the upstream slope, the crest, the downstream slope, and downstream toe and observations include the following:

- New areas of movement/deterioration not previously documented;
- Changes to previously documented areas of movement/deterioration;
- Seepage through the downstream slope;
- Water presence in downstream channel/sump; and
- Areas of movement/deterioration of downstream channel/sump (where present).

Any issues or potential problems identified will be addressed accordingly by the Geotechnical Engineer in order to mitigate risks and maintain dike integrity.

3.12.4 Water Diversion Channel and Berm Inspections

In addition to the water management structures requiring inspections under the Water Licence, Agnico Eagle will carry out inspections of all channels on site listed within Section 3.6.1 and Table 1 for the following conditions:

- Obstructions to flow (ice, debris);
- Inflows not part of the water management system;
- Structural failure of channel banks;
- Seepage through water diversion berms resulting in water movement to areas not planned within the water management system; and
- Erosion of diversion berms (i.e., undercutting, slope failure).

In the case that any of the above conditions are observed, corrective actions as directed by the Geotechnical Engineer will be taken if there is potential for compromise effectiveness of the channel function or potential for unplanned impact to water quality or quantity in associated containment ponds.

SECTION 4 • WATER MANAGEMENT STRATEGY

There are three major sources of inflow water considered in the Mine water management system; freshwater pumped from Meliadine Lake, natural run off from precipitation and natural groundwater inflow to the Underground Mine.

A brief summary of the water management strategy for the Mine is presented as follows:

- Contact water from key mine infrastructure will be diverted and/or collected in the containment ponds (CP1, CP2, CP3, CP4, CP5, CP6, the Saline Ponds and the P-Area).
- The collected water in CP2 to CP6 will be pumped to CP1. Water collected in CP1 may be reused by the process plant and the excess water will be treated by the EWTP prior to discharge via the diffuser into Meliadine Lake.
- Contact water from the Underground Mine will be contained in underground sumps and the water storage stope and reused for mining operations. Excess water volumes will be stored in temporarily inactive underground developments, the Saline Ponds, treated by the SWTP to be transported to CP1, or will be treated at the SETP and discharged to Melvin Bay.
- Runoff water in the open pits will be collected in sumps and then pumped to the designated water containment ponds (CP5).
- Natural flooding of the open pits at end of mining will be supplemented by using freshwater from Meliadine Lake.
- Upon the completion of underground mining, the Underground Mine workings will be allowed to naturally flood by groundwater seepage.

Appendix B presents the Freshet Action Plan, which includes the Freshet Action Procedure and the Snow Management Procedure for the Mine. Table 9 summarizes the overall contact water management plan for the key infrastructure and presents the initial water collection locations and final water destinations. The plans for water management at key areas are described in the following sections.

Table 9: Overall Site Surface Contact Water Management Plan

Contact Water Source	Initial Contact Water Collection Location	Final Contact Water Collection Location
Industrial Site Pad Area (camp/process plant area)	CP1	CP1
WRSF1 Area	CP1, CP4 and CP5	
WRSF3 Area	CP2 and CP6	
Dry Stack TSF Area	CP1 and CP3	
Ore Stockpile OP2	CP1	
Landfill	CP1	
Landfarm (biopile)	Sump within Landfarm	To CP1 after oil separation
Tiriganiaq Pit 1 Tiriganiaq Pit 2	Open pit sumps	First to CP5 and then to CP1
Tiriganiaq underground	Sumps in underground mine	Sumps in underground mine, surface saline water storage ponds (saline ponds), SWTP to CP1 and/or discharge to sea

The following sections describe the strategy for water management at different areas for the Mine.

4.1 Key Water Management Activities

The activities required for the WMP are summarized in Table 10. Water management activities during closure are described in Section 7.

Table 10: Key Water Management Activities

Mine Year	Major Water Management Activities and Sequence
Q4 of Yr -5 (2015)	<ul style="list-style-type: none"> Started to re-use the underground water Dewatered top 0.5 to 1.0 m of fresh water in Pond H17 Constructed Channel 2
Yr -4 (2016)	<ul style="list-style-type: none"> Dewatered H17 into Meliadine Lake. Started construction of D-CP1 to impound CP1 Started construction of D-CP5 to impound CP5 Dewatered Pond A54 in Q3 of Year -4 and pumped the water to CP1 Constructed Saline Pond 1 (SP1) for additional underground saline water storage Constructed and operated P-Area Containment Ponds Started to store the excess groundwater from the underground mine at surface. Implemented and tested evaporators at P-Area to reduce water volumes stored at surface.

Mine Year	Major Water Management Activities and Sequence
	<ul style="list-style-type: none"> • Constructed trenches down gradient from DP1-B and DP3-A to be able to pump collected water and pump back to P1 and P3, respectively. • Constructed Channel 5 • Installed Culverts 3 and 4
Yr -3 (2017)	<ul style="list-style-type: none"> • Completed construction of D-CP1, jetty and Pumping station CP1 • Completed construction of D-CP5, jetty and Pumping station CP5 • Started construction Channel 1 • Constructed Berm 3 • Constructed freshwater intake in Meliadine Lake and installed pumping station • Constructed Lv75 water stope for additional underground saline water storage • Installed Culvert 13 • Started to treat sewage from Sewage Treatment Plant (STP) and pump the treated sewage from STP to CP1. • Started to pump the contact water from CP5 to CP1 for treatment (solids removal) • Started to pump water collected in trenches, down gradient from D-CP1, D-CP5, DP1 and DP3 to the associated containment pond • Started to pump the water from the Type A Landfarm to CP1 after oil/water separator treatment • Started to pump water from washbay to underground for storage until a biological treatment unit for hydrocarbon reduction/removal arrives at the site
Yr -2 (2018)	<ul style="list-style-type: none"> • Completed construction of Channel 1 • Started construction Channel 3, Berm CP3 and Pond CP3 • Installed Culverts 1, 2, 15 and 16 • Constructed Berm 2 • Started to pump the water from CP1 to EWTP for treatment prior to discharge via the diffuser to Meliadine Lake. • Pumped the solids sludge from EWTP to CP1. To limit recirculation of the sludge within CP1, the discharge of the sludge was located away from the EWTP intake. • Started diversion of the contact water from industrial pad to CP1 via Channel 1 • Constructed and commissioned (in Q4) SWTP to discharge to CP1.
Yr -1 (2019)	<ul style="list-style-type: none"> • Constructed Saline Pond 2 within footprint of Tiriganiaq Pit 2 and began storing excess saline water • Installed culverts 7, 8, 10, 11 and 20 • Constructed Channels 7 and 8 and Berm 1 • Completed construction of Channel 3, Berm CP3 and Pond CP3 and started to collect contact water • Constructed Channel 4, Pond CP4 and Berm CP4 and started to collect contact water • Start to pump the contact water in Ponds CP3 and CP4 to the partially drained Pond H13 where the water will flow through Channel 1 into CP1 • Constructed, commissioned and started discharge of saline water through the discharge to sea diffuser system • Partially dewatered Ponds H19 and H20 in Q3 of Year -1 by pumping water to the EWTP for discharge to Meliadine Lake • Started construction of Saline Pond 4 (SP4) within footprint of Tiriganiaq Pit 1

Mine Year	Major Water Management Activities and Sequence
Yr 1 (2020)	<ul style="list-style-type: none"> • Constructed Saline Pond 4 (SP4) • Constructed Pond CP6 and Berm CP6 • Transferred water from Saline Pond 2 to Saline Pond 4 • Start to pump contact water in CP6 to CP1 • Start to pump contact water collected in Tiriganiaq Pit 2 to CP5 • Assess feasibility of pumping EWTP sludge to process plant filter press to be added to TSF
Yr 2 (2021)	<ul style="list-style-type: none"> • Start to pump contact water collected in Tiriganiaq Pit 1 to CP5 • If feasible, begin pumping EWTP sludge to process plant filter press to be added to TSF
Yr 3 (2022)	<ul style="list-style-type: none"> • Stop pumping water from Tiriganiaq Pit 2 to CP5 when mined out • Tiriganiaq Pit 2 to serve as temporary saline water storage, if needed
Yr 4 (2023)	<ul style="list-style-type: none"> • Water management plan similar to Year 3
Yr 5 (2024)	<ul style="list-style-type: none"> • Water management plan similar to Year 3 • Construct Pond CP2 and Berm CP2 • Construct Channels 9 and 10
Yr 6 (2025)	<ul style="list-style-type: none"> • Water management plan similar to Year 3
Yr 7 (2026)	<ul style="list-style-type: none"> • Stop pumping water from Tiriganiaq Pit 1 to CP5 when mined out
Yr 8 (2027)	<ul style="list-style-type: none"> • Start to fill the mined-out Tiriganiaq Pits 1 and 2 with active pumping from Meliadine Lake • Stop pumping excess water from underground when underground mine is completed • Start natural flooding of Tiriganiaq Underground mine with groundwater seepage • Stop pumping water to process plant when the processing is completed

4.1.1 Pond Dewatering and Displacement

The initial dewatering at Lake H17 and Lake A54 was conducted in 2016 prior to constructing CP1 and CP5, respectively. The water from these ponds was pumped to Meliadine Lake through a temporarily installed diffuser.

Preparation for construction of CP4 facility required dewatering of the two shallow ponds B8 and B9 into CP1. Preparation for CP3 did not require dewatering as B28 contained insufficient volumes to dewater.

In Q3 2019, partial dewatering of Ponds H19 and H20 to the EWTP took place, following the advanced timeline for the construction of CP6 and WRSF3. Specifically, H19 was partially dewatered to facilitate construction of Berm-CP6, while H20 was partially dewatered to allow the placement of waste rock and overburden within the drained lake basin. Detailed information regarding the CP6 design and subsurface thermal analysis can be found in the CP6 and Berm Design Report (Tetra Tech, 2020).

Table 11 summarizes the pond dimensions, dewatering date, and estimated dewatered volumes.

Table 11: Estimated Pond Dewatering Schedule

Pond	B8	B9	H20	H19
Maximum Pond Water Depth (m)	-	1.4	1.6	1.4
Existing Pond Surface Area (ha)	-	0.63	9.58	2.91
Dewatering Schedule	Q4 2018	Q4 2018	Q3 2019	Q3 2019
Estimated Total Volume of Water Dewatered (m ³)	2,993	6,840	90,307	16,431

4.1.2 Underground Water Management

The Underground Mine will extend approximately 650 m below the ground surface and part of the underground workings will be operated below the base of continuous permafrost. The underground excavations act as a sink for groundwater flow during mining, with water induced to flow through the bedrock to the Underground Mine workings below the base of the permafrost.

The underground water management system is designed to prevent water from affecting the workings or production. The system contains a series of sumps (generally one at the access of each level) designed to capture groundwater inflows and runoff from mining operations (i.e., drilling), a clarification system, and a pumping system to redistribute the clarified water. Excess underground water is pumped to surface to be managed in the saline ponds. Temporarily inactive underground developments (similar to the water stope) are used for additional storage of excess underground water. Further details on the underground water management system is provided in Appendix A.

Beginning December 2018, the SWTP began treating groundwater to reduce stored saline water on site (See Section 3 for details). Furthermore, as part of the strategy to manage excess groundwater infiltration of saline water within the underground portion of the mine, Agnico Eagle received approval for marine discharge of saline water with the amended Project Certificate on February 26, 2019 (See Section 3.11 and Appendix A for details).

Combined (mine-wide) inflow values to the Underground Mine are currently estimated by manually measuring and summing all visible inflows across the mine. Recorded measurements are logged in a database from which daily estimated inflow rates can be produced.

Table 12 presents the predicted groundwater inflow rates estimated for passive groundwater inflow to the Underground Mine. Details pertaining to model inputs and assumptions are found in Appendix A. Values presented in Table 12 do not include grouting efforts or ventilation loss.

Table 12: Predicted Groundwater Inflow to the Underground Mine (2017 to 2032)

Year	Quarter	Predicted Groundwater Inflow (m ³ /day)
2020	Q1	410
2020	Q2	410
2020	Q3	420
2020	Q4	420
2021	Q1	420
2021	Q2	430
2021	Q3	440
2021	Q4	460
2022	Q12	480
2022	Q34	510
2023	-	530
2024	-	540
2025	-	580
2026	-	570
2027	-	530
2028	-	510
2029	-	490
2030	-	480
2031	-	470
2032	-	460
203	-	450

4.1.3 Water Management for Haul Road

A network of roads provide access to infrastructure at the Mine. The majority of the roadways servicing the mining area are located so that drainage is directed by berms, channels and culverts towards CP1, CP2, CP3, CP4, CP5, and CP6. As shown in Appendix C, water diverted to CP2, CP3, CP4, CP5 and CP6 will eventually be transferred to CP1. Detailed information about water management on roads is described in the Roads Management Plan (Agnico Eagle, 2019c).

4.1.4 Water Management for Landfarm and Landfill

Any water that accumulates at the onsite Landfarm is pumped through an oil/water separator prior to discharge into CP1. Additional details for Landfarm water management are described in the Landfarm Management Plan (Agnico Eagle, 2015a).

Leachate from the Landfill is anticipated to be non-hazardous and non-toxic due to the controls put in place on the materials accepted for deposition in the Landfill. Annual Landfill operations involves clearing of snow prior to spring melt. In the event there is leachate from the Landfill due to periods of

heavy rainfall or spring freshet, the runoff will be collected, controlled and treated, if necessary (Agnico Eagle, 2015b), and sent to CP1.

4.1.5 Water Management for Emulsion Plant Area

Freshwater is trucked to the emulsion plant and used for manufacturing emulsion as well as for washing vehicles. Water within the emulsion plant is re-used when feasible, and excess water is collected and disposed of on site (i.e., STP) or stored and shipped south as hazmat.

4.1.6 Water Management for the Wash Bay

Water used in the Wash Bay is re-used when feasible and excess water is recycled through a biological treatment system designed to reduce or remove hydrocarbons. Waste from the treatment process is removed in the form of solids and disposed of appropriately (Landfarm or hazmat).

4.2 Freshwater and Sewage Management

Additional freshwater usage and sewage management is described in the following sections.

4.2.1 Freshwater Management

Major freshwater usages on site include potable use, fire suppression, make-up water for the mill, and other operational needs, such as drilling and paste production for backfill. Freshwater is sourced from Meliadine Lake through a freshwater intake and pump system. For dust suppression, water is sourced from any ponded water located along the All Weather Access Road (AWAR) or small ponds proximal to the road.

Freshwater is pumped through an overland pipeline to an insulated main storage tank located at the plant site. Under the Licence, 318,000 m³/year of freshwater is permitted during operation phase. Additionally, approximately 4,000,000 m³ of freshwater is permitted per year to fill the mined-out open pits during the mine closure. These quantities are inclusive of water needs for dust suppression.

The design flow rate for the potable water for the main camp and accommodations (kitchen, laundry) is 136 m³ per day (based on a 680-person camp capacity and a nominal consumption of 200 L/day/person). There is an onsite Potable Water Treatment System (Section 3.9.1). Treated potable water is piped to areas in the service complex and other facilities requiring potable water.

4.2.2 Sewage Management

Sewage collected from the camp and MSB facilities is pumped to the STP. The objective of the STP is to treat sewage to an acceptable level for discharge to CP1 via a treated sewage water discharge pipeline. The STP is housed in a prefabricated (modular) structure, located at south-east of the service complex at the Industrial Pad, as shown in Figure 2. The sewage treatment system is designed based

on a flow rate of 200 L per day per worker for a peak load of 680 people, for an average daily flow rate of 136 m³ (5.67 m³/h).

The STP for the camp facilities is designed to meet appropriate guidelines for wastewater discharge (Agnico Eagle, 2017c). Details regarding STP specifications and operation can be found in the Operation & Maintenance Manual Sewage Treatment Plant (Agnico Eagle, 2017c).

4.2.3 Process Water Management

Process water is required in the mill for ore processing and is primarily sourced from Meliadine Lake through the freshwater intake system. However, contact water from CP1 is currently being evaluated for reclaim purposes in order to minimize the amount of freshwater use at the mill. The permitted freshwater usage value of 318,000 m³/d will be in sufficient to provide make-up water at the mill over life of mine. Agnico Eagle is currently investigating strategies to reclaim water (i.e., from CP1) and assessing mill water usage over life of mine. A Licence amendment to accommodate required mill water usage will be requested accordingly.

4.3 Meliadine Lake Diffuser Effluent Flow Rates

The EWTP is currently configured to discharge effluent to Meliadine Lake via a diffuser at a rate of 22,000 m³/day. This discharge rate was assessed in the initial design of the Meliadine Lake diffuser and falls within the acceptable range for capacity in the receiving environment. The pump does not operate continuously at the maximum rate. The amount of effluent requiring discharge over each month per year (Table 13) is based on the overall water balance for a mean climate year (Golder, 2020b).

As a component of the treatment process, approximately 2.6% of the treated volume is returned to CP1 as underflow sludge from the Actiflo[®] TSS removal unit. As a mitigation to water quality impacts at CP1 during closure, AEM is investigating EWTP sludge disposal options. Over 2020, the potential long-term EWTP sludge disposal option of TSF deposition will be assessed. This option would generally include further thickening of sludge from the Actiflo[®] unit via a Multflo[®] unit at the EWTP (Tetra Tech, 2017). This thickened sludge would then be transferred to the filter press at the mill to be filtered with tailings from the mill process and deposited within the TSF. Over 2020, assessments on operational requirements (i.e., piping, pumping) and sludge characteristics (i.e., particle size distribution, geochemistry) are planned. Information gathered will be applied to assess operational feasibility and potential geotechnical risks at the TSF.

Table 13 shows the estimated total volume of effluent released per month per year.

Table 13: Estimated Effluent Flow Rates over Mine Operating Life

Year	Effluent Released Over the Course of the Month under Mean Climate conditions (m ³)			
	June	July	August	September
1: 2020	330,000	413,012	51,331	8,361
2: 2021	199,726	302,927	50,228	81,626
3: 2022	201,115	275,162	45,487	76,444
4: 2023	191,532	281,612	47,622	78,770
5: 2024	195,151	316,826	53,041	88,116
6: 2025	213,039	317,767	54,251	89,354
7: 2026	215,346	326,998	56,087	91,190
8: 2027	219,018	317,767	48,201	81,999
9: 2028	206,520	317,767	48,201	81,999
10: 2029	-	-	-	-
11: 2030	-	-	-	-

SECTION 5 • WATER BALANCE

5.1 Global Water Balance

A water balance model was developed to assist in the evaluation of the water management infrastructure and estimation of the pumping requirements over the life of the Mine and under closure conditions. The model included a water balance conducted on both a monthly and yearly basis. The model focused specifically on contact water management infrastructure and areas that are affected by mining activities. The water balance was conducted for CP1, CP3, CP4, CP5, CP6, Tiriganiaq Pit 1, Tiriganiaq Pit 2, water in the underground mine operation, make-up water for the mill, water for the WTPs, and freshwater during mine construction period to mine closure under mean precipitation years. In 2020, an update to the water balance was carried out by Golder (2020b) in support of the Water License Amendment application, including the incorporation of CP2. The water balance framework, assumptions, inputs, and results of the updated water balance model are presented in Appendix C.

5.2 Waterbody Inventory

Table 14 presents the three watersheds (Watershed A, Watershed B and Watershed H) and various waterbodies that are impacted by the Mine activities. Watersheds and waterbodies in proximity to the Mine location and waterbodies affected by Mine infrastructure are shown on Figure 5.

Table 14: Inventory of Waterbodies Impacted by Mining Activities

Watershed	Waterbody	Maximum Lake Water Depth, m	Total Area (ha)	Water Volume (m ³)	Notes
A	A9	N/A	0.18	-	Flow regimes impacted by the development of Tiriganiaq Pit 1
	A10	0.67	0.26	-	Ponds removed by development of Tiriganiaq Pit 1
	A11	0.45	0.40	-	
	A12	0.87	0.47	-	Pond drained due to construction of Channel 5
	A13	0.30	0.26	-	
	A17	0.30	0.16	-	Covered by WRSF 1
	A38	N/A	0.05	-	Flow regimes impacted by the development of Tiriganiaq Pit 2
	A39	0.48	0.12	-	Ponds removed by development of Tiriganiaq Pit 2
	A54	1.3	5.99	34,545	Dewatered for CP5
	A58	0.50	0.43	-	Covered by Laydown Area
B	B8	0.8	1.43	-	As part of CP4/Berm-CP4
	B9	1.40	0.64	-	Dewatered for CP4
	B10	0.8	0.33	-	Ponds removed by development of Tiriganiaq Pit 1
	B28	N/A	0.45	-	As part of CP3/D-CP3
H	H6	0.58	0.75	-	As part of CP1
	H7	0.67	0.11	-	
	H8	0.59	0.38	-	Partially covered by Laydown area and haul road
	H9	0.40	0.42	-	Partially covered by OP2
	H10	0.11	0.10	-	Partially covered by OP2, drained due to construction of Channel1
	H11	0.27	0.28	-	
	H12	0.81	0.97	-	Drained due to construction of Channel1 and partially covered by OP2
	H13	1.04	3.49	-	Drained due to construction of Channel1 and partially covered by industrial pad
	H14A	0.37	0.15	-	Covered by industrial pad
	H15D	0.30	0.15	-	Partially covered by TSF
	H15G	0.40	0.38	-	
	H17	1.70	15.8	195,700	Dewatered for CP1
	H17A	1.50	0.13	1,365	Dewatered for Meliadine esker
	H17B	1.50	0.69	10,350	Dewatered for Meliadine esker
	H17C	1.50	0.23	3,450	Dewatered for Meliadine esker
H18	0.67	0.74	-	Covered by OP2	
H19	1.40	2.91	16,431	Dewatered for CP6	
H20	1.60	9.58	90,307	Covered by WRSF3	
“-” indicates that data not available or not applicable Ponds to be drained Ponds to be dewatered					

SECTION 6 • WATER QUALITY

Water quality monitoring is an important part of the Water Management Plan to verify the predicted water quality trends, conduct adaptive management should differing trends be observed, and to ensure all water quality limits at discharge points are met (i.e., effluent to Meliadine Lake and Melvin Bay). Water quality results and water transfers (i.e., origin, destination, rate) at the Mine are monitored and documented pursuant the Licence.

Water quality monitoring was initiated at the pre-development stage, continued through construction into operations, and will continue into closure and post-closure. Monitoring occurs at three levels:

1. Regulated discharge monitoring that occurs at monitoring points specified in the Licence or MDMER regulations.
2. Verification monitoring that is undertaken for operational and water management purposes by Agnico Eagle.
3. General monitoring that is commonly included in the Licence, specifying what is to be monitored according to a schedule. This monitoring is subject to compliance assessment to confirm sampling was carried out using established protocols, included quality assurance/quality control provisions, and addressing identified issues. General monitoring is subject to change as directed by an Inspector, or by the Licensee, subject to approval by the NWB.

With the exception of sampling specific to the WQ-MOP (Golder, 2020a), Appendix E details the Water Quality and Flow Monitoring Plan. Figure 6 and Figure 7 depict Monitoring Program Stations on Site and at Itivia.

6.1 Summary of Regulatory Guidelines

Water quality results are compared to MDMER criteria and effluent quality limits listed in the Licence. Water quality pertaining to MEL-14 will be compliant to Part F, Item 3 of the Licence prior to discharging to Meliadine Lake. All surface runoff and/or discharge from drainage management systems associated with the Mine, including laydown areas and All-Weather Access Road, where flow may directly or indirectly enter a Water body, shall not exceed the Effluent quality limits listed in Part D, Item 18 of the Licence. Furthermore, all waters from natural water body dewatering activities shall be directed to Meliadine Lake and shall not exceed the Effluent quality limits listed in Part D, Item 12.

Post-closure discharge water quality will be compared to Canadian Council of Ministers of the Environment Water Quality Guidelines (CCME-WQG) guidelines or the Meliadine SSWQO developed for aluminum, fluoride, and iron (Golder 2013a, 2013b, 2014). The Meliadine SSWQO criteria was developed as a conservative protection to the aquatic receiving environment and was developed by Golder (2013a, 2014) to assess whether waste rock consisted of a deleterious substance according to

Environment Canada (2013). The outcome of the assessment was that Meliadine waste rock is not a deleterious substance (Environment Canada 2014).

6.2 Water Quality Monitoring - Licence Amendment No. 1

As a component of Amendment No. 1 to the Water License, additional regulated discharge monitoring is being carried out in 2020, as described in the Water Quality Management and Optimization Plan (WQ-MOP; Golder 2020a). The purpose of the WQ-MOP sampling program is both to assess conditions experienced in Meliadine Lake during the 2020 discharge event and for the application as a science-based framework to support the determination of acceptable effluent quality conditions (EQCs) and Site-Specific Water Quality Objectives (SSWQOs). Further information regarding the WQ-MOP, including specifics of the sampling program and application of monitoring data, as well as adaptive management measures related to Amendment 1 can be found in Golder (2020a).

6.3 Water Quality Modelling and Forecasts

Water quality predictions for the Mine were generated using the GoldSim database management and simulations code (Version 11.1.2) where Mine contact water flows derived from the Meliadine water balance were combined with chemistry data from materials exposed in mine infrastructure (tailings storage facility, waste rock piles, etc.), and site baseline information. Water quality estimates were generated for the operational and post-closure periods for effluent to Meliadine Lake, each contact water containment pond (CP1, CP3, CP4, CP5, and CP6), for sumps in the two open pits and for the two fully flooded open pit lakes post-closure. These results and further details pertaining to this model were submitted with the 2015 WMP (Agnico Eagle, 2015e).

In 2020, an update of the water quality model was carried out in support of the Water License Amendment application, including the incorporation of CP2. The model framework, inputs, assumptions, and results of the updated water quality model are presented in Appendix C. Assuming no further iterations are required, this version of the water quality model will also be submitted with the 2021 Annual Report as per Part E Item 12 of the Water License.

6.4 Post-Closure

As provided in the 2014 FEIS water quality model provided in Agnico Eagle (2015e), long-term, post-closure water quality in the containment ponds (CP1, CP3, CP4, CP5, and CP6) and in the flooded open pit lakes are anticipated to meet MDMER limits and CCME-WQG for the protection of aquatic life or the SSWQO developed for the Mine for aluminum, fluoride, and iron. Arsenic concentrations in CP3 could slightly exceed the SSWQO post-closure, a criterion that is conservatively protective of the receiving aquatic environment (Golder, 2013a). If arsenic levels exceed post-closure SSWQOs then water arsenic treatment will be implemented accordingly until arsenic levels decrease below the SSWQO concentration.

SECTION 7 • WATER MANAGEMENT DURING CLOSURE

The detailed Mine closure and reclamation activities are provided in the Interim Closure and Reclamation Plan (SNC-Lavalin, 2020). Water management during closure and reclamation will involve flooding the open pits using precipitation and freshwater from Meliadine Lake, flooding the Underground Mine workings with groundwater inflows (groundwater seepage), and maintaining contact water management systems on site until monitoring results demonstrate that water quality are acceptable for discharge of all contact water to the environment without further treatment. Once water quality meets the discharge criteria, the water management systems will be decommissioned to allow the water to naturally flow to the environment.

The key water management activities during Mine closure are summarized in Table 15. Figures 8 and 9 illustrate the WMP during and after Mine closure, respectively. Additional details for the activities are described in the following sections.

Table 15: Key Water Management Activities during Mine Closure

Mine Year	Figure	Key Water Management Activities and Sequence
Yr 9 to 11 (2028 to 2030)	8	<ul style="list-style-type: none"> • Finish flooding the mined-out Tiriganiaq Pit 1 and Tiriganiaq Pit 2 by Q4 of Year 10 • Continue to collect and manage the contact water in CP1, CP2, CP3, CP4, CP5 and CP6 • Continue to pump the contact water in CP1 to EWTP, if required, for treatment before being discharged to the outside environment • Remove non-essential site infrastructure • Pump the underflow sludge water from EWTP to CP1 • Continue natural flooding of Tiriganiaq Underground Mine with groundwater seepage • Remove Meliadine Lake pumping system
Post-Closure	9	<ul style="list-style-type: none"> • Treat the contact water until water quality meet direct discharge criteria and then decommission the water management system • Continue natural flooding of Tiriganiaq Underground (progressive reclamation since Year 8) • Breach water retention dikes D-CP1, D-CP5, and thermal berms CP2, CP3, CP4, and CP6 once water quality monitoring results meet discharge criteria to allow water to naturally flow to outside environment • Remove culverts and breach remaining water retention berms in Year 18 (pending the demonstration of acceptable water quality)

7.1 Open Pits Flooding

When flooding the open pits for closure, the maximum pumping rate from Meliadine Lake shall not exceed 4,000,000 m³/year during closure of the Mine, as stated in Part E Item 2 of the Licence. The planned pumping period will occur during the open water season from mid-June to end of September for each year. Table 17 summarizes the pit volume and expected water elevations at the completion

of flooding activities. It will take approximately three years to fill the pits with an assumed pumping rate of 0.44 m³/s (38,300 m³/day). The assumed pumping rate of 0.44 m³/s from Meliadine Lake during closure will have negligible effect to Meliadine Lake when compared to the average outflow rate at the outlet of Meliadine Lake. The pumping rate will be evaluated further to validate that any possible negative effects to Meliadine Lake do not occur.

Table 16: Pit and Underground Flooding

Pit	Volume (Mm ³)	Final Water Elevation (masl)	Water Source
Tiriganiaq Pit 1	9.20	64.14	Freshwater from Meliadine Lake
Tiriganiaq Pit 2	2.25	64.38	Freshwater from Meliadine Lake
Tiriganiaq Underground	1.4	Groundwater level	Groundwater seepage

The water quality model results indicated that water quality in the flooded pits will meet the discharge criteria and post closure treatment will not be required. The water quality within the pits will be monitored during flooding to verify the prediction of the water quality model. The information will be used to develop a strategy to minimize contamination of the regional surface water system.

7.2 Underground Mine Flooding

Passive flooding of the Tiriganiaq Underground Mine will occur following the completion of mining. The estimated total flooding volume of the underground workings is 1,372,000 m³. Seepage water into the Underground Mine will be the main water source for flooding. At the predicted seepage rate it is estimated to take 6 years to flood the Underground Mine.

7.3 Containment Ponds, Dikes and Berms

The containment ponds, dikes and berms will remain in place to collect the surface runoff water and seepage from the Mine until the water quality meets discharge criteria. Once the water quality meets discharge criteria, dikes/berms will be breached to allow runoff to follow natural (topographically induced) flow paths. Dikes/berms breaching will involve the removal of a portion of the dikes to a minimum depth of 1 m below average water level or back to original ground levels. Consideration will be given to breach staging, with the above water portions of the dike/berm in the breach area removed during winter periods, when there will be little surface water flow, thereby minimizing the potential release of sediments to the neighbouring waterbodies. The remainder of the breach would be conducted during the open water season following freshet. Turbidity curtains would be deployed to minimize any potential sediment release to surface water.

7.4 Channels and Sumps

Once monitoring results have indicated that contact water conveyed in channels and sumps meets acceptable water quality, the infrastructure will be graded and/or surface treated according to site-specific conditions to minimize wind-blown dust and erosion from surface runoff, if required. This closure activity is intended to enhance site area development for re-colonization by native plants and wildlife habitat.

REFERENCES

- Agnico Eagle. 2015a. Meliadine Gold Project: Mine Plan. Version 1. 6513-MPS-10. April 2015.
- Agnico Eagle. 2015b. Meliadine God Project: Landfarm Management Plan. Version 1. 6513-MPS-15. April 2015.
- Agnico Eagle. 2015c. Meliadine Gold Project: Landfill and Waste Management Plan. Version 4. 6513-MPS-06 April 2015.
- Agnico Eagle. 2015d. Meliadine Gold Project: Preliminary Closure and Reclamation Plan. Version 1.0. 6513-CRP-01. April 2015.
- Agnico Eagle. 2015e. Meliadine Gold Project: Water Management Plan. Version 1. 6513-MPS-11. April 2015.
- Agnico Eagle. 2017a. Final Spill Report, Tank Release April 8, 2017. June 2017.
- Agnico Eagle. 2017b. Meliadine Gold Project. Operational & Maintenance Manual – Sewage Treatment Plant – Version 2, February 2017.
- Agnico Eagle. 2018. Design Report, Saline Water Treatment Plant. Document number: 6515-E-132-013-105-REP-035, August 2018.
- Agnico Eagle. 2019a. As Built Report, Saline Water Treatment Plant (SWTP), July 2019.
- Agnico Eagle. 2019b. Design Report, Saline Effluent Treatment Plant (SETP). Document number: 6528-680-132-REP-003, Rev. 01, May 2019.
- Agnico Eagle. 2019c. Meliadine Gold Project. Roads Management Plan. Version 8. 6513-MPS-03. December 2019.
- Agnico Eagle. 2019d. Meliadine Gold Project: Water Management Plan. Version 5. 6513-MPS-11. January 2019.
- Environment Canada. 2013. Guidelines for the Assessment of Alternatives for Mine Waste Disposal. Ottawa, ON, Canada. June 2013.
- Environment Canada. 2014. Electronic mail communication from Environment Canada to Agnico Eagle. Subject: Assessment of Meliadine Waste Rock. May 6, 2014.
- Golder (Golder Associated Ltd.). 2009. Assess of completeness of geotechnical data for feasibility design Tiriganiaq open pit. Submitted to Comaplex Minerals Corp., 26 May 2009, Doc. 008 Rev. 0

- Golder. 2012a. SD 7-2 Aquatic Baseline Studies- Meliadine Gold Project, Nunavut, Canada. A Technical Report Submitted to Agnico Eagle Mines Ltd. by Golder Associates, September 19, 2012.
- Golder. 2012b. SD 6-1 Permafrost Thermal Regime Baseline Studies- Meliadine Gold Project, Nunavut, Canada. A Technical Report Submitted to Agnico Eagle Mines Ltd. by Golder Associates, September 25, 2012.
- Golder. 2012c. Tailings Storage Facility Preliminary Design – Meliadine Gold Project, Nunavut. A Draft Report Submitted to Agnico Eagle Mines Ltd. by Golder, August 16, 2012. INAC, 1992. Guidelines for ARD Prediction in the North. Department of Indian Affairs and Northern Development, Northern Mine Environment Neutral Drainage Studies No.1, Prepared by Steffen, Robertson and Kirsten (B.C.) Inc.
- Golder. 2013a. Site specific Water Quality Objectives (SSWQO) Assessment – Meliadine Gold Project, Nunavut. Document 371. Report to Agnico-Eagle Mines Ltd. February 22, 2013. 57 p.
- Golder. 2013b. Appendix 7.2-B, Hydrogeological Modelling, Meliadine Gold Project, Nunavut. Technical Report Submitted to Agnico Eagle Mines Ltd. Reference No. Doc 335-101370076, Jan. 16, 2013.
- Golder. 2014. Assessment of Site Specific Exposure and Toxicity Modifying Factors on Aluminum Toxicity and Validation of Non-Deleterious Nature of All Parameters of Potential Concern in Waste Rock Leachate – Meliadine Gold Project, Nunavut. Document 440. 2014. Report to Agnico-Eagle Mines Ltd. March 14, 2014. 7 p.
- Golder. 2015. Meliadine Gold Project. Appendix E: Near-Field Modelling and Diffuser Design. Report Number: Doc 493-1405283 Ver. 0. March 2015.
- Golder. 2020a. Meliadine Gold Project. Water Quality Management and Optimization Plan (WQ-MOP) Progress Update: Phase 3 - Finalize Meliadine Mine Effluent Discharge Benchmarks for TDS. 19132390-751-RPT-Rev3. August, 2020.
- Golder. 2020b. Meliadine Gold Project. Meliadine Site Water Balance and Water Quality Model. Type A 2AM-MEL1631 Water Licence Amendment. 20144940-779-RPT-Rev1. August, 2020.
- Government of Canada. 2020. Metal and Diamond Mining Effluent Regulations. SOR/2002-222; current to February 26, 2020.
- H2O Innovation. 2016. Process and Control Narrative: Meliadine WTP. P65873-I13-0001, 01. July 25, 2016.
- Nunavut Impact Review Board (NIRB). 2019. NIRB Meliadine Gold Mine Project Certificate [NO.: 006] Amendment. February 26, 2019.

- Nunavut Water Board (NWB). 2016. Type A Water Licence: No: 2AM-MEL1631. April 1, 2016.
- SNC Lavalin Inc., 2020, Meliadine Interim Closure and Reclamation Plan – Update 2020, Final report.
- Snowden. 2008. Tiriganiaq gold deposit, Nunavut – resource update. Submitted to Comaplex Minerals Corp. January 2008.
- Tetra Tech EBA. 2014. Tailings, Waste and Water Management for Feasibility Level Study, Meliadine Project, Nunavut. File: E14103188-01. December 2014.
- Tetra Tech EBA. 2015. Summary of Water Balance Key Assumptions and Results, Meliadine Gold Project. Technical Memorandum Submitted to Agnico Eagle Mines Ltd. by Tetra Tech EBA, October 2015.
- Tetra Tech EBA. 2016. Meliadine Lake Diffuser Design Progress Report for Discussion. September 20, 2016. File: E14103230-01 Task 007.
- Tetra Tech. 2017. Construction Summary Report for EWTP, Pumping Stations, Pipelines and Diffuser. September 2018. 6515-E-132-005-132-REP-014.
- Tetra Tech. 2018a. Design Report for CP3, CP4, CP Berms, Berm2, Channel3, and Channel4, Meliadine Project, Nunavut. June 2018. File: ENG.EARC03076-02, Document number: 6526-695-100-REP-001.
- Tetra Tech. 2018b. Construction Summary (As-Built) Report Effluent Water Treatment Plant, Pumping Stations, Pipelines, And Diffuser, Meliadine Gold Project, NU. September 2018. Project number: 28920, Document number: 6515-E-132-007-132-REP-014.
- Tetra Tech. 2020a. Design Report for CP6 and CP6 Berm, Meliadine Project, Nunavut. January 24, 2020. File: ENG.EARC03140-06, Document number: 6526-695-100-REP-001.
- Tetra Tech. 2020b. Technical memo for prefeasibility level design of WRSF3 with extended footprint and associated water management infrastructure. June 2020. File: 704-ENG.EARC3206-01. July 2020.

FIGURES

Figure 1 : General Mine Site Location Plan




Figure 2: General Mine Site Plan Layout




Figure 3: P-Area Plan View




Figure 4: Location and design of Saline Pond 4 (SP4) within Tiriganiaq Pit 1




Figure 5: Watersheds and Waterbodies in Proximity of Mine Site




Figure 6: Water Quality Monitoring Locations on Site




Figure 7: Water Quality Monitoring Locations at Itivia



Note – MEL-12 is located to the Northwest along the Bypass road but could not be effectively included in this map due to its distance from Itivia.

Figure 8: Mine Site Layout for Water Management During Closure from Feasibility Level Study (TetraTech, 2014).





Figure 9: Mine Site Layout After Closure from Feasibility Level Study. (TetraTech, 2014).



APPENDIX A • MELIADINE GROUNDWATER MANAGEMENT PLAN



AGNICO EAGLE

MELIADINE GOLD MINE

Groundwater Management Plan

APRIL 2020
VERSION 5

EXECUTIVE SUMMARY

This document presents the Groundwater Management Plan (GWMP) for the collection, treatment, storage and discharge of saline groundwater in accordance with Agnico Eagle's Type A Water Licence 2AM-MEL1631, Part E, Item 14.

The Groundwater Management Strategy is composed of short-, medium- and long-term management strategies. Presently most of the short-term management strategies have been implemented on site and Agnico Eagle is currently working on increasing the trucking discharge to sea flow rate to 1,600 m³/day in collaboration with NIRB and NWB. The next step will be to evaluate the construction of the waterline from the site to the Melvin Bay in order to increase the discharge rate, recover storage capacity on site and improve the robustness of the groundwater water management.

Agnico Eagle Mines Limited (Agnico Eagle) is developing the Meliadine Gold Mine (the Mine), located approximately 25 kilometres (km) north of Rankin Inlet, and 80 km southwest of Chesterfield Inlet in the Kivalliq Region of Nunavut.

The Mine Plan proposes mining methods for the development of the Tiriganiaq gold deposit, with two open pits (Tiriganiaq Pit 1 and Tiriganiaq Pit 2) and one Underground Mine. Based on the current Mine Plan, the Mine will produce approximately 15.4 million tonnes (Mt) of ore, 31.4 Mt of waste rock, 7.0 Mt of overburden waste, and 15.4 Mt of tailings. There are four phases to the development of the Mine; just over 3.5 years of construction (2015 to 2019), 8.5 years of Mine operation (Q2 of 2019 to 2027), 3 years of closure (2028 to 2030), and post-closure (2030 and forwards).

Tiriganiaq Underground Mine is planned to extend to approximately 625 m below the ground surface; therefore, part of the Underground Mine will operate below the base of the continuous permafrost. The underground excavations will act as a sink for groundwater flow during operation, with water induced to flow through the bedrock to the Underground Mine workings once the Mine has advanced below the base of the permafrost. Currently, groundwater inflow mitigations are being carried out, including grouting efforts and avoiding mining areas expected to produce high inflow rates. The range of mitigated groundwater inflow rates to the Underground Mine over 2019 was reported to be up to 394 m³/day. Non-contact groundwater quality data from samples taken over 2017 - 2019 from diamond drillholes (DDHs) show a mean TDS concentration of 56,000 mg/L.

Saline water generated from the Underground Mine is currently stored in underground sumps and in non-active development, as well as on surface in the saline ponds. A second containment pond, Saline Pond 2 (SP2), was commissioned in Q2 2019, however will be decommissioned and replaced by Saline Pond 4 (SP4) in March 2020. Saline groundwater stored on site is currently pumped to the Saline Water Treatment Plant (SWTP) for desalination treatment, or treated at the Saline Effluent Treatment Plant (SETP) for discharge to sea at Melvin Bay as per the Nunavut Impact Review Board (NIRB) Project Certification 006 Amendment 001, issued in February 2019. Over 2019, SWTP performance did not

achieve design criteria and availability was less than expected. Thus, resulting in a greater than predicted accumulation of saline water inventory on site.

SECTION 4 • GROUNDWATER MONITORING PROGRAM 26

4.1 Water Quality and Quantity Monitoring26

 4.1.1 Water Quantity26

 4.1.2 Water Quality26

REFERENCES 29

Appendix A • Site location and Mine Site Layout 29

Appendix B • Underground Water Management Flow Sheet Diagram 32

Appendix C • Groundwater quality sampling results 2017 - 2019 32

LIST OF TABLES

Table 1: Predicted Groundwater Inflow to Underground Mine (2019 to 2032) 17

Table 2: Salt Water Storage Capacity at the Mine for Groundwater and Water Primarily Influenced by Underground Workings 20

Table 3: High Level Mine Schedule 25

Table 4: Groundwater Monitoring Plan 27

DOCUMENT CONTROL

Version	Date	Section	Page	Revision	Author
1	February 2018	All		In compliance with Agnico Eagle's Type A Water Licence 2AM-MEL1631, Part E, Item 14	Golder Associates Ltd. on behalf of Agnico Eagle Mines Limited
2	June 2018	4		In compliance with ECCC comments from 16 March 2018	Golder Associates Ltd. on behalf of Agnico Eagle Mines Limited
3.	December 2018	All		In compliance with Agnico Eagle's Type A Water Licence 2AM-MEL1631, Part E, Item 11	Agnico Eagle Mines Ltd.
		Exec Summary		Updated dates and quantities	
		2.4		Revised mine development plan bullets	
		3.3		Updated saline GW quality	
		3.4		Updated groundwater management	
		4.1		strategies	
		4.4		Updated GW monitoring program quantity and quality data	
				Expanded table 5 monitoring to include SWTP	
4.	March 2019	All		In compliance with Agnico Eagle's amended No. 006 Project Certificate, Condition No. 25	Agnico Eagle Mines Ltd.
		Exec Summary		Updated to include discharge to sea approval	
		1	1-2	Update to include requirements of No. 006 Project Certificate Condition No. 25	
		2.4	5	Addition of SWTP and discharge to sea	
		3.1	6-7	Section revision	
		3.1.1	7-8	Addition of inflow model assumptions/uncertainties	
		3.2	8-9	Updated with discharge to sea	
		3.3	9-10	Interpretation added and table Aug-18 results corrected	
		3.4	11-15	Addition of discharge to sea and update of SWTP performance	
		3.6	16-18	Addition of mitigation measures under greater than expected inflows	
		4.2	19	Addition of second pumping line from UG	
		4.3	21-23	Addition of discharge to sea related sampling/monitoring	
5.	March 2020	All		In compliance with Agnico Eagle's amended No. 006 Project Certificate, Condition No. 25	Agnico Eagle Mines Ltd.

Exec Summary		General update to reflect updated Plan
2.4	15	Update high level mine plan, schedule, addition of SETP and RO
3.1	16-17	General section update, and updated groundwater inflow rates included
3.2	18-19	Updated saline water control structures
3.3	19-20	General section update/revision; moved water quality table to Appendix C
3.4	20-24	Section update to reflect changes to saline water management strategy
3.5	24	Section revision/update to include SP4, timeline details
3.6	-	Former Section 3.6 was updated and moved into other sections
4.1	25-27	General section revision/update, QAQC portion moved to Water Quality and Flow Monitoring Plan and can be found in QAQC plan

ACRONYMS

Agnico Eagle	Agnico Eagle Mines Limited
ANFO	Ammonium Nitrate/Fuel Oil
CP	Collection Pond
DDH	Diamond Drillhole(s)
EMPP	Environment Management and Protection Plan
EWTP	Effluent Water Treatment Plant
FEIS	Final Environmental Impact Statement
GWMP	Groundwater Management Plan
MDMER	Metal and Diamond Mining Effluent Regulations
NIRB	Nunavut Impact Review Board
NWB	Nunavut Water Board
Mine	Meliadine Gold Mine
QA	Quality Assurance
QC	Quality Control
RO	Reverse Osmosis
SD	Support Document
SSWQO	Site Specific Water Quality Objectives
SWTP	Saltwater Treatment Plant
TDS	Total Dissolved Solids
TSS	Total Suspended Solids
WMP	Water Management Plan

UNITS

%	percent
°C	degrees Celsius
°C/m	degrees Celsius per metre
ha	hectare(s)
mg/L	milligram(s) per litre
km	kilometer(s)
km ²	kilo square meter(s)
m	metre(s)
m/day	metre(s) per day
mm	millimetre(s)
m ³	cubic metre(s)
m ³ /day	cubic metre(s) per day
m ³ /s	cubic metre(s) per second
m ³ /hour	cubic metre(s) per hour
m ³ /year	cubic metre(s) per year
Mm ³ /year	million cubic metre(s) per year
Mm ³	million cubic metre(s)
t	tonne(s)
tpd	tonne(s) per day
Mt	million tonne(s)

SECTION 1 • INTRODUCTION

Agnico Eagle Mines Limited (Agnico Eagle) is developing the Meliadine Gold Mine (Mine), located approximately 25 kilometres (km) north of Rankin Inlet, and 80 km southwest of Chesterfield Inlet in the Kivalliq Region of Nunavut. The Mine is subject to the terms and conditions of both the Mine Project Certificate (No. 006) issued by the Nunavut Impact Review Board in accordance with the Nunavut Agreement Article 12.5.12 on February 26, 2015 and Nunavut Water Board Type A Water Licence (No. 2AM-MEL1631, 2016) issued by the Nunavut Water Board (NWB) on April 1, 2016.

This document presents the Groundwater Management Plan (GWMP) for the collection, treatment, storage and discharge of saline groundwater in accordance with the Type A Water Licence 2AM-MEL1631 (Licence) and in accordance with Condition No. 25 of the amended Mine Project Certificate. The overall water management plan for the life of the Mine and post-closure is described in the Agnico Eagle Meliadine Gold Mine Water Management Plan (WMP).

1.1 Objectives

The objective of the GWMP is to provide consolidated information on groundwater management for the Meliadine Gold Mine. The GWMP is divided into the following components:

- Introductory section (Section 1);
- A brief summary of the physical setting at the mine site and the mine development plan (Section 2);
- A description of groundwater inflow forecasts and management strategies (Section 3); and
- A description of the groundwater monitoring program (Section 4).

The GWMP will be updated as required to reflect any changes in operations or economic feasibility that occurs, and to incorporate new information and latest technology, where appropriate.

SECTION 2 • BACKGROUND

2.1 Site Conditions

The Mine is located in an area of poorly drained lowlands near the northwest coast of Hudson Bay. The dominant terrain in the Mine area consists of glacial landforms such as drumlins (glacial till), eskers (gravel and sand), and many small lakes. The topography is gently rolling with a mean elevation of 65 metres above sea level (masl) and a maximum relief of 20 metres (m).

The local overburden consists of a thin layer of topsoil overlying silty gravelly sand glacial till. Cobbles and boulders are present throughout the region at various depths. Bedrock at the mine site area consists of a stratigraphic sequence of clastic sediments, oxide iron formation, siltstones, graphitic argillite and mafic volcanic flows (Snowden 2008; Golder 2009).

The climate is extreme in the area, with long cold winters and short cool summers, and mean air temperatures of 12 °C in July and -31 °C in January. The mean annual air temperature at the Mine site is approximately -10.4 °C (Golder 2012a). Strong winds blow from the north and north-northwest direction more than 30 percent of the time.

The mean annual precipitation in the area is approximately 412 mm and is typically equally split between rainfall and snowfall.

Late-winter ice thicknesses on freshwater lakes in the mine site area were recorded from 1998 to 2000. The measured data indicated that ice thickness ranges from 1.0 to 2.3 m with an average thickness of 1.7 m. Ice covers usually appear by the end of October and are completely formed in early November. The spring ice melt typically begins in mid-June and is complete by early July (Golder 2012b).

2.2 Local Hydrology

The Mine is located within the Meliadine Lake watershed. Meliadine Lake has a surface water area of approximately 107 square kilometres (km²), a maximum length of 31 km, features a highly convoluted shoreline of 465 km and has over 200 islands. Unlike most lakes, it has two outflows that drain into Hudson Bay through two separate river systems. It has a drainage area of 560 km² from its two outflows. Most drainage occurs via the Meliadine River, which originates at the southwest end of the lake. The Meliadine River flows for a total stream distance of 39 km. The Meliadine River flows through a series of waterbodies, until it reaches Little Meliadine Lake and then continues into Hudson Bay. A second, smaller outflow from the west basin of Meliadine Lake drains into Peter Lake, which discharges into Hudson Bay through the Diana River system (a stream distance of 70 km). At its mouth, the Diana River has a drainage area of 1,460 km².

Watersheds in the Mine area are comprised of an extensive network of waterbodies, and interconnecting streams. The hydrology of these watersheds is dominated by lake storage and evaporation.

2.3 Hydrogeology

The Mine is located in an area of continuous permafrost. Based on thermal studies and measurements of ground temperatures, the depth of permafrost at the mine site is estimated to be in the order of 360 to 495 m. The depth of the active layer ranges from about 1 m in areas with shallow overburden, up to about 3 m adjacent to the lakes. The depth of the permafrost and active layer varies depending on proximity to the lakes, overburden thickness, vegetation, climate conditions, and slope direction (Golder 2012b). The typical permafrost ground temperatures at the depths of zero annual amplitude are in the range of -5.0 to -7.5 °C in the areas away from lakes and streams. The geothermal gradient ranges from 0.012 to 0.02 °C/m (Golder 2012c).

Groundwater characteristics at the Mine are detailed in Final Environmental Impact Statement (FEIS) Volume 7, Section 7.2 Hydrogeology and Groundwater, and in a hydrogeological assessment completed for the Mine (Golder 2016). The groundwater characteristics for the Mine are briefly summarized below.

Two groundwater flow regimes in areas of continuous permafrost are generally present:

- a deep groundwater flow regime beneath the base of the permafrost; and
- a shallow flow regime located in an active (seasonally thawed) layer near the ground surface.

From late spring to early autumn, when temperatures are above 0 °C, the active layer thaws. Within the active layer, the water table is expected to be a subdued replica of topography, and is expected to parallel the topographic surface. Mine area groundwater in the active layer flows to local depressions and ponds that drain to larger lakes.

Taliks exist beneath waterbodies that have sufficient depth such that they do not freeze to the bottom over the winter. Beneath small waterbodies that do not freeze to the bottom over the winter, a talik bulb that is not connected to the deep groundwater flow regime will form (a closed talik). Elongated waterbodies with terraces (where the depth is within the range of winter ice thickness), a central pool(s) (where the depth is greater than the range of winter ice thickness), and a width of 340 to 460 m or greater are expected to have open taliks extending to the deep groundwater flow regime at the Mine site. A review of bathymetric data, ice thickness data, and results of thermal modelling suggests that Meliadine Lake and Lake B7 are likely to have open taliks connected to the deep groundwater flow regime (Golder 2012a).

Tiriganiaq Underground Mine is planned to extend to approximately 625 m below the ground surface; therefore, part of the underground mine will be operated below the base of the frozen permafrost (top of the cryopeg). The underground excavations will act as a sink for groundwater flow during

operation, with water induced to flow through the bedrock to the underground mine workings once the mine has advanced below the base of the frozen permafrost.

Both Tiriganiaq Pit 1 and Tiriganiaq Pit 2 will be mined within the frozen permafrost, therefore, groundwater inflows to the open pits is expected to be negligible.

2.4 Mine Development Plan

The Mine Plan proposes mining methods for the development of the Tiriganiaq gold deposit, with two open pits (Tiriganiaq Pit 1 and Tiriganiaq Pit 2) and one Underground Mine. The current mine plan applies the following approach for the development of the Tiriganiaq gold deposit:

- Tiriganiaq Underground Mine will be developed and operated from Year -5 to Year 8 (2015 to 2027);
- Tiriganiaq Pit 1 will be mined from Year 2 to Year 7 (2021 to 2026); and
- Tiriganiaq Pit 2 will be mined from Year 1 to Year 3 (2020-2022).

Mine facilities on surface include a plant site and accommodation buildings, two ore stockpiles, a temporary overburden stockpile, a tailings storage facility, three waste rock storage facilities, a water management system that includes containment ponds, water diversion channels, retention dikes/berms, a final Effluent Water Treatment Plant (EWTP), a Saline Water Treatment Plant (SWTP), a Reverse Osmosis Plant (RO), and a Saline Effluent Treatment Plant (SETP). Details on each treatment plant can be found in the WMP.

SECTION 3 • GROUNDWATER MANAGEMENT STRATEGY

3.1 Groundwater Volumes

In the WMP of the water licence application (Agnico Eagle 2015a) it was stated that supplemental hydrogeological investigations were to be undertaken to provide additional information on potential volumes and quality of the saline groundwater to be managed. These investigations were undertaken in 2015 and 2016 and are summarized in Golder (2016). They included the completion of twenty-four packer tests, two pumping tests, two injection tests, eleven groundwater samples, and seven surface water samples. The work plan for the fieldwork was developed in consultation with two independent technical advisors, Dr. Shaun K. Frape and Dr. Walter A. Illman (both of the University of Waterloo).

The additional hydraulic conductivity measurements resulted in a refined interpretation on the variability of hydraulic conductivity between geological formations and data on the storage properties of the bedrock. Furthermore, piezometer data records and diamond drillhole (DDH) water intersect data was applied to re-calibrate the model in 2019. A summary of predicted groundwater inflows between 2019 and 2033, based on this refined interpretation and re-calibration, are provided in Table 1.

Table 1: Predicted Groundwater Inflow to Underground Mine (2020 to 2032)

Year	Quarter	Predicted Groundwater Inflow (m ³ /day)
2019	Q1	380
2019	Q2	400
2019	Q3	430
2019	Q4	420
2020	Q1	410
2020	Q2	410
2020	Q3	420
2020	Q4	420
2021	Q1	420
2021	Q2	430
2021	Q3	440
2021	Q4	460
2022	Q12	480
2022	Q34	510
2023	-	530
2024	-	540
2025	-	580
2026	-	570

2027	-	530
2028	-	510
2029	-	490
2030	-	480
2031	-	470
2032	-	460
2033	-	450

Predicted groundwater inflow rates provided in Table 1 represent unmitigated inflow forecasts; not accounting for inflow mitigations currently being conducted to reduce groundwater inflows to the underground development. Over 2019, inflow mitigation included both grouting (pre-production and in response to inflows) and avoiding mining in areas expected to produce high groundwater inflow rates. As such, the magnitude of inflow forecasts in Table 1 were not sustained throughout 2019, but were rather periodically approached and mitigated.

Combined (mine-wide) groundwater inflow values to the Underground Mine are currently estimated by manually measuring and summing all visible inflows across the mine (Section 4). The mitigated inflows over 2019 was measured up to 394 m³/day. It is important to note that as mining advances, inflow rates are susceptible to rapid and sustained increase if water bearing structures are intercepted within stopes, where grouting is not possible. As such, and as noted above, mining in areas known to contain highly-pressurized, large-scale water bearing structures is currently being avoided due to limited capacity to manage forecasted inflow rates. The long-term groundwater management strategy (Section 3.4.3) will aim to provide capacity to manage non-mitigated inflows over the life of mine.

3.1.1 Groundwater Inflow Predictions – Assumptions and Uncertainties

Hydraulic conductivities of both the Hanging Wall and Footwall units are assumed to be reduced by an order of magnitude between the top of the basal cryopeg and the bottom of the cryopeg. This assumption reflects that this portion of the permafrost, which will contain unfrozen groundwater due to freezing point depression (salinity and pressure induced), is expected to have reduced hydraulic conductivity relative to the unfrozen bedrock because of the presence of isolated pockets of frozen groundwater within this zone. Linearly decreasing hydraulic conductivity with temperature is assumed within this zone, with a full order of magnitude decrease assumed at the top of the basal cryopeg, and hydraulic conductivity equivalent to the unfrozen rock at the bottom of the cryopeg.

In crystalline rocks, fault zones may act as groundwater flow conduits, barriers, or a combination of the two in different regions of the fault depending on the direction of groundwater flow and the fault zone architecture. These zones, termed Enhanced Permeability Zones (EPZs), were assigned hydraulic conductivity values based on both field measurements and testing conducted at similar faulting in various locations within the Canadian Shield. Furthermore, EPZs were assumed not to be impacted by isolated freezing in the cryopeg and were therefore assigned similar hydraulic conductivity values

within and below the cryopeg. The latter assumption along with the assumption that all faults are considered EPZs is considered conservative. For instance, observations made at other gold mines in the Canadian Shield indicate not all faults are EPZs (Golder, 2016).

Based on the geometry of water bodies, it was assumed that Lake B7, Lake D7, and Meliadine Lake possess open taliks connected to the deep groundwater flow regime. It was conservatively assumed that the surface water/groundwater interaction through open taliks is not impeded by lower-permeability lakebed sediments that may exist.

Combined, the assumptions discussed above result in the following sources of uncertainty in the groundwater inflow model:

1. If there is a lack of reduction in hydraulic conductivity between the top of the basal cryopeg and the bottom of the cryopeg, it is likely that greater than expected inflows upon stoping will occur in the cryopeg (300 to 450 m below ground surface).
2. If faults within the model do not act as EPZs, then it is expected that inflows resulting from development near these structures will be less than expected. The degree of deviation from expected inflows and timing will be dependent on the location of the structure in relation to development.
3. If hydraulic conductivity of faults within the cryopeg are impacted by isolated freezing, then lower than expected inflows will be observed when development in the cryopeg progresses near the structures. The degree of deviation from expected inflows and timing will be dependent on the location of impacted EPZs in relation to development.
4. If significant thicknesses of lakebed sediments with relatively low permeability exist within in the flow path connecting surface water to groundwater through open taliks, it is likely that mine-wide inflows will be less than expected due to a reduction in expected recharge to the groundwater flow regime.

3.2 Existing Groundwater Management Control Structures

Contact water in the Underground Mine is contained within underground sumps, in non-active development underground, and in the surface saline ponds. Over 2019 this included Saline Pond 1 (SP1) and Saline Pond 2 (SP2). Saline Pond 3 (SP3) acts as a temporary final storage pond where the SETP effluent is stored prior to discharge to sea. As discussed in the WMP, SP2 will be replaced by Saline Pond 4 (SP4) in March 2020. A proportion of the underground water is recirculated as make-up water for underground drilling. The remaining underground water is stored for desalination treatment by the SWTP (Section 3.4.2), or treatment by the SETP for discharge to sea. Over 2020, excess underground contact water stored in non-active development will be transferred to SP4 to allow advancement of the current mine plan.

In previous years (2016 – 2018) saline water was directed to and stored in the P-Area containment ponds (P1, P2, and P3) for evaporation. In 2019, inputs to the P-Area were limited in an effort to begin

the decommissioning process of the containment structures. In 2020, saline water inputs to the P-Area are not planned and the only planned inputs will be the result of precipitation runoff; in order to facilitate the decommissioning of the P-Area in 2020.

Calcium chloride is currently not added to the underground water but has been used in the past to prevent freezing in drill holes when drilling in permafrost with low salinity drill water.

A schematic of the underground dewatering system is provided in Appendix B. Pond capacities for storage of saline water are presented in Table 2.

Table 2: Salt Water Storage Capacity at the Mine for Groundwater and Water Primarily Influenced by Underground Workings

Surface Pond	Capacity (m ³)	Occupied storage capacity (m ³)
Saline Pond 1	32,686	27,227
Saline Pond 2*	78,862*	76,000
Saline Pond 3	7,895	Emptied for winter
Saline Pond 4	233,122**	121,689†
P1	20,781	3,158§
P2	6,828	237§
P3	2,912***	1,821§

Source: Agnico Eagle (2017).

* SP2 to be decommissioning in March 2020 (Section 3.2). Volume stored in SP2 will be transferred to SP4 (Section 3.4.1)

** Based on Design, subject to change based on As-Built

*** Adjusted for volume reduction due to Saline Pond 3 construction (Water Management Plan Section 3.4)

† Accounting for emptying of SP2 and underground storage to SP4 (Section 3.4.1)

§ No saline water additions to P-Area planned for 2020 to support potential decommissioning of P-Area (Section 3.4.1)

Based on forecasted groundwater inflow rates (Table 1) and groundwater management strategies currently in place (Sections 3.4.1 and 3.4.2), it is expected that saline pond storage shown in Table 2 (excluding P-Area ponds) will be at capacity by mid-May 2021. Further information is provided in Section 3.4.2.

3.3 Groundwater Quality

Historically, groundwater investigations suggested that total dissolved solids (TDS) concentrations are relatively consistent below the permafrost at approximately 64,000 mg/L (Golder 2016). Groundwater quality samples have been collected from 2017 through 2019 from diamond drillholes (DDHs) intersecting water bearing structures (Section 4). Results from the 146 samples collected from 2017 to 2019 indicate stable and consistent concentrations for several parameters (Appendix C) and indicate that TDS concentrations are less than predicted at a mean concentration of 56,000 mg/L. The

discrepancy between expected and observed TDS levels is potentially due to the difference of sampling depth between pre-development testing and samples collected during development. Pre-development samples were collected below permafrost (>450 m below ground surface), whereas the bulk of samples collected to-date have been collected in the basal cryopeg (280 m to 450 m below ground surface). Samples and trends will continue to be assessed as development progresses below the cryopeg. It should also be noted that mining operations include drill-and-blast excavation for the development of the Underground Mine, which results in certain parameters in groundwater to be influenced by explosives (particularly ammonia and nitrate).

3.4 Groundwater Management Strategy and Associated Control Structures

Based on the groundwater inflow volume, the following options were considered and form part of the short-, medium- and long-term management of groundwater inflows to the Underground Mine:

- Short-term Strategy: Store saline contact water on site (Section 3.4.1)
- Medium-term Strategy: Treat saline groundwater for discharge to receiving environment in Meliadine Lake and Melvin Bay via trucking (Section 3.4.2)
- Long-term Strategy: Treat saline groundwater for discharge to receiving environment in Melvin Bay via waterline (Section 3.4.3).

The short-, medium- and long-term groundwater management strategies are described below.

3.4.1 Short-Term Management Strategy - Groundwater On-site Storage

This alternative was considered as part of the Type A Water Licence Application and has been implemented on site as part of the short-term management of groundwater inflow. It involves storing all excess groundwater in an underground water stope and in dedicated surface saline water ponds at the Mine. As outlined in the WMP, a total of twelve water containment ponds are planned on Site at the Mine surface. These are CP1, CP3, CP4, CP5, CP6, the P-Area (P1, P2, and P3), SP1, SP2 (to be replaced by SP4 in 2020), SP3 and SP4). Ten of these have been constructed and are in use (CP1, CP3, CP4, CP5, P-Area [P1, P2, and P3], SP1, SP2, and SP3). SP2 is scheduled for decommissioning in Q2 2020 to allow the mining of Tiriganiaq Pit 2. SP2 is to be replaced by SP4, which is scheduled to be commissioned in March of 2020. The addition of SP4 has two purposes. First, to replace SP2 and allow the mining of Tiriganiaq Pit 2, and second, to supply additional storage for saline water on site. The additional storage is required due to continued groundwater infiltration to the underground workings and finite existing surface storage capacity. In March of 2020 following the completion of SP4, water contained within SP2 and water currently stored in development underground will be transferred to SP4. SP2 will be decommissioned following this transfer of water. Further information on storage ponds is included in the WMP.

Five saltwater evaporators have been in-use on site since mid-2017 at P1 to reduce saline groundwater volumes stored in surface water ponds. While evaporators have been used with some

success, realized groundwater inflows to be managed is greater than the available long-term storage at the Mine, and therefore, discharge to environment has been required and was initiated in 2019 (Section 3.4.2). No additional saline water inputs were made to the P-Area throughout 2019. All subsequent inflows to the P-Area were primarily the result of direct precipitation and surface run-off from up-gradient areas. Throughout 2020, inputs to the P-Area will continue to be kept minimal to facilitate the potential for decommissioning of the P-Area in 2020.

3.4.1.1 Short-Term Mitigation Measures – Increased Storage and Treatment Rate

Upon the occurrence of greater than expected groundwater inflows to the underground mine, Agnico Eagle will utilize contingency saline water storage ponds until inflows can be reduced or treatment/discharge is capable of managing inflows.

As of March 2020, the commissioning of SP4 (and decommissioning of SP2) will introduce an additional 155,000 m³ of saline water storage on surface. Under the condition that SP4 reaches capacity due to higher than expected inflows, the mine plan as it relates to open pits, can be adapted to provide additional storage (for example mining Tiriganiaq Pit 2 can be stopped to accommodate saline water storage needs and SP4 water can be transferred so that mining of Tiriganiaq Pit 1 is made possible). Furthermore, additional adaptive management measures with regards to saline water at Meliadine are being explored.

It will be the goal of Agnico Eagle to reduce the amount of saline water stored in SP1, SP4 and underground as much as possible during the open water season through discharge to sea in order to maximize storage potential.

3.4.2 Medium-Term Management Strategy

3.4.2.1 Saltwater Treatment Plant (SWTP) - Desalination

Agnico Eagle has constructed and commissioned a Salt Water Treatment Plant (SWTP) consisting of two evaporator crystallizers (SaltMakers) used to treat groundwater. The SWTP removes excessive total suspended solids (TSS), calcium chloride (CaCl₂), sodium chloride (NaCl), metals, phosphorous (P), and nitrogen compounds from the influent saline water.

The SWTP consists of two parallel units. Each unit can be operated to produce brine or solid by-product. The SWTP will operate in solid-mode over the duration of 2020 however at a reduced capacity due to design challenges. Further specifications of the SWTP can be found within the SWTP Design Report (Agnico Eagle 2018) and the SWTP As-Built Report (Agnico Eagle 2019a).

Following the commissioning of the SWTP in solid-mode over 2019, the actual operational rate has been less than design. Over Q3 and Q4 of 2019, the combined treatment rate of the two Saltmaker units (120 m³/day design total) was reported at 46.5 m³/day. Furthermore, availability has been much lower than expected over this same period. As a result, over Q3 and Q4 over 2019, the SWTP treated a calculated total of 6,045 m³ (compared to a design calculated total of 20,862 m³).

SWTP effluent is currently discharged to CP5, which is then transferred to CP1 and subsequently discharged to the receiving environment in Meliadine Lake. EWTP effluent discharge to Meliadine Lake was performed in 2019 in accordance with the conditions outlined in Part F, Item 3 of the Water Licence. Discharge to Meliadine Lake, including the treated groundwater, will remain within the permitted discharge criteria defined in the License, be non-acutely lethal, and meet the Canadian federal end-of-pipe discharge criteria (per the amended MDMER; GC 2019). Additionally, SSWQOs for EWTP effluent (including treated groundwater) will be met at the edge of the mixing zone in Meliadine Lake. Further details regarding the EWTP are provided in Sections 3.9.4 and Section 4.3 of the WMP.

3.4.2.2 Saline Effluent Treatment, Storage and Haulage

The site will be increasing the trucking and volumes of discharge at Melvin Bay. The increased trucking was included in the Roads Management Plan (Agnico Eagle, 2019b). The increased volume for discharge to Melvin Bay will be elevated from 800 m³/day to 1600 m³/day.

Saline water will be pumped from underground and stored in SP1 and SP4. Saline water will then be transported to the Saline Effluent Treatment Plant (SETP) for treatment of ammonia and total suspended solids (TSS). Treated saline water will meet MDMER end-of-pipe discharge criteria and be non-acutely and non-chronically toxic as per regulated toxicity testing per the MDMER. Initial treatment will include TSS removal. Next, breakpoint chlorination treatment will be applied to remove elevated ammonia levels, which are inferred to be the result of the use of explosives. Excess free chlorine will be removed with activated carbon filters. Following the activated carbon filters, saline water will be pumped to Saline Pond 3 (SP3) for final settling and storage. The SETP will be designed to treat 1,600 m³/day of saline water for TSS and ammonia.

Treated saline water stored in SP3 will hauled by tanker trucks to Itivia. Truck loads will be up to 36 m³ per truck and will be unloaded using a flexible 4" HDPE suction pipe. The truck discharge pump will transfer the treated effluent into the 6" discharge HDPE pipeline and through the diffuser. The truck discharge pump will also be used to transfer effluent into the storage tank until the next day before it is pumped into sea, when necessary. Further information on trucking can be found in the Roads Management Plan (Agnico Eagle 2019b).

Based on forecasted groundwater inflow values provided in Table 1 and the medium-term strategy described here, it is expected that saline water storage capacity (Table 2) will be at capacity by mid-May 2021. Thus, short- and medium-term strategies described in this section are not sustainable. This assessment does not incorporate SWTP application due to unreliability of the treatment plant.

3.4.2.3 Pumping and Diffusion Plan 2020

The flow rate to be discharged to Melvin Bay will not exceed 1,600 m³/day with a TDS of 39,600 mg/L. The discharge facility includes a 778 m pipeline extending to an engineered diffuser located 20 m below surface in Melvin Bay to ensure proper mixing and prevent interference with traditional activities. Pumping will occur during the summer season (June to October) of 2020 and following years

until the long-term strategy is approved and constructed. The saline effluent will be discharged in a controlled manner through the diffuser to allow for maximum diffusion and minimum environmental impact to the marine environment. Environmental monitoring is discussed in the Ocean Discharge Monitoring Plan (Agnico Eagle, 2020).

The effluent discharge system will consist of a discharge pump, a 50,000 L storage tank, as well as suction and discharge pipelines. The 50,000 L storage tank will only be used to contain the treated effluent until the next day, if the 1,600 m³/day discharge limit is attained upon a truck's arrival. The storage tank is installed on a containment area, built on a geomembrane with underlying and overlying granular materials and surrounded by berms.

3.4.2.4 Medium-Term Mitigation Measures – Groundwater Monitoring

Hydraulic Monitoring

As a strategy to support groundwater inflow modelling and monitor groundwater responses to mining, twelve (12) vibrating wire piezometers are currently installed in the rock mass surrounding the Underground Mine. These piezometers are currently and will continue to be applied to assess response of the groundwater pressure (pressure head) to groundwater inflows, and as calibration data for the groundwater inflow model (Section 3.1).

Furthermore, a hydrogeological investigation is currently ongoing as a means to provide additional calibration data/information for the hydrogeological model. The purpose of this data collection is both to increase the understanding of local hydrogeology and to reduce uncertainty of groundwater modelling. The hydrogeological investigation is being carried out over 10 – 15 DDHs and includes: core logging of water bearing structures; hydrogeological testing to characterize aquifer and fracture hydrogeological properties; and installing up to 20 vibrating wire piezometers. The investigation is expected to be completed by end of Q2 2020.

Groundwater Quantity and Quality Monitoring

The groundwater monitoring program (Section 4) allows ongoing comparison of modelled water quantity/quality to realized trends. Details pertaining to the groundwater monitoring program are found in Section 4.

Non-contact groundwater samples as part of the groundwater monitoring program are used to identify trends and improve predictions regarding groundwater inflow chemistry. If non-contact groundwater samples collected indicate that TDS concentrations are more than 20% higher than the estimated 64,000 mg/L (Section 3.3), then water quality predictions for underground will be reviewed and updated, if required.

Similarly, observed groundwater inflow rates are compared to model predictions (Table 1) on a yearly basis. If significant variations from model predictions are observed, the assumptions/inputs behind the model will be reviewed and the model updated, if required. In addition, updates to the

groundwater model may be required based on operational changes as the Underground Mine advances.

3.4.3 Long-Term Management Strategy - Treated Groundwater Discharge to Melvin Bay at Itivia Harbour via a Waterline

Based on the current inventory of saline water stored on site (Table 2), plus current and forecasted groundwater inflows (Section 3.1), the proposed long-term strategy of discharging to Melvin Bay via a waterline will be required to ensure we meet all obligations. The long term strategy will be submitted to the appropriate authorities in Q1 2020.

3.5 Discharge Schedule - 2020

The following Table summarizes the 2020 discharge schedule.

Table 3: High Level Mine Water Management Schedule - 2020

Activity	Timeline	Notes
On-site water storage	Ongoing	SP4 replacing SP2 in March 2020
Discharge saline water to the sea (Melvin Bay, Rankin Inlet)	Annually June through October	Typically open water initiates discharge to Melvin Bay
Active Discharge to Meliadine lake	Annually May through October;	—
Operation of Salt Water Treatment Plant	24 hr. a day / 7 days a week, year round	In-service as required
Inactive Discharge	Annually November through May	Water will be stored underground and in surface containment ponds during the winter until the long-term strategy is implemented

SECTION 4 • GROUNDWATER MONITORING PROGRAM

4.1 Water Quality and Quantity Monitoring

Water quantity and quality monitoring is an important part of the groundwater management strategy to verify the predicted water quantity and quality trends and conduct adaptive management should differing trends be observed.

Groundwater monitoring is carried out for operational and water management purposes by Agnico Eagle. This monitoring data will not be reported to the Regulators in the Annual Water License Report, but can be provided upon request by the Regulators.

The groundwater monitoring plan, summarized in Table 4, will be further defined as the Mine advances and will be conducted in agreement with the WMP for the Mine (Agnico Eagle 2019c).

4.1.1 Water Quantity

Combined (mine-wide) groundwater inflow rates to the Underground Mine are currently estimated by manually measuring and summing all visible inflows across the mine. Recorded measurements are logged in a database from which daily estimated inflow rates can be produced. The database is updated accordingly as flow rates at existing inflow locations change (i.e., grouted) and as new inflows are observed. Thus, the database is maintained to represent the current state of mine-wide groundwater infiltration. Groundwater inflow rates are compared to modelled rates (Table 1) on a quarterly basis (Section 3.4.2.3).

Excess underground water volumes transferred from the Underground Mine to storage ponds on surface (SP1 and SP4) are recorded at a flow meter located after the main pumping station from underground to surface. Furthermore, water volumes in SP1 and SP4 are tracked via water elevation surveys applied to volume-elevation curves. Further details pertaining to the underground water management system can be found in Appendix C.

4.1.2 Water Quality

Underground Contact Water

Underground contact water is sampled on a monthly basis at the locations identified in Table 4. All underground contact water sampling locations are analyzed for the following parameters: conventional parameters (specific conductivity, TDS, TSS, pH, hardness, alkalinity, total and dissolved organic carbon, turbidity), oil and grease, major ions, total and free cyanide, radium 226, dissolved and total metals (including mercury), nutrients (nitrate and nitrite, ammonia, Kjeldahl nitrogen, total phosphorus, orthophosphate) and volatile organic compounds (i.e., benzene, xylene, ethylene toluene, F2-F4 petroleum hydrocarbons). The Sump 125 sampling location (sampled 2016 – 2019) will be replaced by the Level 300 sampling location in 2020 due to reconfiguration of the underground water management system (Appendix C).

Non-contact Groundwater

Non-contact groundwater quality is monitored at mine seeps and/or DDH water intersects to verify the quality of formation water flowing into the mine prior to contact. Flushing and sampling techniques used to ensure samples are taken without contamination are described in Section 2.2.3 of the Quality Assurance/Quality Control Plan (Agnico Eagle, 2019d). Samples are collected quarterly at a minimum but actual sampling frequency may be greater depending on rate of progress, frequency of water intersects, and observed trends in groundwater quality with time. DDH intersect water samples are analyzed for the following parameters: conventional parameters (specific conductivity, TDS, TSS, pH, hardness, alkalinity, total and dissolved organic carbon, turbidity), major ions, nutrients (nitrate and nitrite, ammonia, Kjeldahl nitrogen, total phosphorus, orthophosphate), radium 226, dissolved and total metals (including mercury). Results from DDH water intersect sampling over 2017 – 2019 can be found in Appendix D.

Saline Water Treatment Plant (SWTP) Influent and Effluent

Water samples at the SWTP are currently collected every two weeks at both the inlet and outlet of the SWTP. The results of the sample analysis are used by SWTP operators to fine-tune the treatment process and ensure its optimal performance. Samples taken at the outlet of the SWTP are analyzed to provide the quality of treated water produced by the SWTP that is transferred to CP5.

Water samples are analyzed for the following parameters: conventional parameters (pH, hardness, TDS, TSS), chloride, sulphate, nutrients (nitrite and nitrate, ammonia, total phosphorus), total metals (including mercury), total and free cyanide, oil and grease and volatile organic compounds (F2-F4 petroleum hydrocarbons)..

Table 4 presents a summary of the groundwater monitoring plan presented in Section 4.1.

Table 4: Groundwater Monitoring Plan

Monitoring Type	Monitoring Location	Purpose	Frequency
Verification	Underground Seeps	Quantity - Seepage survey to verify underground inflow rates	Updated daily
Verification	SP1 and SP4	Quality – Monitor quality of surface saline storage ponds	Monthly

Monitoring Type	Monitoring Location	Purpose	Frequency
Verification	Level 300 pre-clarification	Quality – Monitor quality of collective saline contact water underground prior to clarification	Monthly
Verification	Underground seeps/DDHs	Quality – Verify quality of groundwater flowing into underground mine	Quarterly
Verification	SWTP Inlet and Outlet	Quality – Monitor quality of saline contact water being pumped from underground and monitor final treated effluent prior to continued transfer to CP5	Every two weeks


Source: Agnico Eagle (2018).

REFERENCES

- Agnico Eagle. 2014. Final Environmental Impact Statement (FEIS) - Meliadine Gold Project, Nunavut from: <ftp://ftp.nirb.ca/02-REVIEWS/ACTIVE%20REVIEWS/11MN034-AgnicoEagle%20MELIADINE/2-REVIEW/09-FINAL%20EIS/FEIS> Accessed on November, 2014.
- Agnico Eagle. 2015a. Meliadine Gold Project, Type A Water Licence. Water Management Plan. Version 1. Submitted to the Nunavut Water Board. April 2015.
- Agnico Eagle. 2015b. Meliadine Gold Project: Environmental Management and Protection Plan (EMPP). Version 4. 6513-MPS-07. April 2015.
- Agnico Eagle. 2018. Meliadine Gold Project: Design Report Saline Water Treatment Plant. 6515-E-132-013-105-REP-035. August 2018.
- Agnico Eagle. 2019a. Meliadine Gold Project: As Built Report Saline Water Treatment Plant. July 2019.
- Agnico Eagle. 2019b. Meliadine Gold Project Roads Management Plan. Version 8. 6513-MPS-03. December 2019.
- Agnico Eagle. 2019c. Meliadine Gold Project Water Management Plan. Version 8. 6513-MPS-11. November 2019.
- Agnico Eagle. 2019d. Meliadine Gold Project Quality Assurance / Quality Control Plan. Version 3. 6513-QQY-01. March 2019.
- Agnico Eagle. 2020. Ocean Discharge Monitoring Plan. Version 3 - NIRB. April 2020.
- CCME (Canadian Council of Ministers of the Environment). 2003. Canadian Environmental Quality Guidelines – Water Quality Guidelines for the Protection of Aquatic Life.
- Environment Canada. 1992. Biological test method: fertilization assay with echinoids (sea urchins and sand dollars). Ottawa (ON): Environmental Technology Centre. Report EPS 1/RM/27, December 1992, Amended in November 1997.
- ECCC (Environment Canada and Climate Change). 2018. Biological test method: reference method for determining acute lethality using threespine stickleback. Method Development and Applications Unit, Science and Technology Branch, Environment and Climate Change Canada. EPS 1/RM/10. 2018.
- Golder (Golder Associated Ltd.). 2009. Assess of completeness of geotechnical data for feasibility design Tiriganiaq open pit. Submitted to Comaplex Minerals Corp., 26 May 2009, Doc. 008 Rev. 0

- Golder. 2012a. SD 7-2 Aquatic Baseline Studies- Meliadine Gold Project, Nunavut, Canada. A Technical Report Submitted to Agnico Eagle Mines Ltd. by Golder Associates, September 19, 2012.
- Golder. 2012b. SD 6-1 Permafrost Thermal Regime Baseline Studies- Meliadine Gold Project, Nunavut, Canada. A Technical Report Submitted to Agnico Eagle Mines Ltd. by Golder Associates, September 25, 2012.
- Golder. 2012c. Tailings Storage Facility Preliminary Design – Meliadine Gold Project, Nunavut. A Draft Report Submitted to Agnico Eagle Mines Ltd. by Golder, August 16, 2012. INAC, 1992. Guidelines for ARD Prediction in the North. Department of Indian Affairs and Northern Development, Northern Mine Environment Neutral Drainage Studies No.1, Prepared by Steffen, Robertson and Kirsten (B.C.) Inc.
- Golder. 2016. Hydrogeological Assessment in Support of the Underground Mine Development at Tiriganiaq, March 21, 2016.
- Golder. 2017. Updated Predictions of groundwater Inflow to Tiriganiaq Underground Mine – V5 Mine Plan, December 18, 2017.
- Golder. 2019. Modelling Assessment of Groundwater Discharge into the Melvin Bay Marine Environment, Rev B. February 1, 2019.
- Hatch. 2013. Agnico Eagle Mines Ltd. - Meliadine Desalination Study - Salt Water Treatment Plant Report. Report No. H350003-000-05-124-002/6505-SSR-01_R82, Rev 2. September 30, 2013.
- NWB (Nunavut Water Board). 2016. Type A Water Licence No. 2AM-MEL1631.
- Snowden. 2008. Tiriganiaq gold deposit, Nunavut – resource update. Submitted to Comaplex Minerals Corp. January 2008.
- US EPA (United States Environmental Protection Agency). 2002. Short-term methods for estimating chronic toxicity of effluent and receiving waters to marine and estuarine organisms. Third edition. Cincinnati (OH): Environmental Monitoring Systems Laboratory, U.S. Environmental Protection Agency. EPA/821/R-02/014. October, 2002

APPENDIX A • SITE LOCATION AND MINE SITE LAYOUT



LEGEND

- CATCHMENT BOUNDARY
- SERVICE ROAD
- HAUL ROAD
- WATERBODY
- WATER COLLECTION POND
- DRAINED POND AREA
- OPEN PIT
- OVERBURDEN
- WASTE ROCK
- ORE
- TAILINGS
- INDUSTRIAL SITE PAD
- CONTACT WATER FLOW DIRECTION

AGNICO EAGLE

TETRA TECH

L'INFORMATION CI-CONTENUE EST LA PROPRIÉTÉ DE AGNICO EAGLE LTD. ET DOIT ÊTRE RETOURNÉE SUR DEMANDE, SANS AUTORISATION ÉCRITE PRÉALABLE. TOUTE TRANSMISSION DE COPIES À AUTRI ET TOUTE UTILISATION AUTRE QUE CELLE POUR LAQUELLE L'INFORMATION EST PRÉVUE SONT INTERDITES. © AGNICO EAGLE LTD.

THE INFORMATION HERE ON IS THE PROPERTY OF AGNICO EAGLE LTD. AND MUST BE RETURNED UPON REQUEST. WITHOUT WRITTEN PERMISSION, ANY COPYING, TRANSMISSION, TO OTHERS AND ANY USE EXCEPT THAT FOR WHICH IT IS ISSUED ARE PROHIBITED. © AGNICO EAGLE LTD.

—	—
—	—
—	—
—	—
—	—
—	—
TITRE / TITLE	# DWG

DESSINS EN RÉFÉRENCE/REFERENCE DRAWINGS

REV	DESCRIPTION	DATE	PAR BY
0	ISSUED FOR USE	01-22-2020	GZ
A	ISSUED FOR REVIEW	01-17-2020	GZ


REVISIONS

DESSINÉ PAR DRAWN BY	EL	DATE	01-22-2020
VÉRIFIÉ PAR CHECKED BY	GZ	DATE	01-22-2020
APPROUVÉ PAR APPROVED BY			
No. PROJET PROJECT NO.	6526		

TITRE / TITLE
AGNICO EAGLE – MELIADINE GOLD PROJECT
FIGURE 2 LOCATION PLAN FOR CP6 AND CP6 BERM
AS SHOWN ON GENERAL SITE LAYOUT PLAN
FOR PROPOSED INFRASTRUCTURE DURING
MINE OPERATION (YEAR 7)

ECHELLE/ SCALE	1:15000	FICHER FILE	.DWG
No. DESSIN/ DRAWING NO.		REVISION	0
		FEUILLE/SHT	1 / 1

**APPENDIX B • UNDERGROUND WATER MANAGEMENT FLOW SHEET
DIAGRAM**



PIPE UNDER PRESSURE
 PIPE WITHOUT PRESSURE
 EQUIPMENT LEVEL
 SECTION
 FIRST PIPE LENGTH (M)
 SECOND PIPE LENGTH (M)
 BALL VALVE NO
 GATE VALVE NO
 CHECK VALVE
 PRESSURE REDUCING VALVE
 BUTTERFLY VALVE
 MOTORISED BUTTERFLY VALVE
 LEVEL SENSOR
 FLOW METER
 CONCENTRIC REDUCER

4\"/>

NOTE:
 - ESTIMATED LENGTH OF PIPING, TO BE CONFIRMED BY CUSTOMER.

**NE PAS UTILISER
 POUR CONSTRUCTION**
 (NOT FOR CONSTRUCTION)

POUR APPROBATION
 (FOR APPROVAL)
 DATE : 2018-08-02

REV	DATE	DESCRIPTION	INIT.	INIT.
D	2018-11-15	ISSUED FOR COMMENTS	A.L.	A.L.
C	2018-09-26	ISSUED FOR COMMENTS	P.B.	M.B.
B	2018-09-18	ISSUED FOR COMMENTS	P.B.	M.B.
A	2018-08-08	ISSUED FOR COMMENTS	P.B.	A.L.

EMISSION/ISSUED FOR



CLIENT: AGNICO EAGLE
 MELIADINE
 PROJET/PROJECT: WATER MANAGEMENT AUDIT
 P1806201
 TITRE/TITLE: FLOWSHEET DIAGRAM
 MID TERME
 NOVEMBER 2018

CONÇU PAR/DESIGNED BY: A. Lobbe, P. Eng.	INIT.
DESSIN PAR/DRAWN BY: P. Bellerose	INIT.
VERIFIÉ PAR/CHECKED BY: A. Lobbe, P. Eng.	INIT.
APPROUVE PAR/APPROVED BY: A. Lobbe, P. Eng.	INIT.
ECHELLE/SCALE: N/A	DATE DE CREATION/CREATION DATE: 2018-08-08
# DE PROJET/PROJECT #: P1806201	REVISION
# DE DESSIN/DRAWING #: P1806201-0002	D

APPENDIX C • GROUNDWATER QUALITY SAMPLING RESULTS 2017 - 2019

Magnesium (Mg)	mg/L	2168	2120	2080	2200	2050	2092	1962	2105	1975	2017	2350	2150	2106	2208	2411	2078	2220	2150	2229	2267	2335	1970	1800	2200	2170	2355	1893	2030	2048	2290	2234	2130	1775	1800	1820	2550	2084		
Mercury (Hg)	mg/L	0.000 01	0.000 01	0.000 01	0.000 001	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	0.000 01	
Molybdenum (Mo)	mg/L	0.025	0.015	0.010	0.250	0.026	0.047	0.075	0.100	0.170	0.083	0.050	0.083	0.078	0.096	0.094	0.090	0.067	0.035	0.043	0.058	0.043	0.050	0.093	0.061	0.066	0.075	0.067	0.050	0.050	0.050	0.067	0.100	0.050	0.050	0.050	0.050	0.050	0.050	0.060
Nickel (Ni)	mg/L	0.025	0.015	0.100	0.070	0.017	0.050	0.080	0.100	0.350	0.083	0.050	0.083	0.085	0.096	0.094	0.090	0.067	0.035	0.043	0.058	0.043	0.050	0.093	0.050	0.065	0.075	0.067	0.050	0.050	0.050	0.067	0.100	0.050	0.050	0.050	0.050	0.050	0.050	0.060
Nitrate (NO ₃) as N	mg/L	0.50	2.6	0.10	2.58	0.23	0.89	4.35	0.17	0.34	0.29	0.10	0.21	1.03	2.02	0.38	0.24	0.30	0.30	0.42	0.52	0.61	0.46	2.93	0.10	0.75	0.50	0.37	0.40	0.23	0.50	0.35	0.10	8.68	4.66	0.10	0.10	1.45		
Nitrite (NO ₂) as N	mg/L	0.05	0.266	0.10	0.13	0.09	0.14	0.39	0.04	0.03	0.03	0.02	0.02	0.11	0.12	0.04	0.04	0.03	0.03	0.04	0.05	0.07	0.04	0.11	0.06	0.06	0.05	0.04	0.04	0.02	0.02	0.03	0.01	0.13	0.17	0.01	0.01	0.05		
Total Kjeldahl Nitrogen (TKN)	mg/L	3.78	8.7	4.60	5.20	7.83	7.40	12.00	72.02	4.50	9.00	5.60	4.87	12.13	6.12	4.97	5.90	5.27	4.95	5.54	4.18	7.50	4.60	6.77	6.50	5.66	4.40	4.80	5.08	4.27	6.55	4.33	4.00	14.00	9.60	4.30	3.85	5.93		
Phosphorous (P)	mg/L	0.070	0.04	0.040	0.130	0.120	0.080	0.090	0.100	—	0.390	0.080	0.080	0.111	0.075	0.083	0.162	0.073	0.200	0.173	0.118	0.175	0.420	0.154	0.100	0.158	0.150	0.120	0.175	0.100	0.105	0.122	0.210	0.094	0.093	0.110	0.115	0.127		
Potassium (K)	mg/L	496	446	407	609	433	463	518	488	763	502	528	465	510	490	532	512	479	474	500	491	539	444	391	680	503	477	429	430	438	482	467	400	427	395	371	530	440		
Radium-226 (Ra 226)	mg/L	0.49	0.29	0.30	1.20	1.95	1.80	1.90	2.20	0.29	2.20	2.40	1.67	1.39	1.85	3.68	3.88	2.63	2.05	1.94	1.83	2.45	0.67	0.91	1.80	2.15	2.15	1.26	2.90	2.37	2.00	1.58	2.90	1.13	0.40	0.89	2.05	1.78		
Selenium (Se)	mg/L	0.003	0.002	0.010	0.002	0.002	0.005	0.008	0.010	0.007	0.008	0.005	0.008	0.006	0.010	0.009	0.009	0.007	0.004	0.004	0.006	0.016	0.005	0.009	0.005	0.008	0.008	0.008	0.007	0.005	0.005	0.005	0.007	0.010	0.005	0.005	0.005	0.005	0.005	
Silver (Ag)	mg/L	0.001	0.000 3	0.002	0.001	0.000	0.001	0.002	0.000	0.018	0.003	0.001	0.002	0.003	0.002	0.004	0.002	0.001	0.001	0.001	0.001	0.001	0.002	0.002	0.001	0.002	0.002	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001
Sodium (Na)	mg/L	14625	14250	13400	15400	13900	14369	14654	14417	9433	14900	17000	15300	14304	15183	16389	14860	14967	14750	15725	15333	16450	13550	12629	16600	15131	15950	14200	15925	14500	15950	15800	15600	12965	13000	14100	16300	14935		
Strontium (Sr)	mg/L	43.1	45.5	38.4	136.0	40.0	39.0	43.5	36.5	23.6	40.0	35.1	35.7	46.4	37.2	37.3	37.1	40.1	47.7	43.9	40.0	41.3	61.9	47.4	83.4	47.0	39.5	42.7	37.5	43.5	38.2	38.4	113.0	33.6	39.1	45.7	40.0	46.5		
Sulphate (SO ₄ – dissolved)	mg/L	3125	3150	3100	3100	3233	3169	2969	3120	3067	3200	3500	3433	3181	3367	3500	3320	3367	3350	3250	3467	3625	3200	2829	3200	3316	3450	3000	3400	3200	3500	3467	2600	2850	3100	2600	3400	3142		
Thallium (Tl)	mg/L	0.001	0.000 2	0.001	0.000	0.000	0.001	0.001	0.001	0.002	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.000	0.000	0.001	0.000	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	0.001	
Uranium (U)	mg/L	0.003	0.002	0.010	0.006	0.002	0.005	0.008	0.010	0.090	0.008	0.005	0.008	0.013	0.010	0.009	0.009	0.007	0.004	0.004	0.006	0.006	0.005	0.009	0.005	0.007	0.008	0.007	0.005	0.005	0.007	0.010	0.005	0.005	0.005	0.005	0.005	0.006		
Vanadium (V)	mg/L	0.130	0.08	0.500	0.100	0.080	0.230	0.380	0.500	0.330	0.417	0.250	0.417	0.285	0.479	0.472	0.450	0.333	0.175	0.213	0.292	0.213	0.250	0.464	0.250	0.326	0.375	0.333	0.250	0.250	0.250	0.333	0.500	0.250	0.250	0.250	0.250	0.299		
Zinc (Zn)	mg/L	0.125	0.06	0.500	0.120	0.080	0.230	0.380	0.500	0.340	0.417	0.250	0.417	0.285	0.479	0.472	0.450	0.333	0.175	0.259	0.292	0.213	0.250	0.464	0.250	0.331	0.375	0.333	0.250	0.250	0.250	0.333	0.911	0.250	0.250	0.250	0.250	0.337		

* One sample result from February 24, 2017 removed from average calculations due to contamination of sample with drill water and resultant unrepresentative results of non-contact groundwater.

APPENDIX B • FRESHET MANAGEMENT PLAN



AGNICO EAGLE

Meliadine Division

Freshet Management Plan

**MARCH 2020
VERSION 6**

DOCUMENT CONTROL

Version	Date (YM)	Section	Page	Revision
1	March 2016	ALL	-	Comprehensive plan
2	March 2017	ALL	-	
3	March 2018	ALL	-	
4	December 2018	ALL	-	
5	March 2019	ALL	All 2 3 5-6 9-10 13 Figure 1 Figure 2 Appendix A	Update to reflect transitional changes to Operations phase Include DCP-1 and DCP-5 in areas of risk during Freshet Update section 2.1.2/2.1.3 noting 5 evaporators and discuss SP3 Update Section 2.8, discuss time of pond construction. Update Section 3.1, discussion of SP3 and update on inspections. Update Section 3.6., 3.7, 4 to reflect changes in freshet management. Updated to include structure names Updated to include SP3 Update to include emulsion pad to inspection list
6	March 2020	ALL 2 3 4	All 2 Figure 1 4 6-7 7 10 10 13 13 15 Figure 5 Figure 6	Document formatting to match common style Risk areas to include CP6 and TSF Include TSF P-Area volumes, source of inflows Portal sump wording & grammar; include CP6 Itivia wording & grammar Update to P-Area management for 2020 Addition of P-Area emergency pumping strategy Remove downstream D-CP5 risk mitigation; Add TSF Addition of temporary water management structure section Update Snow Management information Update Site snow management figure Update Itivia snow management figure



TABLE OF CONTENTS

TABLE OF CONTENTS	ii
Section 1 • Introduction	1
Section 2 • Areas of Risk during Freshet	2
2.1 P-Area.....	4
2.1.2 P1	4
2.1.3 P2	4
2.1.4 P3	4
2.1.5 Saline Pond 3.....	4
2.2 Portal 1 Sump 1 (LV50 SUMP).....	6
2.3 Portal 2 Sump 1 (LV50 SUMP).....	6
2.4 Landfarm	6
2.5 All Weather Access Road (AWAR).....	6
2.6 Infrastructure Areas	6
2.7 CP1, CP3, CP4, CP5, and CP6.....	6
2.8 Bypass road	7
2.9 Itivia.....	7
2.10 Tailings Storage Facility	7
Section 3 • Freshet Risk Management	10
3.1 P-Area Risk Management.....	10
3.2 Portal 1 Sump 1 Risk Management.....	10
3.3 Landfarm Risk Management	11
3.4 AWAR, Bypass Road and CP3/CP4 access road Risk Management	11
3.5 Infrastructure Areas	11
3.5.1 Camp Pads and Surroundings	11
3.5.2 Industrial Pad and Access Road	12
3.6 CP1, CP3, CP4, CP5, CP6, and Quarries	12
3.7 Itivia.....	12
3.8 Tailings Storage Facility	13

3.9 Temporary Water Management Structures 13

Section 4 • Snow Management 14

Section 5 • References 17

Appendix A: Freshet Action Plan Procedure

Appendix B: Snow Management Procedure

Figure 1: Site Plan View with Areas of Risk at Site during Freshet 3

Figure 2: P-Area Plan View..... 5

Figure 3: AWAR Map Showing Water Crossing Location 8

Figure 4: Bypass Road and Culvert Location 9

Figure 5: Snow Management Plan on Site 15

Figure 6: Itivia Snow Management Areas 16

SECTION 1 • INTRODUCTION

The purpose of the Freshet Action Plan (Plan) is to provide Agnico Eagle with specific management and mitigation measures to address and manage water associated with the freshet season (Freshet), a response plan, and procedures to prevent and to minimize potential negative impacts to the surrounding environment at the Meliadine Site (Site).

The term freshet refers to spring thaw, which can result in inundation of floodplains. Freshet at Meliadine typically takes place between May 15 and July 30. In some years, Freshet can also happen in early fall, when freezing re-occurs (mid-October) and then thaws. There are areas at the Site that are vulnerable to excess water produced during Freshet; the objective of this document is to identify those areas, and to develop a plan with defined roles and responsibilities to manage excess water produced on site.

The following guiding principles are applicable to the Plan:

- To ensure that mine contact water from runoff or seepage is managed to prevent adverse environmental impacts;
- To ensure the health and safety of Agnico Eagle employees and contractors; and
- To ensure the Site is in compliance with the Nunavut Water Board (NWB) Type A Water Licence No.: 2AM-MEL1631 (Type A Licence).

The Plan identifies areas of risk during Freshet, risk management and the procedures necessary to address potential concerns.


SECTION 2 • AREAS OF RISK DURING FRESHET

The key areas of risk during Freshet at the Site include the following:

- P-Area
- Portal 1 Sump 1 (Sump LV50)
- Portal 2 Sump 1 (Sump LV50)
- Landfarm A and Landfarm B
- Landfill
- All Weather Access Road (AWAR) and Quarries along the road
- Infrastructure Areas; including the Exploration Camp area, Portal 1 & 2 and the Industrial Pad Areas
- Containment Pond 1 (CP1), Containment Pond 3 (CP3), Containment Pond 4 (CP4), Containment Pond 5 (CP5) and Containment Pond 6 (CP6)
- D-CP1 and D-CP5
- Meliadine Esker Quarry
- Bypass Road
- Itivia laydown and fuel handling facility (Itivia)
- Tailings Storage Facility

Identified areas of risk at Site are shown in Figure 1, and are described in the following section.

Figure 1: Site Plan View with Areas of Risk at Site during Freshet



2.1 P-Area

Surface runoff that has come in contact with the southern portion of the future Waste Rock Storage Facility 2 (WRSF2) and surface works in the area of Portal 1 flows preferentially to the P-Area containment.

The P-Area includes three containment areas (Figure 2); P1 Containment Area (P1), P2 Containment Area (P2), and P3 Containment Area (P3) and has a cumulative capacity of 30,521 m³. Periodic pumping to P1, from P2 and P3, is planned to manage water levels in P2 and P3. In past years active evaporation has been applied. In 2020, alternatives to active evaporation are being assessed by AEM as a means to facilitate potential decommissioning of the P-Area.

2.1.2 P1

P1 has a capacity of 20,781 m³ and is the largest of the three ponds that make up the P-Area. Water contained in P1 includes direct precipitation, surface runoff in the P1 catchment area and any water accumulated in P2 or P3. Five evaporators are installed at P1. As mentioned above, alternatives to the evaporators are being assessed.

2.1.3 P2

P2 has a capacity of 6,828 m³ and is located directly adjacent to and down-gradient from P1. In addition to direct precipitation, P2 captures surface runoff from the surrounding catchment area. Water captured in P2 is pumped to P1, as required.


2.1.4 P3

P3 has a capacity of 2,912 m³ and is down-gradient of P1 and P2. P3 contains surface runoff from the surrounding catchment, including the portal entrance area. Water from P3 is pumped to P1, as required. Furthermore, for the 2020 freshet, a back-up pump from P3 to CP5 is planned to manage greater than expected inflows to the P-Area and to ensure management of P3 water levels and protection of the SP3 liner (Section 3.1).

2.1.5 Saline Pond 3

Saline Pond 3 (SP3) is located south of P3 and has a maximum water storage capacity of 7,985 m³. The design of the containment structure uses an elevated dike approximately 2 m higher than the adjacent road surface. As such, runoff water in this area does not flow into SP3.

Figure 2: P-Area Plan View



2.2 Portal 1 Sump 1 (LV50 SUMP)

LV50 is located 50 meters below grade (mbg) and is the first sump located down the Portal 1 ramp. Snowmelt and surface run-off that flows down the portal entrance is directed to sump LV50 where it is then pumped to CP5. The overall capacity for Portal 1 Sump 1 is 29 m³. Water pumped from Portal 1 Sump 1 to CP5 is measured with a volumetric flow meter and recorded daily.

2.3 Portal 2 Sump 1 (LV50 SUMP)

LV50 is located 50 meters below grade (mbg) and is the first sump located down the Portal 2 ramp. Snowmelt and surface run-off that flows to the portal entrance to sump LV50 is pumped from LV50 to Channel 1. The overall capacity for Portal 2 Sump 1 is 55 m³. Water pumped from Portal 2 Sump 1 to Channel 1 is measured with a volumetric flow meter and recorded daily.

2.4 Landfarm

The Type A License Landfarm is located adjacent and east of the Industrial Site Pad and is designed to receive soils, rock, snow, and ice contaminated with petroleum hydrocarbons. This includes light hydrocarbons such as diesel and gasoline (Agnico Eagle, 2019). It was assumed that an annual volume of 500 m³ of contaminated ice and snow would require management and the Landfarm has been designed to account for this volume.

The Landfarm has geotextile liners and is filled with soil. Water that pools, collects or flows from the Landfarm is collected for monitoring and treated before it is discharged to CP1.

2.5 All Weather Access Road (AWAR)

The All-Weather Access Road (AWAR) was built in 2013 to connect the Site to the hamlet of Rankin Inlet. The road is approximately 23.8 km long with twenty-two water crossings; three bridge crossings and nineteen culverts installed (Figure 3).

2.6 Infrastructure Areas

Infrastructure Areas represent buildings, pads and towers installed at the Site and include the Industrial Pad, Exploration Camp, and Emulsion Plant (Figure 1).

2.7 CP1, CP3, CP4, CP5, and CP6

Engineered water containment dikes constructed in 2017 at lakes A54 and H17 were developed as D-CP5 and D-CP1, respectively. The dikes are designed to contain contact water within the footprint of the Site and prevent pollution provisions of the *Fisheries Act*. Both CP1 and CP5 are used for Site contact water and snow and ice collection prior to Freshet. CP1 and CP5 are illustrated in Figure 1 and discussed in Section 3 of this plan.

CP3 and CP4 are containment ponds designed to collect runoff from the Tailings Storage Facility (TSF) area and Waste Rock Storage Facility 1 (WRSF1) area, respectively. CP3 construction was completed in Q4 of 2018 and CP4 construction was completed in Q2 2019. CP3 and CP4 design plans implement engineered thermal protection berms. Maximum operating levels within CP3 and CP4 are such that Berm-CP3 and Berm-CP4 will not be required to retain water (see Water Management Plan).

Construction of CP6 is on-going and the facility will be commissioned prior to Freshet of 2020. CP6 is designed to collect runoff from Waste Rock Storage Facility 3 (WRSF3) where the water will then be pumped to CP1 for containment prior to discharge. CP6 design implements an engineered thermal protection berm. Maximum operating level within CP6 is such that Berm-CP6 will not be required to retain water (see Water Management Plan).

2.8 Bypass road

The Bypass Road is a 5.9 km access road that provides a means to divert site-related traffic around the community of Rankin Inlet. The Bypass Road spans from the northwest margin of Itivia to km 2.9 on the AWAR (Figure 4) and has 19 culverts installed at 13 locations along the road.

2.9 Itivia

Itivia is located in Rankin Inlet and is accessed by the Site from the AWAR and Bypass Road. In combination with the Bypass Road, Itivia is intended to support the Site as a staging point for incoming and outgoing fuel and material handling for barge shipments. Itivia is also the location of the final discharge point for saline effluent generated by the mine. The location of Itivia is shown on Figure 3 and the plan view of the Itivia Site is presented as Figure 6. A culvert is installed to divert runoff around the Itivia Site and to allow passage of run-off from the Itivia laydown area (Figure 6).

2.10 Tailings Storage Facility

The Tailings Storage Facility (TSF) is a dry stack tailings storage facility. The TSF dry stack is located west of the Industrial Pad as shown in Figure 1. The facility stores compacted tailings that are transported from the process plant by haul truck. The tailings are spread and compacted in the facility. The tailings are deposited within a rockfill bermed area. The rockfill berm will ultimately form the cover for the placed tailings. Culvert 1 is in place to allow passage of water through the TSF haul road.

Figure 3: AWAR Map Showing Water Crossing Location Section





Figure 4: Bypass Road and Culvert Location



SECTION 3 • FRESHET RISK MANAGEMENT

Managing the risks prior to Freshet is a primary objective at Site. Planning and preparing before Freshet alleviates some of the risk from excess water that may suddenly occur, and helps to ensure compliance with applicable regulations. This is managed by removing water (pumping) at containment pond areas prior to winter freeze (fall) to allow for increased capacity from precipitation, snow and ice removal on roads, road water crossings, culverts, ditches, and select containment ponds after winter freeze and before Freshet (winter and spring).

Risk management practices for the Site areas during Freshet are described below and Appendix A presents the Freshet Action Plan Procedure for preparation prior to, during and after Freshet. Section 4 describes snow management at Site and Appendix B presents the Snow Management procedure.

3.1 P-Area Risk Management

The following management practices are maintained at the P-Area during Freshet and are described in more detail in Appendix A:

- Water levels will be monitored. The water level will not exceed the maximum design elevation in any of the three containment ponds (P1, P2 or P3). P3 water levels will be kept as minimal as possible to keep water from affecting the base of Saline Pond 3 (SP3), which is located immediately adjacent to (southwest of) P3, prior to Freshet (see Water Management Plan for details). To ensure maintenance of P3 water levels under scenarios of pump failure or greater than expected runoff volumes, installation of a back-up pump from P3 to CP5 is planned.
- Runoff water contained in the downstream sumps of DP1-B and DP3-A will be pumped into P1-B and P3, respectively.
- Agnico Eagle will conduct weekly freshet structural inspections of the dikes and note any observed seepage. Inspections will also include monitoring the base of SP3 for settling, slumping and cracking.
- Active evaporation from use of the evaporators may be used to contribute to managing the quantity of water contained at P-Area. However, alternatives to active evaporation as a means to manage P-Area water are being explored by AEM.
- Weekly water sampling during Freshet.

In the event that emergency removal of water contained within one or more cells comprising the P-Area is necessary, the most recent water quality data available will be used to determine an appropriate location for the water to be pumped to. The receiving location will also be assessed for sufficient capacity to receive the P-Area water.

3.2 Portal 1 Sump 1 Risk Management

If CP5 becomes filled to capacity and LV50 sump needs to be pumped, the water from LV50 will flow down gradient to the Underground Water Stope.

3.3 Landfarm Risk Management

If there is any excess water collected at the Landfarm during Freshet and treatment is not immediately possible, the excess volume will be transferred to the contaminated snow cell located in the Northwest extent of P1. If the snow cell is at capacity and the Landfarm contains excess water, the water will be sampled and, pending acceptable results, the water will be moved to CP1. If results do not allow transfer to CP1, water will be stored in totes until treatment is possible.

In the event that the water sample results do not allow transfer to CP1, potential treatment methods are as follows:

- Oil/water Separator
- CI Agent E-VAC Waste Water Filter System
- Carbon Filter System

If a suitable treatment cannot be completed, the water will be shipped south in totes or bladders for disposal in a certified disposal facility.

3.4 AWAR, Bypass Road and CP3/CP4 access road Risk Management

The following management practices are maintained to ensure the integrity of the AWAR, Bypass Road and CP3/CP4 access roads before and during Freshet and are described in further detail in Appendix A:

- Large culverts will be heated/steamed as necessary to allow the free flow of Freshet water.
- Prior to Freshet, water crossings and culverts will have snow removed from ice surface on the up and downstream side of the crossing to allow free flow of water.
- Visual inspections of AWAR and Bypass Road will be undertaken as to the structural integrity of the abutments and road integrity by the E&I Supervisor.
- Weekly (minimum) written inspections throughout Freshet and daily during excessive rainfall response including TSS transport, culvert/crossing function, flow rates, and integrity of roads will be completed by the Environment Department in conjunction with the E&I Department.

If erosion or ground surface scouring are observed, the E&I Department will be notified for repairs. TSS barriers, silt fences, straw logs or other sediment control methods will be implemented as required.

3.5 Infrastructure Areas

Risk management practices for the main Infrastructure Areas at the Site during Freshet are described in the following sections.

3.5.1 Camp Pads and Surroundings

Risk management practices are maintained at the Exploration Camp, Main Camp and surrounding camp areas as follows:

- Clearing off ice and debris from culverts prior to and during Freshet;

- Visual inspections for excessive water pooling. If pooled water is observed to flow into a water body, a water sample will be collected and monitored for TSS. Follow-up samples will be collected on a weekly basis thereafter;
- Visual inspections for snowmelt runoff. If runoff is observed to flow into a water body, a water sample will be collected and monitored for TSS. Follow-up samples will be collected on a weekly basis thereafter;
- Visual inspections to ensure flow through culverts and along channels is not impeded; and
- TSS transport will also be monitored at the culvert beside the garage that flows straight to Meliadine Lake. This area will be monitored for TSS, and preventative measures (install straw wattles and/or booms) will be installed to prevent deleterious substances from entering Meliadine Lake.

3.5.2 Industrial Pad and Access Road

The following management practices are maintained to ensure the integrity of the industrial pad and access road:

- This area will be monitored for turbidity and preventative measures (install straw wattles and/or booms) will be implemented to prevent deleterious substances from entering Meliadine Lake.

3.6 CP1, CP3, CP4, CP5, CP6, and Quarries

Risk management practices for CP1, CP3, CP4, CP5, CP6, and the Meliadine Esker and Quarries include discharging/pumping the water prior to winter freeze to be treated and/or discharged as per the Type A Water Licence and the Water Management Plan. If water is observed to be flowing or ponding, it will be sampled to ensure deleterious substances and TSS is not released to surrounding water bodies (Part I, Item 11 of the Type A Water Licence). Inspections of CP1, CP3, CP4, CP5, CP6, and associated water management structures or thermal protection berms, will be conducted following Part E Item 15 of the Type A Water Licence and Section 3.12 of the Water Management Plan.

3.7 Itivia

The following management practices are maintained to ensure the integrity of Itivia and the Bypass Road:

- The culvert installed between the Itivia laydown and the existing laydown areas (Figure 4) will be cleared of snow and ice prior to Freshet and will be monitored closely for TSS transport;
- Rip rap was installed around the culvert to control erosion and a decantation sump will be maintained downstream to collect suspended sediment;
- Two rock check dams were installed in 2019 upstream of the culvert to mitigate TSS transport through the Itivia site (Figure 6; Tetra Tech 2019);
- The upstream and downstream extents of the culvert area will be monitored for turbidity and preventative measures (install straw wattles and/or booms) will be implemented to prevent deleterious substances from entering Hudson's Bay; and

- Weekly water sampling at locations of runoff.

3.8 Tailings Storage Facility

The following management practices are maintained to ensure the integrity of the Tailings Storage Facility (TSF) and its associated structures:

- Culvert 1 (access road to TSF) will be cleared of snow and ice prior to Freshet and will be monitored closely for TSS transport;
- Snow that has accumulated on the TSF deposition surface will be removed prior to Freshet to reduce snowmelt runoff and pooling (Section 4);
- Daily visual inspections for ponding and areas of elevated sediment transport;
- Weekly inspections carried out to identify areas of concern including issues of seepage, cracking, and ponding on the TSF and associated structures.

3.9 Temporary Water Management Structures

Based on anticipated areas of ponding and/or impediment to flow on Site, or in reaction to unexpected ponding and/or impediment to flow on Site, temporary water management structures may be implemented to protect infrastructure by encouraging water movement through the water management system. Temporary water management structures will be constructed as needed and decommissioned when the event invoking the requirement (i.e., ponding) comes to an end. Such structures will be built in such a way that they maintain the overall flow direction of waters on site and do not affect the discharge to the receiving environment. No temporary measures would be placed outside the project footprint, nor alter the way water enters into the receiving environment. Temporary water management structures may include:

- Trenching in snow and/or ice;
- Excavation into ice to allow the immediate installation of pumps, avoiding the necessity to wait for ice to thaw; or
- Trenching/spillways across roads on Site at areas of ponding where pumping rates are unable to match accumulation rates.

SECTION 4 • SNOW MANAGEMENT

Proper snow management during the winter contributes to risk mitigation from excess water during Freshet and prevents possible environmental impacts. *The Snow Management Procedure* (Procedure Number MEL-ENV-0017) (Appendix B) presents the plan to efficiently manage snow at the Site.

Snow that is removed from the Main Camp, Industrial Pad, Ore Pad, 6 Million Liter Fuel Farm, Portal 2 Pad, and Crusher Pad will be transported to a snow dump in the north end of CP1. Snow removed from the Tailing Storage Facility (TSF) will be transported to the north end of the TSF depositional footprint which is currently not occupied by tailings. Snow removed from the Paste Plant, Batch Plant, and surrounding laydowns will be transported immediately north of the Batch Plant and maintained as a level snow pad. Snow removed from the 3 Million Liter Fuel Farm, Portal 1 Pad, Vent Raise, SWTP/SETP Pad, and associated laydowns will be transported to CP5 and maintained as a level snow pad.

Snow and ice from the other areas at the Site are removed from roadways with a snow blower or plow and/or transported to CP1 or CP5, depending on the catchment of origin. Snow removal outside of the designated zones is generally maintained as a clean, level snow pad. Figure 5 illustrates the locations for snow collection during the winter and prior to Freshet. Figure 6 illustrates the snow management and storage areas for Itivia.




Figure 5: Snow Management Plan on Site. The locations identified by “x” are snow deposition areas for respective snow clearing areas (coloured polygon areas). Each snow clearing area and “x” are colour coded to identify where snow cleared from each area is deposited.




Figure 6: Itivia Snow Management Areas

SECTION 5 • REFERENCES

Agnico Eagle. 2019. Meliadine Gold Project: Landfarm Management Plan. Version 3. March 2019. 6513-MPS-15.

Tetra Tech. 2019. Construction summary (as-built) report for Rankin Inlet Itivia site fuel storage and containment facility Meliadine project, Nunavut. Amendment#01 to 6515-E-132-005-132-REP-015. September 2019.

APPENDIX A: FRESHET ACTION PLAN PROCEDURE

DOCUMENT ID: MEL-ENV-Freshet Management Plan Procedure

People concerned: Agnico Eagle employees, contractors, visitors on the Meliadine site

Effective Date: March 28, 2018

This procedure corresponds to the required minimum standard. Each and everyone also have to comply with the rules and regulations of the Nunavut Government in terms of health and safety at work.

Rev #	Date	Description	Initiator
1	2018-03-28	Change to Intalex Format	Matt Gillman
2	2018-12-14	Updated for 2019 Season	Matt Gillman
3	2019-03-12	Updated for 2019 Season, updated snow procedure spreadsheet to include D-CP5 and SP2	Matt Gillman
4	2020-03-17	Updated for 2020 Season, updated snow procedure to reflect current infrastructure, updated inspection frequencies	John Baechler Matt Gillman

Objective:

- To provide a plan to prevent potential environmental incidents at the Meliadine Site (Site) caused by the freshet season (Freshet) by recognizing specific areas for risk at the Site, possible actions to be undertaken and the departmental responsibilities to address the required actions.

Definitions (If applicable):

Tool/Equipment Required	PPE Required
<ul style="list-style-type: none"> N/A 	<ul style="list-style-type: none"> N/A

This document is void 24 hours after printing

Procedure				
Winter and Spring – Preparation Prior to Freshet¹				Risks/ Impacts
Area for Risk		Action	Responsible Department	Approximate Dates
P-Area	P1, P2 & P3	<ul style="list-style-type: none"> Snow must not be stockpiled in any of the P-Area containment ponds 	Environment to coordinate with Energy & Infrastructure, Engineering and Construction	All times
AWAR, Bypass Road & CP3/CP4 Service Roads	Culverts	<ul style="list-style-type: none"> Weekly Inspections Snow and ice clearing¹, including ice and snow that may impede free water flow through culverts (including the culvert at Itlivia) and at major water crossings Effort is to be made to ensure road surface material is not removed during snow clearing. Ensure snow is not stockpiled along roadside Repairs (mark culvert locations, add armouring around downstream culverts and bridges, replace pipe as needed, and document maintenance and repairs) 	Environment	April - May
	Major Crossings	<ul style="list-style-type: none"> Monitor signs of erosion (especially downstream at culverts 14.9 and 16 Km on AWAR) Notify the Environmental Department about any areas for concern^{2,3} 	Energy & Infrastructure	Winter Freeze to May (start of thaw)
	Overall Roads	<ul style="list-style-type: none"> Inspection as needed and weekly from April - May Snow and ice clearing¹, including ice and snow that may impede free water flow through culverts and at major water crossings Repair any erosion Notify the Environmental Department about any areas for concern^{2,3} 		
Industrial Pad & Emulsion Pad	Culverts	<ul style="list-style-type: none"> Inspection as needed and weekly from April - May Snow and ice clearing¹, including ice and snow that may impede free water flow through culverts and at major water crossings Repair any erosion Notify the Environmental Department about any areas for concern^{2,3} 	Environment	Winter Freeze to May (start of thaw)
	Channels and ditches	<ul style="list-style-type: none"> Repair any erosion Notify the Environmental Department about any areas for concern^{2,3} 	Energy & Infrastructure	
	Access Road	<ul style="list-style-type: none"> Repair any erosion Notify the Environmental Department about any areas for concern^{2,3} 		
Quarries		<ul style="list-style-type: none"> Snow and ice clearing¹, including ice and snow that may impede free water flow through culverts and at major water crossings Re-grade disturbed areas to provide appropriate drainage 	Construction Environment (for Sampling)	Winter Freeze to May (start of thaw)



This document is void 24 hours after printing





<p>Tailings Storage Facility</p>	<ul style="list-style-type: none"> • Culvert 1 (access road to TSF) will be cleared of snow and ice prior to freshet and will be monitored closely for TSS transport; • Snow that has accumulated on the TSF deposition surface will be removed prior to freshet to reduce snowmelt runoff and pooling (Section 4); 	<p>Energy & Infrastructure</p>	<p>Winter Freeze to May</p>	
----------------------------------	---	------------------------------------	-----------------------------	--

Note:

¹ See the *Snow Management Procedure* (Procedure No.: MEL-ENV-0017) for additional information for snow removal at the Site.

² The Environmental Department will assess the area of concern and action will be undertaken to comply with the Nunavut Water Board (NWB) Water Licence No.: 2AM-MEL1631 (Licence)(i.e. collect field parameters or water samples for analysis of total suspended solids, turbidity, or any deleterious substance).

³ Areas of concern are defined as high water areas on roads, near the up gradient opening of a culvert, flowing water with sediment, spills, wildlife, etc.

Spring and Summer – During Freshet or During Heavy Rainfall				Risks/ Impacts
Area for Risk	Action	Responsible Department	Approximate Dates	
P-Area				
P1, P2, and P3	<ul style="list-style-type: none"> Weekly visual inspection at minimum (daily as needed) Daily monitor and record water levels Weekly written inspection Water sampling 	Environment	May - October	   
	<ul style="list-style-type: none"> If water levels or structural integrity of berms are observed to be compromised, immediate action is required. Notify Supervisor 	Engineering		
	<ul style="list-style-type: none"> P2 and P3 water volume should be kept as minimal as possible. Pumping of this water should occur regularly (daily) Measure and record pumping volumes daily and report to Environment weekly 	Energy & Infrastructure		
Evaporators	<ul style="list-style-type: none"> Commission after sub-zero temperatures no longer occur Operate as efficient as possible 	Energy & Infrastructure		
DP1 and DP3 Trenches /Seep	<ul style="list-style-type: none"> Install pump and flow meter at trench to collect seep Pump water to respective containment area (P1 or P3) Measure and record pumping volumes daily and report to Environment weekly 	Energy & Infrastructure		
AWAR, Itivia, Bypass Road, CP3/CP4 Access Roads				
Culverts	<ul style="list-style-type: none"> Inspections for free flow water through culverts and major crossings, pooling water on road, and integrity of road and abutments (Weekly (minumum) or after heavy rainfall between May and October and daily during peak flow) Sample as required² 	Environment	May - October	
	AWAR Major Crossings	<ul style="list-style-type: none"> Snow and ice clearing¹, including ice and snow that may impede free water flow through culverts and at major water crossings 		
Overall Roads and Itivia	<ul style="list-style-type: none"> Repairs and erosion/sediment control implementation Notify the Environmental Department about any areas for concern ^{2,3} 	Environment (for Sampling)		
Quarries	<ul style="list-style-type: none"> Repairs and erosion/sediment control implementation Re-grade disturbed areas to provide appropriate drainage 	Construction Environment (for Sampling)		

This document is void 24 hours after printing

	<ul style="list-style-type: none"> Notify the Environmental Department about any areas for concern ^{2,3} 			
Spring and Summer – During Freshet or During Heavy Rainfall				
Main Camp Pad/Industrial Pad				
Culverts	<ul style="list-style-type: none"> Weekly inspections (at minimum; daily as needed) for free flow water through culverts and major crossings, pooling water on road, and integrity of road and abutments 	Construction Environment (for Sampling)	May - October	
Channels and Ditches	<ul style="list-style-type: none"> Snow and ice clearing¹, including ice and snow that may impede free water flow through culverts and at major water crossings Repairs and erosion/sediment control implementation Notify the Environmental Department about any areas for concern ^{2,3} 	Construction Environment (for Sampling)	May - October	
Access Road				
Infrastructure Pads				
Exploration Camp and Laydown	<ul style="list-style-type: none"> Weekly visual inspection at minimum (daily as needed) Water sampling as required Installation of TSS mitigations as needed 	Environment	May - June	
Landfarm Structure	<ul style="list-style-type: none"> Daily inspection of the landfarm retaining wall Daily visual inspection for seepage Collect a seepage water sample for hydrocarbon analysis. If seepage is present it should be immediately sampled and the seep be controlled. Whether by creating a sump and pumping back the water or by other methods. 	Environment		
Landfarm	<ul style="list-style-type: none"> Visually monitor excess water in containment area Monitor seep (weekly) and collect water sample Sample water according to the Licence 	Environment	Mid-June and September	
	<ul style="list-style-type: none"> If excess water is present and cannot be treated immediately, sample in preparation for discharge to CP1 		10 days prior to pumping	
	<ul style="list-style-type: none"> Once sample results have received, and if water is acceptable to be pumped to CP1 meets, water can be pumped to CP1 at a low flow to avoid erosion Measure and record pumped volume 	Energy & Infrastructure	Mid-June and September	
Core Box Cemetery and Culvert	<ul style="list-style-type: none"> Install straw wattles for sediment control on the other side of the road 	Energy & Infrastructure	May	
	<ul style="list-style-type: none"> Weekly (at minimum; daily as needed) monitoring of TSS and turbidity and possible contaminant runoff 	Environment	May - June	
Emulsion Plant Pad	<ul style="list-style-type: none"> Weekly Inspections Water sampling of runoff as required for ammonia, nitrates, turbidity and TSS 	Environment	May - June	
	<ul style="list-style-type: none"> Daily visual inspection for pooling water and water run off from pad to tundra, if noticed immediately contact environment department 	Dyno Nobel		

This document is void 24 hours after printing





Tailings Storage Facility	<ul style="list-style-type: none"> • Daily visual inspection for ponding and areas of elevated sediment transport; • Weekly inspections carried out to identify areas of concern including issues of seepage, cracking, and ponding on the TSF and associated structures. 	Environment & Engineering	May - June	
---------------------------	---	---------------------------	------------	--

Note:

¹ See the *Snow Management Procedure* (Procedure No.: MEL-ENV-0017) for additional information for snow removal at the Site.

² The Environmental Department will assess the area of concern and action will be undertaken to comply with the Nunavut Water Board (NWB) Water Licence No.: 2AM-MEL1631 (Licence)(i.e. collect field parameters or water samples for analysis of total suspended solids, turbidity, or any deleterious substance).


³ Areas of concern are defined as high water areas on roads, near the up gradient opening of a culvert, flowing water with sediment, spills, wildlife, etc.

Fall – Preparation Prior to Winter Freeze				Risks/ Impacts
Area for Risk	Action	Responsible Department	Approximate Dates	
LV50	<ul style="list-style-type: none"> Survey water level and calculate water volume and provide to Environment, and/or Measure and record flow meter volume prior to pumping and after pumping and provide to Environment Remove pumps and prepare equipment for maintenance and winter storage 	Mining	Prior to pumping to P2 (Late September)	
	<ul style="list-style-type: none"> Pump to P2 		Late September/Early October	
Lv75/Water Stope	<ul style="list-style-type: none"> Pump to SP1, SP2 (pending approval), or SWTP 		June - September	
P-Area	P2 and P3	<ul style="list-style-type: none"> Pump water to P1 for active evaporation 	June - September	
	P1, P2 & P3	<ul style="list-style-type: none"> Remove pumps and prepare equipment for maintenance and winter storage 	At beginning of winter freeze	
	Evaporators	<ul style="list-style-type: none"> Decommission for winter and prepare equipment for maintenance and winter storage 	Prior to any sub-zero temperatures	
A8	<ul style="list-style-type: none"> Move pump house/pump closer to Site 		Late September	
CP1	<ul style="list-style-type: none"> Water sampling 	Environment	June - September	
	<ul style="list-style-type: none"> Pump water to discharge at Meliadine Lake Remove pumps and prepare equipment for maintenance and winter storage 	Process Plant	Late September/Early October	
Downstream D-CP1	<ul style="list-style-type: none"> Pump water to CP1 	Energy & Infrastructure	June - September	
	<ul style="list-style-type: none"> Remove pumps and prepare equipment for maintenance and winter storage 		Late September/Early October	
CP5/D-CP5	<ul style="list-style-type: none"> Restrict vehicle access on D-CP5 to prevent instrument damage Pump water to CP1/SWTP 		Late September	
Downstream D-CP5	<ul style="list-style-type: none"> Pump water to CP5 		June - September	

This document is void 24 hours after printing

	<ul style="list-style-type: none"> Remove pumps and prepare equipment for maintenance and winter storage 		Late September/Early October	
Saline Ponds	<ul style="list-style-type: none"> Remove pumps and prepare equipment for maintenance and winter storage 		First week of October	
Tailings Storage Facility	<ul style="list-style-type: none"> Daily visual inspections for ponding and areas of elevated sediment transport; Weekly inspections carried out to identify areas of concern including issues of seepage, cracking, and ponding on the TSF and associated structures. 	Environment & Engineering	June - September	

Figure 1: Areas of Risk



This document is void 24 hours after printing

Related Documentation (If applicable):

- 2018 Freshet Management Plan
- MEL-ENV-0017 - Snow Management Procedure

References (If applicable):

- N/A

Authorization (Print Name)

Approved :	Name JOHSC Worker Rep.	Date:	
Approved :	Name Department Superintendent / Delegate	Date:	
Approved :	Name Health & Safety Superintendent / Delegate	Date:	



APPENDIX B: SNOW MANAGEMENT PROCEDURE

This document is void 24 hours after printing

DOCUMENT ID: MEL-ENV-PRO Snow Management

People concerned: Meliadine employees and contractors

Effective Date: 21 December 2019

This procedure corresponds to the required minimum standard. Each and every person must comply with the rules and regulations of the Nunavut Government in terms of health and safety at work.

Rev #	Date	Description	Initiator
1	2018-03-28	Change to Intellex Format	Matt Gillman
2	2018-09-30	Updated for next season	John Baechler Matt Gillman
3	2018-10-11	Updated to include changes to snow management methods at Itivia, bypass road, CP3 and CP4 access roads, and Itivia Gas Boy.	Dan Gorton John Baechler
4	2019-12-17	Revised definitions, updated snow dump/pad location descriptions (table) and figure, removed P-Area snow dump, incorporated dust mitigation with TSF snow removal, updated Itivia snow management figure with flow paths and check dams.	John Baechler

Objective:

The overall purpose of the snow management procedure (SMP) is to provide an outline for snow management that will assist with preventing adverse environmental impacts to the Meliadine Project (Site) and to mitigate risks from excess water during the freshet season (Freshet).

Definitions

Snow pad – A snow storage area where snow is flattened and compacted to promote sublimation, control runoff, reduce the formation of snowdrifts, and reduce the negative impact of snow melt.

Snow pile – A stockpile of snow that has not been further manipulated into a snow pad.

Negative impact of snow melt– High velocity runoff resulting in the transport of fine sediments or deleterious substances.

Tool/Equipment Required	PPE Required
<ul style="list-style-type: none"> • Snow blower • Shovel and haul truck • Grader 	<ul style="list-style-type: none"> • Standard site PPE

Specific Training Requirements
<ul style="list-style-type: none"> • Equipment operator training

Procedure
<p>Snow Removal at Meliadine Site</p> <ol style="list-style-type: none"> 1. Prior to starting any snow removal, supervisors and equipment operators must discuss a removal plan based on the criteria outlined in this procedure. 2. If uncertain, supervisors or equipment operators must receive authorization from the Environment Department prior to moving snow to a non-designated area. 3. If snow is contaminated with a deleterious substance, snow removal should stop immediately to avoid the spread of contamination, and the steps outlined in the Spill Contingency Plan for Spills on Snow and Ice must be followed. 4. Supervisors must determine if the snow receiving location is: <ul style="list-style-type: none"> • Safe for the equipment operators; • Outside of a 31 m buffer zone around any water body; • A designated snow storage area; • A safety sensitive area. 5. Designated snow storage areas are as follows (see Figure 1 in the Appendices):

Snow Removal Area	Designated Snow Storage Area
Main Camp, Industrial Pad, Ore Pad, 6 Million Fuel Farm, Portal 2 Pad, Crusher Pad	Snow to be transported and dumped into a snow pile in the north end of CP1, not requiring further manipulation into a snow pad.
Tailing Storage Facility	Snow to be transported to the north end of the TSF and formed into wind breaking berms, running east-west, for TSF dust mitigation.
Paste Plant, Batch Plant	Snow to be transported immediately north of the Batch Plant and <u>maintained as a snow pad.</u>
3 Million Fuel Farm, Portal 1 Pad, Vent Raise, SWTP/SETP Pad	Snow to be transported to CP5 and <u>maintained as a snow pad.</u>

6. Snow piles are not authorized on the sides of any roadways, including the East Access Road, West Haul Road, CP3 Road, CP4 Road, All Weather Access Road (AWAR), Exploration Camp Road, or Bypass Road. Snow removed from roadways must be blown, or maintained as a snow pad next to the road.
7. The Fuel Farms, Gas Boy, Landfarm, and Itivia Diesel Tanks are safety sensitive areas. The valves and piping/hosing must be protected and available for inspection at all times. Snow must not be removed with a snow plow or heavy equipment.
8. Snow accumulated in Channels 1, 2, 3, 4, and 5 must be left to melt at freshet, as the use of snow removal or plow equipment can damage the synthetic channel liners.
9. A level snow pad may be created over the tundra provided that:
 - Clean snow is used for the pad construction;
 - The surface is cleaned after use;
 - Is not obstructing existing culverts, structures, or roadways.
10. Snow piles areas are not authorized at the Exploration Camp. Snow must be maintained as a snow pad to reduce the formation of snowdrifts and the negative impact of snowmelt at freshet (Figure 2).
11. Snow between the Main Camp dormitory wings must be removed to mitigate drifting against

the wings, which creates confined space under the camp and wildlife habitats (Figure 3).

12. Snow removed by Contractors at their designated worksite will be stockpiled at the worksite and subsequently removed by the Site Services department.

Snow Removal at Itivia Site

1. Snow piles are not authorized at the Itivia Laydown. Snow at the Laydown must be maintained as a snow pad. The existing ATV/snowmobile trail must not be blocked by snow removal (Figure 4).
2. Snow along the bypass road must be removed by blowing. Sand will not be used along the Bypass road as the blown snow must be clean and free of debris.
3. Snow removal from the Itivia Diesel Tank Farm secondary contaminant area must not be done using heavy equipment as to not damage the installed synthetic liner.
4. Snow accumulated in the Gas Boy secondary containment is to be removed using suitable equipment, to maintain capacity for fuel spill mitigation. Diesel contaminated snow will be disposed of appropriately at the snow cell or landfarm.

Appendix:

Figure 1: Authorized Snow Removal and Snow Storage Areas




Figure 2: Exploration Camp Snow Pad Area and No Plow Zone Example





Figure 3: Snow removal from between camp accommodation trailers





Figure 4: Itivia Snow Pad Area and ATV Access Trail



Authorization (Print Name)	
Approved: _____ Name JOHSC Worker Rep.	Date: _____
Approved: _____ Name Department Superintendent / Delegate	Date: _____
Approved: _____ Name Health & Safety Superintendent / Delegate	Date: _____

**APPENDIX C • WATER BALANCE AND WATER QUALITY FORECAST (GOLDER,
2020)**



REPORT

Meliadine Site Water Balance and Water Quality Model

Type A 2AM-MEL1631 Water Licence Amendment

Submitted to:

Agnico Eagle Mines Limited

11600, rue Louise-Bisson
Mirabel, Quebec, Canada J7N 1G9

Submitted by:


Golder Associates Ltd.

1931 Robertson Road, Ottawa, Ontario, K2H 5B7, Canada

+1 613 592 9600

20144940-779-RPT-Rev1

21 August 2020



Distribution List

1 eCopy: Agnico Eagle Mines Limited

1 eCopy: Golder Associates Ltd.

Table of Contents

1.0	INTRODUCTION	1
1.1	Project Description	1
1.2	Scope Description	1
1.3	Project Overview	1
2.0	SITE WATER BALANCE AND WATER QUALITY MODEL	3
2.1	Water Management.....	3
2.1.1	Process Water Management	11
2.1.2	Freshwater Consumption.....	11
2.2	Model Inputs and Assumptions	11
2.2.1	General Water Balance Inputs and Assumptions	12
2.2.2	General Water Quality Inputs and Assumptions.....	12
2.2.2.1	Water Quality Inputs	13
2.2.2.2	Initial Conditions.....	13
2.2.2.3	Model Inputs and Assumptions.....	13
2.2.2.4	TDS Loadings from Underground Run of Mine	14
3.0	RESULTS AND DISCUSSION	14
3.1	Average Year (Base Case) Scenario	14
3.1.1	CP2, CP3, CP4, CP5, and CP6.....	14
3.1.2	P-Area Ponds.....	18
3.1.3	Open Pits	18
3.1.4	CP1 and EWTP.....	20
3.2	Wet Years Scenario	22
3.2.1	CP2, CP3, CP4, CP5, and CP6.....	22
3.2.2	P-Area Ponds.....	26
3.2.3	Open Pits	27
3.2.4	CP1 and EWTP.....	29
4.0	CONCLUSIONS	31

4.1	Uncertainty	31
5.0	LIMITATIONS.....	32
6.0	REFERENCES	33

TABLES

Table 1:	Modelled Constituents and Comparative Guidelines	3
Table 2:	Annual discharge from CP2, CP3, CP4, CP5, and CP6 (average year scenario) - m ³ /yr	14
Table 3:	Maximum and mean monthly discharge from CP2, CP3, CP4, CP5, and CP6 (average year scenario) - m ³ /month	15
Table 4:	Annual contact water discharge from Tiri-1 and Tiri-2 to CP5 (average year scenario) - m ³ /yr.....	19
Table 5:	Monthly contact water discharge from Tiri-1 and Tiri-2 to CP5 (average year scenario) - m ³ /month	19
Table 6:	Annual discharge from CP1 to EWTP (average year scenario) - m ³ /yr	20
Table 7:	Monthly discharge from CP1 to EWTP (average year scenario) - m ³ /month.....	21
Table 8:	Annual discharge from CP2, CP3, CP4, CP5, and CP6 (wet years scenario)- m ³ /yr	23
Table 9:	Maximum and mean monthly discharge from CP2, CP3, CP4, CP5, and CP6 (wet year scenario) - m ³ /month	24
Table 10:	Annual contact water discharge from Tiri-1 and Tiri-2 (wet years scenario) - m ³ /yr	27
Table 11:	Monthly contact water discharge from Tiri-1 and Tiri-2 to CP5 (wet year scenario) - m ³ /month.....	28
Table 12:	Annual discharge from CP1 to EWTP (wet years scenario) - m ³ /yr	29
Table 13:	Monthly discharge from CP1 to EWTP (wet year scenario) - m ³ /month	29

FIGURES

Figure 1:	Meliadine Site Layout - Ultimate Configuration	2
Figure 2:	2020 Contact Water Management	5
Figure 3:	2021 Contact Water Management	6
Figure 4:	2022 and 2023 Contact Water Management	7
Figure 5:	2024 Contact Water Management	8
Figure 6:	2025 and 2026 Contact Water Management	9
Figure 7:	2027 Contact Water Management	10
Figure 8:	Projected TDS concentrations in the CPs (average year scenario).....	17
Figure 9:	Projected TDS concentrations in the P-Area (average year scenario)	18
Figure 10:	Projected TDS concentrations in the open pits (average year scenario).....	20

Figure 11: Projected TDS concentrations in CP1 and through the EWTP (average year scenario).....	22
Figure 12: Projected TDS concentrations in the CPs (wet years scenario)	26
Figure 13: Projected TDS concentrations in the P-Area (wet years scenario).....	27
Figure 14: Projected TDS concentrations in the open pits (wet years scenario)	28
Figure 15: Projected TDS concentrations in CP1 and through the EWTP (wet years scenario)	30
Figure 16: Projected TDS concentrations in CP1 for an average year (base case) scenario, and a wet years scenario.....	30

APPENDICES

APPENDIX A

Environmental Design Inputs and Assumptions

APPENDIX B

Tabulated Water Balance Results, Average Year (Base Case) Scenario

APPENDIX C

Average Monthly Concentrations, Average Year (Base Case) Scenario

APPENDIX D

Tabulated Water Balance Results, Wet Years Scenario

APPENDIX E

Average Monthly Concentrations, Wet Years Scenario

1.0 INTRODUCTION

1.1 Project Description

Agnico Eagle Mines Limited (Agnico Eagle) is operating the Meliadine Gold Project (the Project), located approximately 25 kilometres (km) north of Rankin Inlet, and 80 km southwest of Chesterfield Inlet in the Kivalliq Region of Nunavut. The mine plan proposes open pit and underground mining methods for the development of the Tiriganiaq gold deposit, with two open pits including Tiriganiaq Pit 1 (Tiri-1) and Tiriganiaq Pit 2 (Tiri-2), and one underground mine.

1.2 Scope Description

In May 2020, Golder Associates Ltd. (Golder) was retained to update the predictions of site and downstream water balance and water quality for the Project in support of the 2020 Water Licence Amendment. The scope of work addresses the operational period (i.e., May 2020 through December 2028) for two scenarios, including an average climate (base case) scenario and a wet climate scenario, applied to the critical water management years, using a water balance and water quality model. Although the water balance and water quality model includes all relevant site infrastructure and water management ponds, results are explicitly reported herein for the following locations:

- Containment Ponds: CP1, CP2, CP3, CP4, CP5, and CP6
- P-Area Ponds (year 2020 only)
- Open Pits: Tiri-1 and Tiri-2 (note that Tiri-2 is used for saline water storage from the Underground as of 2022)
- Influent and effluent from the Effluent Water Treatment Plant (EWTP)

This water balance and water quality report is focussed only on surface contact water management.

1.3 Project Overview

The Project for the 2020 Water Licence Amendment consists of mining of the Tiriganiaq gold deposit using a traditional open-pit mining method and underground mining. The ultimate site layout is shown in Figure 1.

The Mine Plan (V11_3) includes two open pits (Tiri-1 and Tiri-2) and one underground mine (Tiriganiaq underground mine) for the development of the Tiriganiaq gold deposit. The Project is expected to produce approximately 15.4 million tonnes (Mt) of ore, 31.4 Mt of waste rock, 7.0 Mt of overburden waste, and 15.4 Mt of tailings (Agnico Eagle 2020a). Waste will be stored on site in a dry stack tailings storage facility (TSF) and two waste rock storage facilities (WRSFs).




Figure 1: Meliadine Site Layout - Ultimate Configuration

2.0 SITE WATER BALANCE AND WATER QUALITY MODEL

2.1 Water Management

Water management at the site is described in the Water Management Plan (Agnico Eagle 2020b). The water management objectives are to minimize potential impacts of the Project to the quantity and quality of surface water at the mine site and the receiving environment. Water management structures (e.g., water retention dikes/berms, pumps and pipelines, and diversion channels) will be constructed as needed to manage contact water from areas within the mine site.

During mine operations, contact water originating from developed areas on the surface will be intercepted and conveyed to the various collection ponds for temporary storage. All contact water is eventually conveyed to CP1. Contact water from CP5 undergoes reverse osmosis (RO) treatment prior to discharge to CP1 if total dissolved solid (TDS) levels exceed 3,500 milligrams per litre (mg/L). From CP1, contact water is routed through the EWTP for treatment of Total Suspended Solids (TSS) and discharged to the receiving environment.

CP1 has a storage capacity of approximately 742,000 cubic metres (m³) at its design maximum operating water level (Agnico Eagle 2020b). The EWTP has an assumed treatment rate of 22,000 cubic metres per day (m³/d) during the open water season (June – September).

Treated discharge from CP1 must meet the regulated discharge criteria provided in Table 1, as per the current Water Licence.

Table 1: Modelled Constituents and Comparative Guidelines

Constituent Group	Regulated Constituents	Surface Contact Water Discharge Criteria (at End of Pipe) (mg/L)
Conventional	Total Dissolved Solids	3,500 ^a
Nutrients	Total Phosphorus	2
	Total Ammonia as Nitrogen	14
Metals	Aluminum	2.0 ^b
	Arsenic	0.3 ^b
	Copper	0.2 ^b
	Nickel	0.5 ^b
	Lead	0.2 ^b
	Zinc	0.4 ^b

^a – Proposed TDS discharge criterion of maximum average concentration (WQ-MOP Rev2a, Golder 2020)

^b – Guideline applies to total concentration; total projected concentrations for metals are limited to the EWTP discharges. The total concentrations are estimated from the modelled EWTP dissolved metal results by adding a particulate fraction to the dissolved concentrations, assuming TSS concentrations (15 mg/L) described in Table 12 of Appendix A using site monitoring data in CP1.

Cyanide and total petroleum hydrocarbons were not included in the water quality model. Cyanide is expected to be largely destroyed by the cyanide destruction process and is mostly undetected throughout the site. Total petroleum hydrocarbons have not been modelled; these constituents do not behave conservatively and each of the varying fractions of TPH behave differently compared to other modelled constituents (e.g., they do not mix within a receiving waterbody). TPH are also often localised at and/or limited to their source, if present, because they are regulated at the source and therefore not usually detected in receiving environments above typical regulated discharge limits (i.e., 5 mg/L).

Flow diagrams for contact water are shown in Figure 2 to Figure 7.




Figure 2: 2020 Contact Water Management




Figure 3: 2021 Contact Water Management




Figure 4: 2022 and 2023 Contact Water Management




Figure 5: 2024 Contact Water Management




Figure 6: 2025 and 2026 Contact Water Management




Figure 7: 2027 Contact Water Management

2.1.1 Process Water Management

The process water reporting to CP3 from the TSF is the main source of arsenic to surface contact water that is managed at the mine. This arsenic transfer from process water to contact water is minimized by the dewatering of the tailings prior to placement in the TSF. Furthermore, freezing of the tailings is the primary mitigation strategy to minimize impact of seepage on the quality of the contact water collected in CP3.

2.1.2 Freshwater Consumption

Freshwater usage for the Project includes potable water supply, fire suppression, make-up water for the mill, and other operational requirements, such as drilling water, batch plant use, and use at the wash bay. The main freshwater sources are Meliadine Lake and Lake A8. Intakes at these sources include an intake housed within a rockfill causeway located northeast of the industrial pad in Meliadine Lake and an additional freshwater intake pump located at Lake A8. The water balance does not consider the use of CP1 water in the process plant. Freshwater requirements for the Project used in the assessment are presented in Appendix A.

2.2 Model Inputs and Assumptions

The water balance and water quality model was completed in Excel and run on a monthly timestep. The model provides results for operations, from May 2020 until December 2028. For each inflow to a facility that is modelled, a corresponding water quality is assigned, or an overall facility mass load release is assigned. These flows are then mixed, and a resulting water quality is calculated. The following facilities were incorporated into the model:

- Containment Ponds: CP1, CP2, CP3, CP4, CP5, and CP6
- Open Pits: Tiri-1 and Tiri-2 (note that Tiri-2 is used for saline water storage from the Underground as of 2022)
- Tiriganiaq Underground
- P-Area (note that this area is fully decommissioned prior to freeze up in 2020)
- WRSF 1 and WRSF 3
- Ore Piles 2 and 2-ext
- Constructed pads (camp site, laydown areas)
- Landfill, landfarm, and landfarm extension areas
- TSF
- EWTP (maximum treatment capacity of 22,000 m³/d)

Predictive water balance and water quality results were specifically generated for the Containment Ponds, Open Pits, P-Area, and the EWTP.

2.2.1 General Water Balance Inputs and Assumptions

Water balance inputs are provided in Appendix A. These include:

- Initial conditions (i.e., pond water levels)
- Freshwater/consumptive flows
- Water treatment rates
- Pond elevation-area-storage curves
- Watershed and facility footprint areas

The annual areas are based on available layouts for years 2020 (i.e., Year 1) and 2027 (i.e., Year 8). For the years in between, it was assumed that a facility's ultimate footprint would be constructed in its first year of operation.

- Climate and runoff data (i.e., monthly precipitation and runoff coefficients)

The water balance was developed to simulate average and 100-year wet year precipitation conditions. The monthly precipitation under these conditions was derived from baseline climate data provided by Okane Consultants Inc. (OKC) based on data from Rankin Inlet and site data (OKC 2020). For this assessment, two scenarios were considered:

- 1) Average precipitation: Under this scenario, average monthly precipitation was assumed throughout operations
- 2) Wet Year precipitation: Under this scenario, 100-year wet precipitation was assumed for years 2020 (i.e., Year 1, the year with the most natural runoff to the contact water management system since the WRSFs are not fully developed) and 2025 (i.e., Year 6, a year with the ultimate layout – CP2 and the full WRSF footprint are online). Average monthly precipitation was assumed for all other operations years.

2.2.2 General Water Quality Inputs and Assumptions

General water quality inputs and assumptions are described in this section. For a more detailed description of the inputs and assumptions, please refer to Appendix A.

The water quality model provides predictions for the following regulated constituents:

- Conventional constituents: TDS
- Nutrients: Total dissolved phosphorus and total ammonia
- Dissolved metals: Aluminum, arsenic, copper, lead, nickel, and zinc

In addition, concentrations of total phosphorus, aluminum, arsenic, copper, lead, nickel, and zinc were calculated only for the EWTP. Total concentrations were estimated from the modelled EWTP dissolved metal results by adding a particulate fraction to the dissolved concentrations, assuming TSS concentrations (15 mg/L) as described in Appendix A and using site monitoring data from CP1.

2.2.2.1 *Water Quality Inputs*

The following source terms were included in the water quality model:

- Natural runoff to site
- Disturbed runoff to site
- Direct precipitation
- Sewage Treatment Plant (STP) effluent
- Landfill runoff
- Landfarm runoff
- WRSF runoff
- Ore stockpile runoff
- TSF runoff and seepage
- Pit wall runoff
- TDS flush of surface piles and constructed pads containing underground material

2.2.2.2 *Initial Conditions*

Initial conditions were represented by monitoring data obtained from site as described in Appendix A. Monitoring data for May 2020 were used for collection ponds where available. Where monitoring data were not available for May 2020, initial concentrations were estimated based on concentrations prior to freeze up in 2019.

2.2.2.3 *Model Inputs and Assumptions*

Model inputs and assumptions are presented in Appendix A. These include:

- Details of source term derivations
- Details of initial condition derivations
- TSS concentration assumptions
- Particulate fraction concentrations for calculation of total concentrations
- Treatment parameters (EWTP)
- Proportions of waste rock, ore, and tailings originating from each pit and the underground
- Lithological proportions of waste rock
- Lithological proportions of exposed pit wall areas

Material loading rates were calculated based on assumed material properties and were scaled to field conditions in a manner consistent with previous water quality modelling assessments for the Project.

2.2.2.4 TDS Loadings from Underground Run of Mine

Additional TDS loadings from underground run of mine (ROM) are accounted for in the model, and consider underground TDS sources throughout the production of the ROM. Constructed pads conservatively reflect some additional TDS concentrations contained within the pore spaces, and waste rock piles and ore stockpiles reflect observed natural groundwater TDS concentrations contained within the pore spaces.

3.0 RESULTS AND DISCUSSION

A summary of the results is presented below. For context, the modelled water quality results for regulated constituents are compared to the water licence discharge criteria applied to CP1 for discharge to Meliadine Lake; however, it should be noted that these criteria do not apply to water transfers within the site and are only applicable at end of pipe following treatment through the EWTP.

Detailed monthly water balance results for the average and wet years scenarios are presented in tabular form in Appendices B and D, respectively. Detailed monthly average water quality model results for the average and wet years scenarios are presented in Appendices C and E, respectively. The results are summarized below.

3.1 Average Year (Base Case) Scenario

3.1.1 CP2, CP3, CP4, CP5, and CP6

The derived annual and monthly discharges from the CPs to CP1 under average precipitation conditions are shown in Table 2 and Table 3. The maximum monthly discharge occurs in June. It is assumed that pumping to CP1 begins mid-June. Note that there is no discharge associated with CP2 until it comes online in 2024 (see Figures 5 to Figure 7).

Table 2: Annual discharge from CP2, CP3, CP4, CP5, and CP6 (average year scenario) - m³/yr

Year	CP2	CP3	CP4	CP5	CP6
2020	0	57,532	51,534	103,828	27,297
2021	0	57,532	41,684	154,416	27,297
2022	0	57,532	31,833	120,094	27,297
2023	0	57,532	31,833	134,487	27,297
2024	94,904	57,532	31,833	107,156	27,728
2025	94,904	57,532	31,833	112,852	27,728
2026	94,904	57,532	31,833	129,426	27,728
2027	94,904	57,532	31,833	90,484	27,728
2028	94,904	57,532	31,833	90,484	27,728

Note:

CP2 becomes operational in 2024.

Table 3: Maximum and mean monthly discharge from CP2, CP3, CP4, CP5, and CP6 (average year scenario) - m³/month

Year	CP2		CP3		CP4		CP5		CP6	
	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge
2020	0	0	26,754	11,506	26,291	10,307	47,026	20,766	15,887	5,546
2021	0	0	26,754	11,506	21,594	8,337	75,494	30,883	15,887	5,546
2022	0	0	26,754	11,506	16,898	6,367	53,344	24,019	15,887	5,546
2023	0	0	26,754	11,506	16,898	6,367	59,794	26,897	15,887	5,546
2024	49,031	18,981	26,754	11,506	16,898	6,367	45,794	21,431	15,887	5,546
2025	49,031	18,981	26,754	11,506	16,898	6,367	46,734	22,570	15,887	5,546
2026	49,031	18,981	26,754	11,506	16,898	6,367	55,965	25,885	15,887	5,546
2027	49,031	18,981	26,754	11,506	16,898	6,367	46,734	18,097	15,887	5,546
2028	49,031	18,981	26,754	11,506	16,898	6,367	46,734	18,097	15,887	5,546

Note:

Mean monthly discharge values reflect the mean flows from June to September (i.e. the non-winter months). The discharge is zero for the other months.

CP2 becomes operational in 2024.

Projected TDS concentrations of contact water in the CPs (Figure 8) show decreasing trends in 2020, as the higher TDS contact water that was present in 2019 is replaced by inflows possessing lower TDS contact water. Steady state TDS concentrations are projected to be below 300 mg/L, reflecting appropriate management of material sourced from underground operations (it is anticipated that much of the waste rock sourced from underground will be used as cemented paste backfill, thereby minimizing the TDS loadings at surface). CP6 shows a more gradual decreasing trend, attributed to proportionally less natural runoff than other CPs, and a slight increase in 2024 – 2026, which is due to changing proportions of overburden versus waste rock and to a small volume of underground waste rock placed in WRSF 3 in 2025. As noted above, CP2 is initiated in 2024 and therefore does not have any water quality projections prior to 2024.

Projected total dissolved phosphorus in the CPs (Appendix C) ranges from approximately 0.01 mg/L to 0.16 mg/L after 2020. For context, all projected total dissolved phosphorus concentrations in the CPs remain below the water licence discharge limit that is applied to CP1.

Projected total ammonia in the CPs (Appendix C) ranges from approximately 2 mg N/L to 25 mg N/L after 2020. CP5 experiences an initial decrease in projected total ammonia concentrations and ranges between 2.0 mg/L and 7.0 mg/L thereafter, until 2027 and 2028, when it decreases to approximately 2.0 mg/L due to the ceasing of pumping from Tiri-1. All projected total ammonia concentrations in the CPs remain below the water licence discharge limit applied to CP1, with the exception of CP6 due to runoff from WRSF 3.

Projected dissolved metal concentrations (Appendix C) generally show more variability between the CPs throughout operations as lithological proportions change in the stockpiled waste rock and as waste rock runoff concentrations are influenced by varying volumes of runoff over the summer. CP5 shows a departure from the trends of metal concentrations in 2027 and 2028; this is due to cessation of pumping from Tiri-1 to CP5, resulting in other inflow sources (e.g., runoff from WRSF 1) having more influence on the metals mass entering CP5. Dissolved metal concentrations in the CPs remain below their respective discharge criteria that are applied to CP1; the addition of respective particulate metal fractions is not expected to adversely affect resulting total metals concentrations, except total arsenic. Maximum total arsenic concentrations in CP3, which receives surface runoff from the TSF, remain slightly above the discharge criterion (maximum concentrations reach approximately 0.36 mg/L in 2021/2022) for the length of operations.

Site observations on and surrounding the TSF in 2020 indicate that there is potential for an increased amount of TDS to reach CP3 via the runoff from the TSF. As limited monitoring data are available at this point, this is not currently predicted by the model; however, continued monitoring of the TSF will inform the model for future iterations.




Figure 8: Projected TDS concentrations in the CPs (average year scenario)

3.1.2 P-Area Ponds

The P-Area is planned to remain operational until October 2020, after which this area and the three P-Area ponds will be decommissioned. The Laydown Area will then be located in the footprint of the P-Area as shown in Figure 1. For modelling purposes, the three P-Area ponds were modelled as one single pond. Assuming average precipitation conditions, 21,180 m³ was estimated to be pumped from the P-Area to CP5 in 2020 prior to the P-Area decommissioning in October.

The P-Area ponds TDS concentrations for May and June were calibrated to observed site conditions for TDS; other constituents were calculated based on measured concentrations in October 2019 (discussed in Appendix A). Historically, the P-Area ponds were used to provide some additional storage for excess water originating from the underground operations. This practice ceased in 2019, and it is not anticipated that any water from the underground operations will be stored in the P-Area ponds in 2020. Therefore, the only other anticipated inflows to the P-Area in 2020 are natural catchment runoff and direct precipitation. Projected TDS concentrations (Figure 9) show a sharp decrease as the ponds are pumped to CP5; during August to October, the only inputs to these ponds are primarily catchment runoff.




Figure 9: Projected TDS concentrations in the P-Area (average year scenario)

Projected total dissolved phosphorus, total ammonia, and metal concentrations (Appendix C) are variable until decommissioning and are reflective of disturbed area runoff inflows. Projected concentrations remain below respective water licence discharge criteria that apply to CP1, except for total ammonia at the start of 2020 pumping to CP5, which is initially higher than the CP1 discharge criterion.

3.1.3 Open Pits

Surface water and other inflows collecting in the Tiri-1 pit are pumped to CP5. Inflows accumulating in Tiri-2 pit are also pumped to CP5 until this pit is required for saline water management in 2021. The derived annual and maximum monthly discharges from the pits to CP5 under average precipitation conditions are shown in Table 4 and Table 5.

Table 4: Annual contact water discharge from Tiri-1 and Tiri-2 to CP5 (average year scenario) - m³/yr

Year	Tiri-1	Tiri-2
2020	0	10,056
2021	62,943	0
2022	31,703	0
2023	46,096	0
2024	18,765	0
2025	22,368	0
2026	38,943	0
2027	0	0
2028	0	0

Table 5: Monthly contact water discharge from Tiri-1 and Tiri-2 to CP5 (average year scenario) - m³/month

Year	Tiri-1		Tiri-2	
	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge
2020	0	0	3,236	2,514
2021	28,376	12,589	0	0
2022	7,550	6,341	0	0
2023	14,000	9,219	0	0
2024	6,455	4,691	0	0
2025	7,355	5,592	0	0
2026	9,231	7,789	0	0
2027	0	0	0	0
2028	0	0	0	0

Note:

Mean monthly discharge values reflect the mean flows from June to September (i.e. the non-winter months). The discharge is zero for the other months.

The open pit sumps collect primarily pit wall runoff and watershed runoff. Additionally, Tiri-2 collects runoff from a small temporary waste rock pile. Projected maximum TDS concentrations in the pits (Figure 10) approach 50 mg/L but are variable throughout the summer months. It is assumed that inflows to the pits during the winter months are negligible and there is no accumulation of volume or water pumped to CP5; therefore, the concentrations over the winter months are assumed to be zero. After 2027, when mining ceases and the pit begins accumulating backfilling volume, Tiri-1 shows a steady-state TDS concentration of approximately 20 mg/L.




Figure 10: Projected TDS concentrations in the open pits (average year scenario)

Projected total dissolved phosphorus concentrations in the open pits (Appendix C) show a similarly varying trend and reach maximum concentrations of approximately 0.030 mg/L. Total ammonia concentrations in the open pits are assumed to consistently be 13 mg N/L (see Appendix A) over the length of operations, and represent residual blasting products.

Projected metal concentrations in the open pits show similar trends to TDS (Appendix C) and for the regulated metals do not exceed their respective discharge criteria as applied to CP1.

3.1.4 CP1 and EWTP

All surface contact water from site is ultimately pumped to CP1 and treated through the EWTP prior to discharge to Meliadine Lake. The derived annual and maximum monthly discharges from CP1 under average precipitation conditions are shown in Table 6 and Table 7. It is assumed that pumping to the EWTP occurs from mid June to October. The maximum treatment rate occurs in June.

Table 6: Annual discharge from CP1 to EWTP (average year scenario) - m³/yr

Year	CP1
2020	883,631
2021	634,507
2022	598,209
2023	599,536
2024	653,135
2025	674,411
2026	689,621
2027	689,621
2028	701,173

Table 7: Monthly discharge from CP1 to EWTP (average year scenario) - m³/month

Year	CP1	
	Max Monthly Discharge	Mean Monthly Discharge
2020	384,180	210,968
2021	302,927	158,627
2022	275,162	149,552
2023	281,612	149,884
2024	316,826	163,284
2025	317,767	168,603
2026	326,998	172,405
2027	317,767	166,746
2028	317,767	163,622

Note:

Mean monthly discharge values reflect the mean flows from June to September (i.e. the non-winter months). The discharge is zero for the other months.


The modelled water quality in EWTP is reflective of the water quality in CP1. The EWTP treats water to be discharged from CP1 for TSS. As the discharge criterion for TSS is 15 mg/L, discharge assumes a TSS concentration equivalent to this criterion. This assumption is conservative, as discharge from the EWTP to Meliadine Lake is measured consistently below 15 mg/L. Total constituent concentrations, as applicable, in discharge from the EWTP accounting for the addition of a particulate fraction associated with 15 mg/L TSS, are presented in Appendices C and E.

Projected TDS concentrations in CP1 and treated through the EWTP (Figure 11) show a decrease over operations (to 2028), following the discharge of elevated-TDS contact water in 2020. It is assumed that there is no reworking of underground waste rock containing pore water with elevated TDS, and that TDS contained in the pore water of constructed pads, underground waste rock, or underground ore, continues to deplete over time. Steady state TDS concentrations in CP1 and the EWTP are projected to be approximately 250 to 400 mg/L and remain well below the discharge criterion.

Total phosphorus concentrations in CP1 and total phosphorus concentrations in the EWTP (Appendix C) are projected to reach a steady state concentration between approximately 0.5 mg/L (summer months) and 0.9 mg/L (over winter), respectively, and remain below the CP1 discharge limit. Projected concentrations in CP1 show an increasing trend over the winter months; this is due to the STP effluent, which has higher concentrations of total dissolved phosphorus than other inflow sources, as in winter conditions it is the only inflow source to CP1.

Total ammonia concentrations in CP1 and the EWTP (Appendix C) are projected to reach a steady state concentration of approximately 4.0 to 5.0 mg N/L and remain below the CP1 discharge limit. Projected concentrations in CP1 show a decreasing trend over the winter months as the STP effluent, which has lower concentrations of ammonia than the pond, is the only inflow source to CP1.

Projected metal concentrations in CP1 and the EWTP (Appendix C) show one of two trends: concentrations decrease over operations, reaching steady state conditions around 2024 (like TDS), or display steady state conditions immediately in 2020. All regulated dissolved and total metals remain below their respective discharge criteria.



Note: The red dashed line represents the proposed TDS discharge criterion of maximum average concentration (WQ-MOP Rev2a, Golder 2020).

Figure 11: Projected TDS concentrations in CP1 and through the EWTP (average year scenario)

3.2 Wet Years Scenario

Based on the results of the average year presented in the previous section, the water balance was re-run assuming 100-year wet year precipitation conditions for years 2020 (Year 1) and 2025 (Year 6), and average precipitation conditions for the other mine years. The results are presented below.

3.2.1 CP2, CP3, CP4, CP5, and CP6

The annual and maximum monthly discharges from the CPs to CP1 under the wet years scenario are shown in Table 8 and Table 9. The maximum monthly discharge occurs in June. It is assumed that pumping to CP1 begins mid-June. Under the 100-year wet years scenario, the monthly discharges (Table 5) remain within the maximum design discharges presented in Appendix A.

Table 8: Annual discharge from CP2, CP3, CP4, CP5, and CP6 (wet years scenario)- m³/yr

Year	CP2	CP3	CP4	CP5	CP6
2020	0	85,951	77,135	163,747	40,858
2021	0	57,532	41,684	154,416	27,297
2022	0	57,532	31,833	120,094	27,297
2023	0	57,532	31,833	134,487	27,297
2024	94,904	57,532	31,833	107,156	27,728
2025	142,050	85,951	47,647	191,884	41,502
2026	94,904	57,532	31,833	129,426	27,728
2027	94,904	57,532	31,833	90,484	27,728
2028	94,904	57,532	31,833	90,484	27,728

Note:

CP2 becomes operational in 2024.

Table 9: Maximum and mean monthly discharge from CP2, CP3, CP4, CP5, and CP6 (wet year scenario) - m³/month

Year	CP2		CP3		CP4		CP5		CP6	
	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge
2020	0	0	40,012	17,190	39,352,	15,427	73,336,	32,749	23,505	8,172
2021	0	0	26,754	11,506	21,594	8,337	75,494	30,883	15,887	5,546
2022	0	0	26,754	11,506	16,898	6,367	53,344	24,019	15,887	5,546
2023	0	0	26,754	11,506	16,898	6,367	59,794	26,897	15,887	5,546
2024	49,031	18,981	26,754	11,506	16,898	6,367	45,794	21,431	15,887	5,546
2025	73,388	28,410	40,012	17,190	25,293	9,529	82,542	38,377	23,780	8,300
2026	49,031	18,981	26,754	11,506	16,898	6,367	55,965	25,885	15,887	5,546
2027	49,031	18,981	26,754	11,506	16,898	6,367	46,734	18,097	15,887	5,546
2028	49,031	18,981	26,754	11,506	16,898	6,367	46,734	18,097	15,887	5,546

Note:

Mean monthly discharge values reflect the mean flows from June to September (i.e. the non-winter months). The discharge is zero for the other months.

CP2 becomes operational in 2024.

Projected TDS concentrations in the CPs (Figure 12) show similar trends as the average year scenario projections but with lower concentrations for 2020 and 2025 when the wet years are applied. This is due to an increase in site runoff volume relative to the mass released. After 2020, TDS concentrations are projected to remain below 300 mg/L.

Projected total dissolved phosphorus in the CPs (Appendix C) ranges from approximately 0.01 mg/L to 0.16 mg/L after 2020. All projected total dissolved phosphorus concentrations in the CPs remain below the water licence discharge criterion for total phosphorus applied to CP1.

Projected total ammonia in the CPs (Appendix E) ranges from approximately 2 mg N/L to 25 mg N/L after 2020. Concentrations in the wet years are lower in the CPs compared to the base case scenario due to an increase in surface water volume with relatively similar residual blasting residual load to that in the base case. Similar to the base case scenario, all projected total ammonia concentrations in the CPs remain below the water licence discharge criterion applied to CP1, with the exception of CP6.

Projected dissolved metal concentrations (Appendix E) show similar trends and ranges as the average year (base case) scenario; however, due to increased surface water volumes on the mine site associated with runoff associated with the wet years scenario, a marked decrease in metals concentrations is modelled in 2020 and 2025. As with the average year scenario, dissolved arsenic in CP3 remains slightly above the regulated CP1 discharge criterion.




Figure 12: Projected TDS concentrations in the CPs (wet years scenario)

3.2.2 P-Area Ponds

Under the 100-year wet years scenario, 27,770 m³ was estimated to be pumped from the P-Area to CP5 in 2020 prior to the P-Area decommissioning in October.

Projected TDS concentrations (Figure 13) show an initial sharp decrease to about 3,000 mg/L for the months calibrated to existing 2020 data (i.e., to June 2020), followed by an increase to approximately 5,000 mg/L between July and August. After August, projected TDS concentrations decrease sharply in September and October.

Projected total phosphorus, total ammonia, and metal concentrations show similar trends. The total ammonia decreases below the regulated CP1 discharge criterion through the summer, and total dissolved phosphorus and metal concentrations remain consistently below the respective discharge criteria applied to CP1 (Appendix E).




Figure 13: Projected TDS concentrations in the P-Area (wet years scenario)

3.2.3 Open Pits

The annual and maximum monthly discharges from the pits to CP5 under the wet year scenario are shown in Table 10 and Table 11.

Table 10: Annual contact water discharge from Tiri-1 and Tiri-2 (wet years scenario) - m³/yr


Year	Tiri-1	Tiri-2
2020	0	27,321
2021	62,943	0
2022	31,703	0
2023	46,096	0
2024	18,765	0
2025	56,449	0
2026	38,943	0
2027	0	0
2028	0	0

Table 11: Monthly contact water discharge from Tiri-1 and Tiri-2 to CP5 (wet year scenario) - m³/month

Year	Tiri-1		Tiri-2	
	Max Monthly Discharge	Mean Monthly Discharge	Max Monthly Discharge	Mean Monthly Discharge
2020	0	0	7,160	5,464
2021	28,376	12,589	0	0
2022	7,550	6,341	0	0
2023	14,000	9,219	0	0
2024	6,455	4,691	0	0
2025	13,604	11,290	0	0
2026	9,231	7,789	0	0
2027	0	0	0	0
2028	0	0	0	0

Note:

Mean monthly discharge values reflect the mean flows from June to September (i.e. the non-winter months). The discharge is zero for the other months.

**Figure 14: Projected TDS concentrations in the open pits (wet years scenario)**

Projected maximum concentrations of TDS and its annual variability in the open pits (Figure 14) are similar to the average year scenario. Due to the increased runoff volume comprising pit wall inflows to Tiri-1 in 2025, maximum TDS concentrations are projected to approximate 70 to 75% of the concentrations in wet years.

Projected total dissolved phosphorus, total ammonia, and metal concentrations show similar trends as TDS, with projected maximum concentrations and their annual variability in the open pits similar to the average year scenario. As noted for TDS, total ammonia and metal concentrations decrease during the wet year of 2025 (Appendix E).

3.2.4 CP1 and EWTP

The annual and maximum monthly discharges from CP1 under the wet years scenario are shown in Table 12 and Table 13. It is assumed that pumping to the EWTP occurs from mid June to October. The maximum treatment rate occurs in June.

Table 12: Annual discharge from CP1 to EWTP (wet years scenario) - m³/yr

Year	CP1
2020	1,052,493
2021	717,659
2022	598,209
2023	599,536
2024	653,135
2025	914,662
2026	783,168
2027	666,985
2028	654,486

Table 13: Monthly discharge from CP1 to EWTP (wet year scenario) - m³/month


Year	CP1	
	Max Monthly Discharge	Mean Monthly Discharge
2020	529,904	330,000
2021	302,927	158,627
2022	275,162	149,552
2023	281,612	149,884
2024	316,826	163,284
2025	485,855	228,665
2026	326,998	195,792
2027	317,767	166,746
2028	317,767	163,622

Note:

Mean monthly discharge values reflect the mean flows from June to September (i.e. the non-winter months). The discharge is zero for the other months.


Similar to the average year scenario, projected TDS concentrations in CP1 and through the EWTP (Figure 15) show a decreasing trend beginning in 2020 to 2021. Figure 16 illustrates the differences in projected TDS concentrations in CP1 between the average year (base case) scenario and the wet years scenario. Due to the increased disturbed area runoff in the wet years and an increase in mass load from other sources, such as the ore stock pile due to a proportionally higher amount of underground material compared to pit material, projected TDS concentrations remain slightly higher in the wet years scenario than the average year scenario. Projected TDS concentrations in CP1 and the EWTP range from approximately 400 mg/L to 1,600 mg/L.

Projected total dissolved phosphorus, total ammonia, and metal concentrations (Appendix E) are similar to the average year scenario projections; however, there is a decrease in concentrations for 2020 and 2025 (the applied wet years). Total phosphorus, total ammonia, and all dissolved and total metals concentrations remain below the regulated CP1 discharge limits.



Note: The red dashed line represents the proposed TDS discharge criterion of maximum average concentration (WQ-MOP Rev2a, Golder 2020).

Figure 15: Projected TDS concentrations in CP1 and through the EWTP (wet years scenario)



Note: The red dashed line represents the proposed TDS discharge criterion of maximum average concentration (WQ-MOP Rev2a, Golder 2020).

Figure 16: Projected TDS concentrations in CP1 for an average year (base case) scenario, and a wet years scenario.

4.0 CONCLUSIONS

Under both the average and wet years scenarios, surface contact water on site can be managed within the design discharge rates and capacities for the various CPs.

The primary objective of the water balance and water quality model is to project the potential volumes and quality of the effluent that will be discharged to Meliadine Lake. Under the average year and wet years scenarios, modelled concentrations of the regulated constituents (i.e., TDS, total phosphorus, total ammonia, aluminum, arsenic, copper, nickel, lead, and zinc) in CP1 are expected to be appropriate for discharge to Meliadine Lake (i.e., meet regulated discharge criteria) and therefore remain aligned with the conclusions of the Final Environmental Impact Statement that no adverse risk to the receiving environment is to be expected. The updated modelling also projects that TDS in the surface contact water will decrease over the life of mine as the TDS currently available from underground ROM is flushed out. Although flows from each of the contact water sources are sensitive to TDS concentrations in the runoff, this variability appears to be generally attenuated by the volume in CP1. Nevertheless, it will be important to empty CP1 prior to the end of the discharge season, and maintain options to discharge in early spring, to mitigate the risk of encountering issues related to storage of surface contact water in CP1.

4.1 Uncertainty

The model provides a simplified representation of a complex natural and engineered system, with inherent variability and uncertainty. It is based on the current understanding of the Project description and mine plan, and deviation from these plans may invalidate the projections presented herein.

Climate change was not considered in this model. Though the effects of climate change are expected to increase over time, the life of the project is short and it is unlikely that any potential changes in climate due to climate change will not be outside the range of current natural climate variability. Therefore, potential changes in climate over the length of the project due to climate change are considered to be sufficiently represented in the sensitivity analysis by introducing wet years with extreme annual precipitation.

The model is limited to the monthly time step, which does not allow to estimate water quantity or quality at a smaller scale. Projected concentrations represent monthly averages, and therefore do not account for daily variability in loadings due to variability in the local weather. Higher daily concentrations may occur due to site conditions, climate conditions, management practices, and extreme events.

Additionally, the model does not account for the formation of ice as there are no pumped flows between CPs anticipated through winter; however, ice formation will concentrate constituents in the remaining water volume during winter conditions. In early freshet conditions once ice begins to melt, observed concentrations at site will likely be lower than projected if samples are taken from an accumulation of water on top of ice surfaces; conversely, they will likely be much higher than predicted if samples are taken under ice. In this way, monitoring data, particularly for CP1, may show initial summer concentrations higher than the discharge criteria; however, these would be expected to decrease as freshet flows from other surface water sources enter CP1 and the ice volume melts.

Uncertainty in the modelling projections for CP1 over Project operations will be managed through the Water Quality Management and Optimization Plan (WQ-MOP), which was initially drafted as part of the Emergency Amendment and revised for the 2020 Water Licence Amendment. The WQ-MOP outlines the process to set benchmarks at the point of discharge and within the receiving environment of Meliadine Lake, so as to make sure Meliadine Lake remains protected, details a monitoring program to validate the benchmarks, and describes a basis for adaptive management for CP1 discharge.

5.0 LIMITATIONS

This report was prepared for the exclusive use of Agnico Eagle Mines Ltd. The report, which specifically includes all tables, figures, and appendices, is based on data gathered by Golder Associates Ltd., and information provided to Golder Associates Ltd. by others. The information provided by others has not been independently verified or otherwise examined by Golder Associates Ltd. to determine the accuracy or completeness. Golder Associates Ltd. has relied in good faith on this information and does not accept responsibility for any deficiency, misstatements, or inaccuracies contained in the information as a result of omissions, misinterpretation or fraudulent acts of the persons who provided the information. Golder Associates Ltd. shall not be held responsible for damages resulting from unpredictable or unknown site conditions, from erroneous information provided by and/or obtained from sources other than Golder Associates Ltd., and from ulterior changes in the site conditions unless Golder Associates Ltd. has been notified by Agnico Eagle Mines. of any occurrence, activity, information, or discovery, past or future, which would modify the site conditions described herein, and have had the opportunity of revising its interpretations and comments. Golder Associates Ltd. shall not be held responsible for damages resulting from any future modification to the applicable regulations, standards, and criteria. Any use of this report and its content by a third party is the responsibility of such third party. Golder Associates Ltd. shall not be held responsible for damages, if any, suffered by any third party as a result of decisions made or actions taken based on this report.

The services performed as described in this report were conducted in a manner consistent with that level of care and skill normally exercised by other members of the engineering and geoscience professions currently practicing under similar conditions, subject to the time limits and financial and physical constraints applicable to the services.

The findings and conclusions of this report are valid only as of the date of this report. If new information is discovered in future work or other studies, Golder Associates Ltd. should be requested to re-evaluate the findings of this report, and to provide amendments as required.

This report provides a professional opinion in light of the information available at the time of this report and therefore no warranty is either expressed, implied, or made as to the conclusions, advice or recommendations offered in this report.

6.0 REFERENCES

Agnico Eagle (Agnico Eagle Mines Limited). 2020a. 2020 Mine Waste Management Plan. Version 7. 6513-MPS-09. July 2020.

Agnico Eagle. 2020b. Meliadine Gold Project: Water Management Plan. Version 10. 6513-MPS-11. August 2020.

Golder (Golder Associates Ltd.). 2020. Water Quality Management and Optimization Plan Rev 2. Submitted to Agnico Eagle. July 2020. Ref No. 19132390-751-RPT-Rev2a.

OKC (Okane Consultants). 2020. Conceptual Model for Thermal Modelling of Meliadine WRSFs. Ref No. 948-021-003 Rev A Draft. Dated May 25, 2020.

Signature Page

Golder Associates Ltd.

original signed by

Adwoa Cobbina, MA.Sc.
Water Resources Specialist

original signed by

Julien Lacrampe, B.Sc. Civil Engineering, P.Eng. (NWT/NU)
Associate, Senior Water Resources Engineer

original signed by

Kristina Skeries, M.Sc.
Environmental Specialist

original signed by

John Faithful, B.Sc. (Hons)
Principal, Senior Water Quality Specialist

AC/JL/KS/JF/jr

Golder and the G logo are trademarks of Golder Associates Corporation

[https://golderassociates.sharepoint.com/sites/128148/project files/5 technical work/2100-2200_wb-wq/reporting/rev1/20144940-779-rpt-wlamendment_wb-wqforecast-rev1.docx](https://golderassociates.sharepoint.com/sites/128148/project%20files/5%20technical%20work/2100-2200_wb-wq/reporting/rev1/20144940-779-rpt-wlamendment_wb-wqforecast-rev1.docx)

APPENDIX A

**Environmental Design Inputs and
Assumptions**



REV1 AUGUST 21, 2020

Meliadine August 2020 Water Licence Amendment - Environmental Design Inputs and Assumptions

Submitted to:

Michel Groleau and Angie Arbaiza

Agnico Eagle Mines Limited

Cc:

Jamie Quesnel, Matt Gillman, Jennifer Levenick, John Faithful, Jennifer Range

Submitted by:

Golder Associates Ltd., Adwoa Cobbina and Kristina Skeries

Table of Contents

DOCUMENT CONTROL	iv
List of Abbreviations and Nomenclature	v
1.0 Introduction	1
2.0 Mine Design Parameters	1
3.0 Climate Assumptions	4
4.0 Water Balance Criteria and Assumptions	4
4.1 Model Attributes	4
4.2 Initial Conditions	4
4.3 Hydrology	5
5.0 Mass Balance Criteria and Assumptions	6
5.1 Modelled Constituents and Comparative Guidelines	6
5.2 Model Source Term Derivations	7
5.3 Initial Conditions	10
5.4 Assumptions	10
6.0 Water Treatment	11
7.0 References	12
ANNEX A – Water quality model inputs	14
ANNEX B – Pond Storage Curves	20
ANNEX C – Watershed Areas	21

TABLES

Table 1: Construction and Operation Schedule3
Table 2: Average Year and Wet Year Precipitation and Runoff Coefficients¹4
Table 3: Model Attributes4
Table 4: Initial Conditions5
Table 5: Consumptive Flows5
Table 6: Max Discharge Rates for Water Containment Ponds5
Table 7: Modelled Constituents and Comparative Guidelines6
Table 8: Water Quality Inputs7
Table 9: Pond Initial Water Quality Conditions10
Table 10: Total Suspended Solids (TSS) Concentrations10
Table 11: Particulate concentration at source point per 1 mg/L of TSS11
Table 12: Water Treatment11

FIGURES

Figure 1: Ultimate LOM Layout2

DOCUMENT CONTROL

Version	Date (YMD)	Section	Revision	Issued By
Rev A	2020-06-29	All	Initial draft for Agnico Eagle internal review	A. Cobbina / K. Skeries
Rev B	2020-07-20	All	Agnico Eagle comments addressed	A. Cobbina / K. Skeries
Rev 0	2020-08-07	All	Final version for submission	A. Cobbina / K. Skeries
Rev 1	2020-08-21	All	Final version for submission, additional Agnico Eagle comments addressed	A. Cobbina / K. Skeries

List of Abbreviations and Nomenclature

Agnico Eagle	Agnico Eagle Mines Limited
CP	Containment Pond
d	Day
EWTP	Effluent Water Treatment Plant
the Project	Meliadine Project
FEIS Addendum	Final Environmental Impact Statement Addendum
Golder	Golder Associates Ltd.
hr	Hour
HCT	Humidity cell test
kg	Kilogram
km	Kilometre
L	Litre
LOM	Life of mine
m	Metre
mm	Millimetre
m ²	Square metre
m ³	Cubic metre
mg	Milligram
mon	Month
NU	Nunavut
Okane	Okane Consultants Inc.
OP	Ore Pad
ROM	Run of mine
SFE	Shake flask extraction test
STP	Sewage Treatment Plant
TDS	Total dissolved solids
TSS	Total suspended solids
TSF	Tailings Storage Facility
Tetra Tech	Tetra Tech, Inc
Tiri	Tiriganiaq pit
UG	Underground
WRSF	Waste Rock Storage Facility
yr	Year

1.0 INTRODUCTION

This document is intended to capture the assumptions the water balance and water quality model used to support the 2020 Water Licence Amendment Application. The content of this document is based on input or review from Agnico Eagle Mines Limited (Agnico Eagle) provided to Golder Associates Ltd. (Golder) up to July 28, 2020. It is a live document that is updated as more information becomes available through monitoring, additional modelling, and development of the mine plan.

2.0 MINE DESIGN PARAMETERS

The V11_3 LOM mine plan is assumed in terms of the mining sequencing and schedule (Table 1). An overview of the basis for the LOM is provided in the Mine Waste Management Plan (Agnico Eagle 2020b).

The V12 LOM 2020 layout is provided in Figure 1. While the V11_3 LOM is used for the sequencing, the V12 layout will be used to generate watershed and facility areas.

Figure 1: Ultimate LOM Layout




Table 1: Construction and Operation Schedule

Dewatering/Construction/Operation Activities	Starts at Beginning of	Ends at the End of
Mine Operation	Q4 of 2015 (Yr – 5)	2027 (Yr 8)
Construction of industrial pad	Q4 of 2015 (Yr – 5)	2019 (Yr -1)
Construction of rock pad for underground ore stockpiles	Q4 of 2015 (Yr – 5)	Q4 of 2015 (Yr – 5)
Construction of Landfarm	2017 (Yr -3)	2017 (Yr -3)
Construction of Ore Pad 2	2018 (Yr -2)	2019 (Yr -1)
Operation of TSF Cell 1	Q1 of 2019 (Yr-1)	2024 (Yr 5)
Operation of WRSF1	2019 (Yr -1)	2024 (Yr 5)
Operation of WRSF3 (expanded)	2019 (Yr -1)	2026 (Yr 7)
Construction Operation Southern Laydown (garages, laydown, transit areas)	2020 (Yr 1)	End of operations
Construction New Contact Water Treatment Plant	2020 (Yr 1)	End of operations
Mining of Tiriganiaq Pit 2	2020 (Yr 1)	2022 (Yr 3)
Enhanced WTP online	2020 (Yr 1)	End of operations
Construction Operation Landfarm C (new one)	2021 (Yr 2)	End of operations
Mining of Tiriganiaq Pit 1	2021 (Yr 2)	2026 (Yr 7)
Mill expansion	2022 (Yr 3)	End of operations
Operation of Ore Pad 2 Ext	2021 (Yr 2)	End of Operations
Construction Roads to Discovery inclusive of AWAR widening and Boat Launch	2022 (Yr 3)	2025 (Yr 6)
Operation of TSF Cell 2	2023 (Yr 4)	2027 (Yr 8)
Placement of closure cover on top of tailings surface in Cell 1 of TSF	2024 (Yr 5)	2024 (Yr 5)

Source: 2020 Mine Waste Management Plan (Agnico Eagle 2020b)

3.0 CLIMATE ASSUMPTIONS

Table 2: Average Year and Wet Year Precipitation and Runoff Coefficients¹

Month	Rainfall and Snowmelt (mm/mon) ²			Runoff Coefficient			
	Average Year	10 yr Wet Year ³	100 yr Wet Year ³	Natural Ground ⁴	Disturbed Ground ⁴	Water Surface ⁴	WRSF and Ore Stockpiles ⁵
January	0	0	0	0	0	0	0
February	0	0	0	0	0	0	0
March	0	0	0	0	0	0	0
April	0	0	0	0	0	0	0
May	0	0	0	0	0	0	0
June	207	267	310	0.52	0.55	0.31	0.043
July	44	57	66	0.52	0.85	-1.9	0.003
August	58	75	87	0.52	0.7	-0.5	0.003
September	51	66	76	0.52	0.6	0.15	0.001
October	56	72	84	0.52	0.55	1	0
November	0	0	0	0	0	0	0
December	0	0	0	0	0	0	0

Notes:

1. Based on timeseries generated by Okane based on data from Rankin Inlet and site data (OKC 2020)
2. Winter precipitation is included in the runoff and snowmelt values for June
3. Wet year values were developed based on frequency analyses on the annual precipitation record from OKC 2020. The monthly values were then assumed based on the monthly distribution for the annual statistics.
4. Estimated from Tetra Tech's Approved water balance: Meliadine Approved Project Water Balance 03172020.xlsx. Negative values indicate evaporative rates greater than precipitation rates
5. Based on Okane runoff estimates from the Whale Tail Expansion Project (OKC 2019).

4.0 WATER BALANCE CRITERIA AND ASSUMPTIONS

4.1 Model Attributes

Table 3: Model Attributes

Attribute	Details
Model Software	Excel
Start Date	May 2020
End Date	December 2028
Timestep	Monthly
Results timestep	Monthly

4.2 Initial Conditions

Volumes in May 2020 are assumed to be the same as the recorded volumes in May where available or in October 2019 (as included in the Tetra Tech water balance [2020a]).

Table 4: Initial Conditions

Waterbody / Reservoir	Condition (May 2020)
CP1	Volume (m ³): 631,587
CP2	Volume (m ³): 0 (not initiated until 2024)
CP3	Volume (m ³): 21,688
CP4	Volume (m ³): 20,187
CP5	Volume (m ³): 16,781
CP6	Volume (m ³): 26,747
P1 Pond	Volume (m ³): 4,781
P2 Pond	Volume (m ³): 691
P3 Pond	Volume (m ³): 2,441

4.3 Hydrology

Table 5: Consumptive Flows

Item	Flow Rate	Volume per year (m ³)
Camp Use	200 L/person/day (680 person)	50,000
Ore moisture content from pits	2% by weight	-
Waste rock moisture content from open pits	2% by weight	-
Ore moisture content from underground	2% by weight	-
Waste rock moisture content from underground	2% by weight	-

Table 6: Max Discharge Rates for Water Containment Ponds

Water Containment Pond	Max Rate (m ³ /d)
CP1	22,000
CP2	11,000
CP5	2020: 16,700 2021- closure: 26,900
CP3	9,400
CP4	11,000
CP6	11,000

Elevation storage relationships and watershed areas are presented in Annexes B and C, respectively.

5.0 MASS BALANCE CRITERIA AND ASSUMPTIONS

5.1 Modelled Constituents and Comparative Guidelines

Water quality data are provided in Annex A and assumptions used are summarized in this section.

Table 7: Modelled Constituents and Comparative Guidelines

Constituent Group	Constituents	Surface Contact Water Effluent Discharge Criteria (end of pipe) (mg/L)
Conventional	Total Dissolved Solids (TDS)	3,500 ^a
Nutrients	Total Dissolved Phosphorus (Total P)	2.0 ^b
	Total Ammonia (NH ₃) as N	14
Metals	Aluminum (Al)	2.0 ^b
	Arsenic (As)	0.3 ^b
	Copper (Cu)	0.2 ^b
	Nickel (Ni)	0.5 ^b
	Lead (Pb)	0.2 ^b
	Zinc (Zn)	0.4 ^b

Notes:

^a - Proposed maximum average concentration TDS discharge criterion (WQMOP Rev2a, Golder 2020)

^b - Guideline applies to total concentration; total concentrations are estimated for model results by adding a particulate fraction to the dissolved concentrations, assuming 15 mg/L TSS.

5.2 Model Source Term Derivations

Table 8: Water Quality Inputs

Modelled Flow	Type	Source
Natural Runoff to Site	Concentration	<ul style="list-style-type: none"> Average parameter concentrations derived from baseline water quality between 1997 and 2011 from stream B6-7 (n = 5) (Golder 2012a, Golder 2015b, and TetraTech 2020b).
Disturbed Runoff to Site	Concentration	<ul style="list-style-type: none"> Average parameter concentrations (total fraction available only) derived from the waste rock pad (n = 5) as per Agnico Eagle, J. Wittemann (2010) (Agnico Eagle 2010, Golder 2012a, Golder 2015b and TetraTech 2020b). For TDS only, monthly average 2019 monitored concentrations from Channel 1 were assigned at a 25% reduction for the year 2020, with a continuing 25% decrease in subsequent years (Tetra Tech 2020c).
Direct Precipitation	Concentration	Assumed pristine water (0 mg/L for all constituents)
STP Effluent – Main Camp	Concentration	<ul style="list-style-type: none"> Average water quality from Main Camp STP effluent monitoring data ranging from January 2019 to June 2020 <ul style="list-style-type: none"> NH₄ and Total Phosphorus: (n = 76, n = 77 respectively) TDS calculated by multiplying average specific conductivity (uS/cm) by 0.7 (n = 66). All other modelled constituents: Average water quality from station MEL-11 (freshwater intake) monitoring data ranging from January 2019 to June 2020 (n = 20)
Landfill Runoff	Concentration	<ul style="list-style-type: none"> Average parameter concentrations (total fraction available only) derived from the waste rock pad (n = 5) as per Agnico Eagle, J. Wittemann (2010) (Agnico Eagle 2010, Golder 2012a, Golder 2015b, and TetraTech 2020b).
Landfarm Runoff	Concentration	<ul style="list-style-type: none"> Average water quality from Landfarm sump monitoring data ranging from August 2018 to August 2019 (n (TDS, Total P) = 8, n (Ammonia) = 9, n (metals) = 4)
WRSF runoff	Loading	<ul style="list-style-type: none"> Overburden: Average parameter loadings derived from SFE data (Golder 2012b, Golder 2015b, TetraTech 2020b) <ul style="list-style-type: none"> Scaled to average climate field precipitation Waste Rock: Parameter loadings derived from HCT and Large Column data (Golder 2012a, Golder 2015b and TetraTech 2020b) <ul style="list-style-type: none"> Loading rate calculations for each rock type were developed using the last two steady state cycles analyzing the whole metal suite and assigning sample proportion contributions by rock type Weekly loading rates were applied as monthly loading rates to scale to field conditions. Overburden and waste rock loadings calculated using cumulative lithological waste rock proportions from the open pits(s) and underground for WRSF1 and WRSF3 TDS from proportion of underground-sourced waste rock is set at 10% the average water quality concentration from Level 300 Sump monitoring data ranging from June 2019 to April 2020 (n = 12); this is the maximum percentage of underground sump water concentrations, recorded in seepage monitoring studies in 2017 (Golder 2017).

Table 8: Water Quality Inputs

Modelled Flow	Type	Source
Ore stockpile runoff	Loading	<ul style="list-style-type: none"> ▪ Average parameter concentrations derived from SFE data (Golder 2012b and TetraTech 2020b) with exception to total ammonia. The maximum concentration recorded from existing pad runoff as per Agnico Eagle, J. Wittemann (2009) for total ammonia was assigned to Large Column leaching tests to calculate and assign a loading rate (Agnico Eagle 2009 and Golder 2015b). <ul style="list-style-type: none"> ○ Rolling piles such as the ore stockpile runoff was not scaled to average climate field precipitation as a conservative measure ▪ TDS from proportion of underground-sourced ore is set at 10% the average water quality concentration from Level 300 Sump monitoring data ranging from June 2019 to April 2020 (n = 12); this is the maximum percentage of underground sump water concentrations, recorded in seepage monitoring studies in 2017 (Golder 2017).
Tailings Storage Facility (TSF) runoff	Loading (with exception to seepage)	<ul style="list-style-type: none"> ▪ Tailings Seepage: Parameter concentrations derived from open pit and underground HCT whole ore tailings data (Golder 2012b and TetraTech 2020b) with exception to total ammonia. Monthly average concentrations for total ammonia were calculated from Meadowbank TSF Pond (ST-21) and applied as monthly concentrations (Golder 2012a). <ul style="list-style-type: none"> ○ Concentrations were developed using average of HCT cycles 0 - 4 ○ Concentration calculated using ore production proportions from the open pit(s) and underground. ▪ Tailings Runoff: Parameter loadings derived from open pit and underground HCT whole ore tailings data (Golder 2012a and TetraTech 2020b) with exception to total ammonia. Monthly average concentrations for total ammonia were calculated from Meadowbank TSF Pond (ST-21) and applied as monthly concentrations (Golder 2012a). <ul style="list-style-type: none"> ○ Loading rate calculations were developed using average of HCT cycles 12 - 16 ○ Weekly loading rates were applied as monthly loading rates to scale to field conditions. ○ Loadings calculated using ore production proportions from the open pit(s) and underground.
	Loading	<ul style="list-style-type: none"> ▪ Waste Rock Cover Seepage and Runoff: Parameter loadings derived from HCT and Large Column data (Golder 2012a, Golder 2015b and TetraTech 2020b) with exception to total ammonia. The maximum concentration recorded from existing pad runoff as per Agnico Eagle, J. Wittemann (2009) for total ammonia was assigned to Large Column leaching tests to calculate and assign a loading rate (Agnico Eagle 2009 and Golder 2015b). <ul style="list-style-type: none"> ○ Loading rate calculations for each rock type were developed using the last two steady state cycles analyzing the whole metal suite and assigning sample proportion contributions by rock type ○ Loadings calculated using cumulative open pit and underground lithological waste rock proportions from WRSF1. ○ Weekly loading rates were applied as monthly loading rates to scale to field conditions.

Table 8: Water Quality Inputs

Modelled Flow	Type	Source
Pit wall runoff	Loading	<ul style="list-style-type: none"> ▪ Overburden: Parameter loadings derived from SFE data (Golder 2012b, Golder 2015b and TetraTech 2020b) <ul style="list-style-type: none"> ○ Scaled to average climate field precipitation ▪ Waste Rock: Parameter loadings derived from HCT and Large Column data (Golder 2012a, Golder 2015 and TetraTech 2020b) <ul style="list-style-type: none"> ○ Loading rate calculations for each rock type were developed using the last two steady state cycles analyzing the whole metal suite and assigning sample proportion contributions by rock type ○ Weekly loading rates were applied as monthly loading rates to scale to field conditions. ▪ Overburden and waste rock loadings calculated using exposed pit wall lithological proportions in final pit shell
TDS flush of surface stockpiles containing underground material	Concentration	<ul style="list-style-type: none"> ▪ TDS concentration override assuming 10% of the average water quality concentration from Level 300 Sump monitoring data ranging from June 2019 to April 2020 (n = 12); this is the maximum percentage of underground sump water concentrations, recorded in seepage monitoring studies in 2017 (Golder 2017)
TDS flush of constructed pads/disturbed area runoff	Concentration	<ul style="list-style-type: none"> ▪ Monthly average 2019 monitored concentrations from Channel 1 were assigned at a 25% reduction for the year 2020, with a continuing 25% decrease in subsequent years (Tetra Tech 2020c).

Note: for the purposes of the derivation of inputs, all values that were less than the mean detection limit were applied their respective detection limit.

5.3 Initial Conditions

Initial conditions for reservoirs containing volume at the start of the model are required. As water quality monitoring typically does not occur in under-ice conditions, there are no data available for many of the ponds for the model start date of May 1, with CP1 being the exception. Therefore, for these ponds, water quality conditions at freeze up from the previous year was used, under the assumption that most of the CP's will not accumulate any further volume over the under-ice period.

To calculate the initial conditions, the mass present in the ponds at freeze-up was calculated using the concentrations and volume present on the day the sample was taken (or as close to as possible). This mass was assumed to be equal to the mass present at the model start date, and concentrations were calculated using the initial volumes from the water balance.

Table 9: Pond Initial Water Quality Conditions

Pond	Source
CP1	Water quality of CP1 on May 3, 2020
CP2	Pond is established after model start date, no initial conditions
CP3	Water quality of CP3 on September 1, 2019
CP4	Water quality of CP4 on September 4, 2019
CP5	Water quality of CP5 on September 3, 2019
CP6	No monitoring data; initial CP4 water quality used as proxy.
P Area	Water quality of P1 on September 1, 2019

5.4 Assumptions

Table 10: Total Suspended Solids (TSS) Concentrations

Location	TSS Concentration	Rationale
Effluent	15 mg/L	assumed to be consistent with MDMER

Table 11: Particulate concentration at source point per 1 mg/L of TSS

Constituent	Particulate Fraction Concentration (mg/L) per 1 mg/L TSS
<i>Conventional</i>	
Total Dissolved Solids (TDS)	0 mg/L
<i>Nutrients</i>	
Total Phosphorus (Total P)	0.078 mg/L ^a
Total Ammonia (NH ₃)	0 mg/L
<i>Metals</i>	
Aluminum (Al)	0.015 mg/L
Arsenic (As)	0.000069 mg/L
Copper (Cu)	0.000027 mg/L
Nickel (Ni)	0 mg/L
Lead (Pb)	0 mg/L
Zinc (Zn)	0.0013 mg/L

Notes:

^a - Calculated as the difference between total phosphorus and ortho-phosphate. Ortho-phosphate concentrations were detected in only 3 of 16 samples.

6.0 WATER TREATMENT

Table 12: Water Treatment

Treatment Type	Dates	Water Flow (Maximum)	Water Quality	Discharge Location
Sewage Treatment Plant (STP)	Operations	680 persons 0.2 m ³ /person/day	<ul style="list-style-type: none"> Main Camp STP: <ul style="list-style-type: none"> 1.0 mg/L NH₃ as N 6.8 mg/L Total P 	<ul style="list-style-type: none"> CP1
Contact Effluent Water Treatment Plant (EWTP)	<ul style="list-style-type: none"> Current Future (Date TBD) 	June 15 – Oct 1: <ul style="list-style-type: none"> Min flow: 6,000 m³/d Max flow: 22,000 m³/d 2.6% of treated water is returned to CP1 as sludge at 1% solids 	<ul style="list-style-type: none"> Treatment is only for TSS which is not tracked in the model. 	<ul style="list-style-type: none"> Meliadine Lake via diffuser

7.0 REFERENCES

- APHA (American Public Health Association). 2017. Standard Methods for the Examination of Water and Wastewater: 23rd edition. Washington DC, USA.
- Agnico Eagle (Agnico Eagle Mines Limited). 2009. File: *June-July-August_Sept WQ Data Report – 2009.xlsx*. File provided by John Witteman on behalf of AEM to Valérie Bertrand of Golder Associates, Ltd., received February 2010.
- Agnico Eagle. 2010. File: *Analytical Results from Pad Runoff.xlsx*. File provided by John Witteman on behalf of AEM to Valérie Bertrand of Golder Associates, Ltd., received July 2010.
- Agnico Eagle. 2020a. Freshwater Usage Spreadsheet_V007_updatedV11.xlsx. Received June 15, 2020.
- Agnico Eagle. 2020b. Mine Waste Management Plan. Version 6. March 2020.
- Agnico Eagle. 2020c. Ore Storage Management Plan. Version 2. March 2020.
- Agnico Eagle. 2020d. PLOM Playbook Rev 1.0. May 19, 2020 (in progress).
- Agnico Eagle. 2020e. File: *Copy of waste piles_V10_Plan.xlsx*. File provided by Angie Arbaiza on behalf of AEM to Kristina Skeries of Golder Associates, Ltd., received July 2020.
- Golder (Golder Associates Ltd.). 2012a. Mine Site Water Quality Predictions Meliadine Gold Project, Nunavut. October 2012. Ref No. 11-1428-0011/6600.
- Golder. 2012b. Geochemical Characterization of Waste Rock, Ore, Tailings, and Overburden. Meliadine Golder Project, Nunavut. Support document 6-3 to the Final Environmental Impact Statement (SD 6-3). Dated October 10, 2012. Ref No. 256-1114280011/6000.
- Golder. 2015a. Conceptual Model – Hydrogeology Support – Meliadine Project. Dated December 7, 2015. Ref No. Doc 540-1416135 Ver 0.
- Golder. 2015b. Mine Site Water Quality Predictions, Meliadine Gold Project, Nunavut. April 2015.
- Golder. 2017. Salinity of Waste Rock Sourced from Underground Assessment and Construction Use, Meliadine Mine, Nunavut. Dated August 3, 2017. Ref No. 1656645/3200/3220 Doc 578 Rev. 1.
- Golder. 2020. Water Quality Management and Optimization Plan. Submitted to Agnico Eagle. July 2020. Ref No. 19132390-751-RPT-Rev2a.
- Kempton, H. 2012. A Review of Scale Factors for Estimating Waste Rock Weathering from Laboratory Tests. Proceedings of the 9th International Conference on Acid Rock Drainage (ICARD), Ottawa, Canada. May 20 – 26, 2012.
- OKC (Okane Consultants). 2019. Agnico Eagle Mines Ltd. Landform Water Balance Modelling of Whale Tail and IVR WRSF.
- OKC. 2020. Conceptual model for Thermal Modelling of Meliadine WRSFs. 948-021-003 Rev A Draft. Dated May 25, 2020.

Tetra Tech. 2020a. *Meliadine Approved Project Water Balance 03172020 – For Golder.xlsm*. File provided by Matt Gillman on behalf of Tetra Tech to J. Faithful, A. Cobbina, K. Skeries, J. Range, and D. Brown of Golder Associates, Ltd., received May 2020.

Tetra Tech. 2020b. File: *Water Quality Model Source Terms-Inputs_08212019.xlsx*. File provided by Amy Hudson on behalf of Tetra Tech to D. Brown and K. Skeries of Golder Associates, Ltd., received, April 2020.

Tetra Tech. 2020c. File: *Meliadine Water Quality Model.pdf*. File provided by Jen Forbes on behalf of Tetra Tech to D. Brown of Golder Associates, Ltd., received, May 2020.

ANNEX A – WATER QUALITY MODEL INPUTS

Table A.1: Initial water quality conditions in the water quality model

Constituents		CP1	CP3	CP4	CP5	CP6	P Area
		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Conventional	Total Dissolved Solids (TDS)	1,297 ^a	854	977	7,153	977	10,950
Nutrients	Total Phosphorus (Total P)	0.034	0.18	0.065	0.067	0.065	0.073
	Total Ammonia (NH ₃) as N	4.3	4.6	0.9	18	0.9	36
Metals	Aluminum (Al)	0.0039	0.016	0.0064	0.025	0.0064	0.030
	Arsenic (As)	0.0019	0.064	0.0056	0.0043	0.0056	0.0059
	Copper (Cu)	0.00080	0.0055	0.0029	0.0067	0.0029	0.0047
	Nickel (Ni)	0.0040	0.022	0.015	0.038	0.015	0.028
	Lead (Pb)	0.00020	0.0011	0.00013	0.0017	0.00013	0.0020
	Zinc (Zn)	0.0086	0.027	0.0033	0.042	0.0033	0.050

^a Concentration calculated using total water and ice volume to account for melting ice in June 2020. Actual concentration under ice in May 2020 was 5,700 mg/L.

Table A.2: Static water quality inputs to the water quality model

Constituents		Natural Runoff	Disturbed Runoff	STP Effluent Main Camp	STP Effluent Exploration Camp	Landfill Runoff	Landfarm Runoff
		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Conventional	Total Dissolved Solids (TDS)	50	Variable	649 ^a	396 ^a	Variable	6,279
Nutrients	Total Phosphorus (Total P)	0.0066	0.031	6.8	7.6	0.031	0.071
	Total Ammonia (NH ₃) as N	0.019	2.3	1.0	16	2.3	59
Metals	Aluminum (Al)	0.0037	0.62 ^b	0.0032	0.0032	0.62 ^b	0.081
	Arsenic (As)	0.0011	0.018 ^b	0.00034	0.00034	0.018 ^b	0.0084
	Copper (Cu)	0.00090	0.0025 ^b	0.00076	0.00076	0.0025 ^b	0.0055
	Nickel (Ni)	0.00028	0.0059 ^b	0.001	0.001	0.0059 ^b	0.014
	Lead (Pb)	0.00084	0.0069 ^b	0.0002	0.0002	0.0069 ^b	0.0007
	Zinc (Zn)	0.0031	0.029 ^b	0.005	0.005	0.029 ^b	0.018

Notes:

^a – TDS was calculated by multiplying specific conductivity (µS/cm) by 0.70 as measured TDS and most major ions were not available.

^b – Represents total metals fraction

Table A.3: Waste rock, overburden, and ore concentration inputs to the water quality model

Constituents		Overburden	Gabbro	Iron Formation	Mafic Volcanic and Sericitized Volcanic ^a	Greywacke-Siltstone and Sediment	Oxidized Sediment	Ultramafic ^b	Ore ^c	Tailings Seepage		Tailings Runoff	
		mg/kg/month ^d	mg/kg/month ^e	mg/kg/month ^e	mg/kg/month ^e	mg/kg/month ^e	mg/kg/month ^e	mg/kg/month ^e	mg/L	Tiriganiaq Pits	Tiriganiaq UG	Tiriganiaq Pits	Tiriganiaq UG
										mg/L	mg/L	mg/kg/month ^e	mg/kg/month ^e
Conventional	Total Dissolved Solids (TDS) ^f	2.0	6.1	12	7.9	8.5	9.2	24	45	48	49	103	177
Nutrients	Total Phosphorus (Total P)	0.0089 ^{g,h}	0.00087 ^g	0.0023 ^g	0.0029 ^g	0.0029 ^g	0.0089 ^{g,h}	0.0089 ^g	0.10 ⁱ	0.10 ⁱ	0.10 ⁱ	0.0089 ^{g,h}	0.0089 ^{g,h}
	Total Ammonia (NH ₃) as N	1.1 [13 mg/L] ^j	1.1 [13 mg/L] ^j	1.1 [13 mg/L] ^j	1.1 [13 mg/L] ^j	1.1 [13 mg/L] ^j	1.1 [13 mg/L] ^j	1.1 [13 mg/L] ^j	12 mg/L ^k	Variable ^l	Variable ^l	Variable ^l	Variable ^l
Metals	Aluminum (Al)	0.025	0.011	0.028	0.017	0.018	0.020	0.11	0.59	0.015	0.010	0.040	0.12
	Arsenic (As)	0.00066	0.0017	0.00062	0.0046	0.0067	0.0055	0.044	0.34	0.011	0.0090	0.20	0.58
	Copper (Cu)	0.00034	0.000058	0.00045	0.00016	0.00017	0.00022	0.00050	0.00054	0.00019	0.00022	0.0010	0.0015
	Lead (Pb)	0.000049	0.0000068	0.000021	0.000012	0.000014	0.000015	0.000020	0.000097	0.0030	0.0060	0.00010	0.00042
	Nickel (Ni)	0.00022	0.000077	0.000090	0.000084	0.00013	0.00013	0.000099	0.00080	0.00025	0.00025	0.00067	0.00077
	Zinc (Zn)	0.0039	0.011	0.028	0.017	0.018	0.020	0.11	0.0010	0.0010	0.0010	0.0011	0.0013

Notes:

^a – Mafic volcanic HCT utilized and applied to sericitized volcanic lithology

^b – Ultramafic lithology represented by ultramafic Wesmeg Pit HCT

^c – Represented by Ore (Greywacke-siltstone) and Ore (Mafic volcanic)

^d – Weekly loading rates derived from SFE results were applied as the monthly rate to scale for site precipitation

^e – Weekly loading rates were applied as the monthly rate to scale for site precipitation

^f – TDS was calculated by summing alkalinity as CaCO₃ (multiplied by a factor of 0.60) and available major ion and metal constituent concentrations. Nitrate, fluoride, and chloride were not analyzed consistently enough to calculate TDS based on APHA 2017.

^g – Represents total phosphorus (metals) fraction

^h – Insufficient data for this lithology; supplemented with the maximum loading rate from remaining lithologies

ⁱ – A concentration of 0.10 mg/L was applied as a conservative estimate as most site data does not exceed 0.1 mg/L.

^j – Maximum concentration recorded from existing pad runoff as per Agnico Eagle, J. Wittemann (2009) assigned to Large Column leaching tests to calculate a loading rate and applied to WRSF's (Agnico Eagle 2009 and Golder 2015b); concentration of 13 mg/L applied to Open Pit Walls

^k – Maximum concentration recorded from existing pad runoff as per Agnico Eagle, J. Wittemann (2009) applied to Ore Stockpiles (Agnico Eagle 2009 and Golder 2015b).

^l – Input as average monthly concentrations reported for the Meadowbank TSF Pond (Golder 2012a): June [50 mg/L], July [25 mg/L], August [20 mg/L], September and October [35 mg/L]

Table A.4: WRSF Source Proportions by WRSF (Agnico Eagle 2020e)

Year	WRSF 1		WRSF 3	
	Tiriganiaq Open Pits	Tiriganiaq Underground	Tiriganiaq Open Pits	Tiriganiaq Underground
	%	%	%	%
2020	100	0	0	0
2021	28	72	100	0
2022	85	15	100	0
2023	88	12	100	0
2024	75	25	100	0
2025	67	33	100	0
2026	67	33	93	7.5
2027	67	33	93	7.5
2028	67	33	93	7.5

Table A.5: Waste Rock Lithological Proportions by Facility (Agnico Eagle 2020d)

	Unit	Facility	Overburden	Gabbro	Lamprophyre	Iron Formation	KMG	Ultra-mafic	Siltstone	Oxidized Sediment	Sericitized -Volcanic	Volcanic	Sediment	Un-defined
Tonnage	tonnes	Tiriganiaq Pit 1	5,765,571	128,457	0	591,341	200,511	0	504,574	2,988,579	771,042	4,163,217	8,276,924	0
		Tiriganiaq Pit 2	693,226	113	0	648,203	0	0	0	1,217,425	0	0	3,979,261	0
		Tiriganiaq Underground	0	47,793	0	493,396	48,535	0	461,343	1,719,781	27,708	1662272	902,549	209,911
Proportion	%	Tiriganiaq Pit 1	91	76	-	39	83	-	57	55	97	75	67	0
		Tiriganiaq Pit 2	9.0	0	-	35	0	-	0	18	0	0	27	0
		Tiriganiaq Underground	0	23	-	27	17	-	43	26	2.9	25	6.1	100

Table A.6: Tailings Source Proportions (Agnico Eagle 2020c)

Year	Tiriganiaq Pit 1	Tiriganiaq Pit 2	Tiriganiaq Underground	Tiriganiaq Pit 1	Tiriganiaq Pit 2	Tiriganiaq Underground
	tonnes	tonnes	tonnes	%	%	%
2020	1,183	128,237	1,392,154	0.078	8.4	91
2021	46,388	143,042	1,560,327	2.7	8.2	89
2022	558,776	264,851	1,542,547	24	11	65
2023	315,190	0	1,516,664	17	0	83
2024	735,511	0	1,486,178	33	0	67
2025	944,833	0	1,453,224	39	0	61
2026	600,057	0	1,503,864	29	0	71
2027	0	0	0	29	0	71
2028	0	0	0	0	0	0
2029	0	0	0	0	0	0

Table A.7: Ore Source Proportions (Agnico Eagle 2020c)

Year	Ore Stockpile Balance (OP2)	Tiriganiaq Pit 1	Tiriganiaq Pit 2	Tiriganiaq Underground	Tiriganiaq Pit 1	Tiriganiaq Pit 2	Tiriganiaq Underground
	tonnes	tonnes	tonnes	tonnes	%	%	%
2020	132,317	1,183	128,237	1,392,154	0.078	8.4	91
2021	172,419	46,388	143,042	1,560,327	2.7	8.2	89
2022	762,979	558,776	264,851	1,542,547	24	11	65
2023	924,582	315,190	0	1,516,664	17	0	83
2024	1,133,271	735,511	0	1,486,178	33	0	67
2025	1,341,329	944,833	0	1,453,224	39	0	61
2026	1,255,251	600,057	0	1,503,864	29	0	71
2027	0	0	0	0	29	0	71
2028	0	0	0	0	0	0	0
2029	0	0	0	0	0	0	0

Table A.8: Exposed Pit Wall Lithological Proportions (End of Mining) (Agnico Eagle 2020d)

Lithology	Tiriganiaq Pit 1	Tiriganiaq Pit 2	Tiriganiaq Pit 1	Tiriganiaq Pit 2
	m ²	m ²	%	%
Overburden	72,082	27,566	19	31
Gabbro	8,901	1.0	2.3	0.0011
Lamprophyre	0	0	0	0
Iron Formation	15,715	21,383	4.1	24
KMG	2,160	0	0.56	0
Ultramafic	0	0	0	0
Greywacke-Siltstone	6,140	0	1.6	0
Oxidized Sediment	47,353	39,221	12	44
Sericitized Volcanic	25,557	0	6.6	0
Volcanic	95,943	0	25	0
Sediment	110,711	0	29	0
Undefined	0	0	0	0

ANNEX B – POND STORAGE CURVES

Table B.1: CP1 Storage Curve

CP1 (Lake H17)		
Pond Elev. (m)	Pond Area (m ²)	Pond Volume (m ³)
62.35	426	30
63	98,197	25,435
63.5	156,178	90,591
64	205,492	180,734
64.5	240,203	293,805
65	257,682	418,861
65.5	267,816	550,474
66	276,175	686,494
66.5	284,528	826,705
66.99	292,023	968,025
67	292,181	970,947

Table B.4: CP5 Storage Curve

CP5 (Drained Lake A54)		
Pond Elev. (m)	Pond Area (km ²)	Pond Volume (M m ³)
64.50	0.001	0.000
65.00	0.016	0.003
65.50	0.044	0.018
66.00	0.071	0.047
66.50	0.084	0.085

Table B.6: SP2 Storage Curve

SP2		
Pond Elev. (m)	Pond Area (m ²)	Pond Volume (m ³)
45.38	0	0
45.90	13	2
46.00	25	4
47.00	1,833	560
48.00	3,394	3,411
50.00	3,851	10,747
55.00	5,252	32,858
60.00	6,431	61,979
62.00	6,962	75,372
62.80	7,205	81,037

Table B.8: Tiri 1 Storage Curve

Mined-out Tiri_1000_01		
Pond Volume (m ³)	Pond Elev. (m)	Pond Area (m ²)
0	-70.0	0
3,721	-65.0	1,363
5,295	-64.0	1,723
7,148	-63.0	1,979
9,254	-62.0	2,236
11,651	-61.0	2,577
14,434	-60.0	2,966
17,589	-59.0	3,349
21,149	-58.0	3,743
25,029	-57.0	4,015
29,180	-56.0	4,292
33,634	-55.0	4,615
38,415	-54.0	4,956
43,542	-53.0	5,289
48,982	-52.0	5,588
54,716	-51.0	5,879
60,742	-50.0	6,174
106,249	-45.0	11,040
259,589	-35.0	17,647
353,880	-30.0	20,964
631,356	-20.0	34,091
809,748	-15.0	37,175
1,003,820	-10.0	40,683
1,219,743	-5.0	53,430
1,509,384	0.0	61,221
1,829,069	5.0	66,497
2,174,492	10.0	71,836

Table B.9: Tiri 2 Storage Curve

Mined-out Tiri_1000_02		
Pond Volume (m ³)	Pond Elev. (m)	Pond Area (m ²)
0	-25.00	0
14,676	-20.00	3,453
36,554	-15.00	5,138
66,004	-10.00	6,631
102,748	-5.00	8,106
148,929	0.00	12,153
294,684	10.00	16,483
482,581	20.00	23,902
755,723	30.00	29,860
1,081,424	40.00	39,404
1,521,715	50.00	47,432
2,032,401	60.00	56,202
2,311,179	64.00	75,110
2,546,311	66.99	81,444

Table B.2: CP3 Storage Curve

CP3		
Pond Elev. (m)	Pond Area (m ²)	Pond Volume (m ³)
53.476	0	0
58.476	5,060	15,254
58.576	5,103	15,764
58.676	5,146	16,279
58.776	5,191	16,798
58.876	5,236	17,321
58.976	5,283	17,850
59.076	5,329	18,382
59.176	5,375	18,920
59.276	5,424	19,462
60.176	5,929	24,595
61.176	6,753	30,943
62.176	7,882	38,315
63.176	9,420	46,993
64.076	10,936	56,245
65.076	11,848	67,746

Table B.5: CP6 Storage Curve

CP6 (Drained H19)		
Pond Elev. (m)	Pond Area (km ²)	Pond Volume (M m ³)
62.80	0.008	0.0023
63.30	0.021	0.0105
63.50	0.032	0.0160
64.00	0.045	0.0348
64.50	0.053	0.0595

Table B.7: SP3 Storage Curve

SP3		
Pond Elev. (m)	Pond Area (m ²)	Pond Volume (m ³)
66.9	175	0
67	710	44
67.1	1,606	160
67.5	2,853	1,212
67.9	3,039	2,390
68	3,086	2,696
68.5	3,327	4,299
69	3,575	6,024
69.5	3,830	7,875
70	4,093	9,856

Table B.3: CP4 Storage Curve

CP4		
Pond Elev. (m)	Pond Area (m ²)	Pond Volume (m ³)
51.79	0	0.1
52.3	576	94.1
52.4	974	177.8
53	2,626	1,443.5
54	3,091	4,369.1
55	3,345	7,588.3
60	5,546	28,194.6
62.01	7,462	41,270.0
63	8,455	49,141.9

Table B.6: SP1 Storage Curve

SP1		
Pond Elev. (m)	Pond Area (m ²)	Pond Volume (m ³)
52.9	0	0
57.9	3,104	11701.22
58	3,121	12013.28
59	3,458	15286.57
60	4,160	19158.03
61	4,502	23522.08
62	4,805	28188.13
62.9	5,185	32686.12

ANNEX C – WATERSHED AREAS

Table C.1: Annual Watershed Areas - TSF and Pits

Year	TSF				Open Pit - Tiri_1000_01			Open Pit - Tiri_1000_02		
	Portion of TSF Waste Rock Cover Surface Where the Runoff Is Collected in CP1	Portion of TSF Tailings Surface Where the Runoff Is Collected in CP1	Portion of TSF Waste Rock Cover Surface Where the Runoff Is Collected in CP3	Portion of TSF Tailings Surface Where the Runoff Is Collected in CP3	Total Catchment Area	Catchment Area for Natural Ground with Vegetation	Pit Footprint Area	Total Catchment Area	Catchment Area for Natural Ground with Vegetation	Pit Footprint Area
	km ²	km ²	km ²	km ²	km ²	km ²	km ²	km ²	km ²	km ²
2020	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069
2021	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069
2022	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069
2023	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069
2024	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069
2025	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069
2026	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069
2027	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069
2028	0.128	0.061	0.128	0.035	0.322	0.055	0.266	0.167	0.099	0.069

Table C.2: Annual Watershed Areas - Collection Ponds

Year	CP1		CP3		CP4		CP5		CP6		CP7	
	Total Catchment Area	Catchment Area for Natural Ground with Vegetation	Total Catchment Area	Catchment Area for Natural Ground with Vegetation	Total Catchment Area	Catchment Area for Natural Ground with Vegetation	Total Catchment Area	Catchment Area for Natural Ground with Vegetation	Total Catchment Area	Catchment Area for Natural Ground with Vegetation	Total Catchment Area	Catchment Area for Natural Ground with Vegetation
	km ²	km ²	km ²	km ²	km ²	km ²	km ²	km ²	km ²	km ²	km ²	km ²
2020	1.785	0.773	0.240	0.073	0.301	0.234	0.499	0.323	0.439	0.112	0.683	0.683
2021	1.698	0.647	0.240	0.073	0.301	0.187	0.499	0.326	0.439	0.112	0.683	0.683
2022	1.698	0.647	0.240	0.073	0.301	0.139	0.499	0.326	0.439	0.112	0.683	0.683
2023	1.698	0.647	0.240	0.073	0.301	0.139	0.499	0.326	0.439	0.112	0.683	0.683
2024	1.698	0.647	0.240	0.073	0.301	0.139	0.499	0.326	0.439	0.112	0.683	0.427
2025	1.698	0.647	0.240	0.073	0.301	0.139	0.499	0.326	0.439	0.112	0.683	0.427
2026	1.698	0.647	0.240	0.073	0.301	0.139	0.499	0.326	0.439	0.112	0.683	0.427
2027	1.698	0.647	0.240	0.073	0.301	0.139	0.499	0.326	0.439	0.112	0.683	0.427
2028	1.698	0.647	0.240	0.073	0.301	0.139	0.499	0.326	0.439	0.112	0.683	0.427

Table C.3: Annual Watershed Areas - Landfarm, Landfill, P Area

Year	Landfarm	Landfarm Ext	Landfill	P_Area
	Footprint	Footprint	Footprint	Total Catchment Area for P1, P2 and P3 (not including SP3)
	km ²	km ²	km ²	km ²
2020	0.010	0.000	0.013	0.046
2021	0.010	0.000	0.013	0.000
2022	0.010	0.021	0.013	0.000
2023	0.010	0.021	0.013	0.000
2024	0.010	0.021	0.013	0.000
2025	0.010	0.021	0.013	0.000
2026	0.010	0.021	0.013	0.000
2027	0.010	0.021	0.013	0.000
2028	0.010	0.021	0.013	0.000

Table C.4: Annual Watershed Areas - WRSF and Ore Stockpiles

Year	WRSF1			WRSF3	WRSF3Ext	Temporary WRSF		OP2	OPExt
	Total Footprint	WRSF	Overburden	Total Footprint	Total Catchment Area	Total Footprint	Footprint to Tiri 2	Total Footprint	Total Footprint
	km ²	km ²		km ²	km ²	km ²	km ²	km ²	km ²
2020	0.121	0.027	0.094	0.314	0.000	0.055	0.008	0.103	0.000
2021	0.315	0.315	0.000	0.314	0.000	0.055	0.008	0.103	0.000
2022	0.315	0.315	0.000	0.314	0.243	0.055	0.008	0.103	0.063
2023	0.315	0.315	0.000	0.314	0.243	0.055	0.008	0.103	0.063
2024	0.315	0.315	0.000	0.314	0.243	0.055	0.008	0.103	0.063
2025	0.315	0.315	0.000	0.314	0.243	0.055	0.008	0.103	0.063
2026	0.315	0.315	0.000	0.314	0.243	0.055	0.008	0.103	0.063
2027	0.315	0.315	0.000	0.314	0.243	0.055	0.008	0.103	0.063
2028	0.315	0.315	0.000	0.314	0.243	0.055	0.008	0.103	0.063

APPENDIX B

**Tabulated Water Balance Results,
Average Year (Base Case)
Scenario**

Water Balance for TSF

Date	Inflow		Outflow					
			The Portion to CP1			The Portion to CP3		
	Total Surface Runoff Water from TSF	Estimated Volume of Seepage through Tailings	TSF Tailings Surface Runoff Collected in CP1	TSF Waste Rock Cover Runoff Water Collected in CP1	Seepage Water through Tailings into CP1	TSF Tailings Surface Runoff Collected in CP3	TSF Waste Rock Cover Runoff Water Collected in CP3	Seepage Water through Tailings into CP3
	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³
May-20	0	0	0	0	0	0	0	0
Jun-20	40112	178	6951	14586	113	3988	14586	65
Jul-20	13214	178	2290	4805	113	1314	4805	65
Aug-20	14396	178	2495	5235	113	1431	5235	65
Sep-20	10767	178	1866	3915	113	1071	3915	65
Oct-20	10812	178	1874	3932	113	1075	3932	65
Nov-20	0	0	0	0	0	0	0	0
Dec-20	0	0	0	0	0	0	0	0
Jan-21	0	0	0	0	0	0	0	0
Feb-21	0	0	0	0	0	0	0	0
Mar-21	0	0	0	0	0	0	0	0
Apr-21	0	0	0	0	0	0	0	0
May-21	0	0	0	0	0	0	0	0
Jun-21	40112	178	6951	14586	113	3988	14586	65
Jul-21	13214	178	2290	4805	113	1314	4805	65
Aug-21	14396	178	2495	5235	113	1431	5235	65
Sep-21	10767	178	1866	3915	113	1071	3915	65
Oct-21	10812	178	1874	3932	113	1075	3932	65
Nov-21	0	0	0	0	0	0	0	0
Dec-21	0	0	0	0	0	0	0	0
Jan-22	0	0	0	0	0	0	0	0
Feb-22	0	0	0	0	0	0	0	0
Mar-22	0	0	0	0	0	0	0	0
Apr-22	0	0	0	0	0	0	0	0
May-22	0	0	0	0	0	0	0	0
Jun-22	40112	178	6951	14586	113	3988	14586	65
Jul-22	13214	178	2290	4805	113	1314	4805	65
Aug-22	14396	178	2495	5235	113	1431	5235	65
Sep-22	10767	178	1866	3915	113	1071	3915	65
Oct-22	10812	178	1874	3932	113	1075	3932	65
Nov-22	0	0	0	0	0	0	0	0
Dec-22	0	0	0	0	0	0	0	0
Jan-23	0	0	0	0	0	0	0	0
Feb-23	0	0	0	0	0	0	0	0
Mar-23	0	0	0	0	0	0	0	0
Apr-23	0	0	0	0	0	0	0	0
May-23	0	0	0	0	0	0	0	0
Jun-23	40112	178	6951	14586	113	3988	14586	65
Jul-23	13214	178	2290	4805	113	1314	4805	65
Aug-23	14396	178	2495	5235	113	1431	5235	65
Sep-23	10767	178	1866	3915	113	1071	3915	65

Water Collection from Ore Stockpiles

Date	OP2		OP2-Extn.	
	Total Water to be Collected	Portion of the Water to be Collected in CP5 (Lake A54)	Total Water to be Collected	Portion of the Water to be Collected in Tiri-1000-02
	m ³	m ³	m ³	m ³
May-20	0	0	0	0
Jun-20	0	0	0	0
Jul-20	0	0	0	0
Aug-20	0	0	0	0
Sep-20	0	0	0	0
Oct-20	918	918	0	0
Nov-20	14	14	0	0
Dec-20	18	18	0	0
Jan-21	5	5	0	0
Feb-21	0	0	0	0
Mar-21	0	0	0	0
Apr-21	0	0	0	0
May-21	0	0	0	0
Jun-21	0	0	0	0
Jul-21	0	0	0	0
Aug-21	0	0	0	0
Sep-21	0	0	0	0
Oct-21	918	918	0	0
Nov-21	14	14	0	0
Dec-21	18	18	0	0
Jan-22	5	5	0	0
Feb-22	0	0	0	0
Mar-22	0	0	0	0
Apr-22	0	0	0	0
May-22	0	0	0	0
Jun-22	0	0	0	0
Jul-22	0	0	0	0
Aug-22	0	0	0	0
Sep-22	0	0	0	0
Oct-22	918	918	561	561
Nov-22	14	14	8	8
Dec-22	18	18	11	11
Jan-23	5	5	3	3
Feb-23	0	0	0	0
Mar-23	0	0	0	0
Apr-23	0	0	0	0
May-23	0	0	0	0
Jun-23	0	0	0	0
Jul-23	0	0	0	0
Aug-23	0	0	0	0
Sep-23	0	0	0	0
Oct-23	918	918	561	561

Water Collection from Ore Stockpiles

Date	OP2		OP2-Extn.	
	Total Water to be Collected	Portion of the Water to be Collected in CP5 (Lake A54)	Total Water to be Collected	Portion of the Water to be Collected in Tiri-1000-02
	m ³	m ³	m ³	m ³
Nov-23	14	14	8	8
Dec-23	18	18	11	11
Jan-24	5	5	3	3
Feb-24	0	0	0	0
Mar-24	0	0	0	0
Apr-24	0	0	0	0
May-24	0	0	0	0
Jun-24	0	0	0	0
Jul-24	0	0	0	0
Aug-24	0	0	0	0
Sep-24	0	0	0	0
Oct-24	918	918	561	561
Nov-24	14	14	8	8
Dec-24	18	18	11	11
Jan-25	5	5	3	3
Feb-25	0	0	0	0
Mar-25	0	0	0	0
Apr-25	0	0	0	0
May-25	0	0	0	0
Jun-25	0	0	0	0
Jul-25	0	0	0	0
Aug-25	0	0	0	0
Sep-25	0	0	0	0
Oct-25	918	918	561	561
Nov-25	14	14	8	8
Dec-25	18	18	11	11
Jan-26	5	5	3	3
Feb-26	0	0	0	0
Mar-26	0	0	0	0
Apr-26	0	0	0	0
May-26	0	0	0	0
Jun-26	0	0	0	0
Jul-26	0	0	0	0
Aug-26	0	0	0	0
Sep-26	0	0	0	0
Oct-26	918	918	561	561
Nov-26	14	14	8	8
Dec-26	18	18	11	11
Jan-27	5	5	3	3
Feb-27	0	0	0	0
Mar-27	0	0	0	0
Apr-27	0	0	0	0

Water Collection from Ore Stockpiles

Date	OP2		OP2-Extn.	
	Total Water to be Collected	Portion of the Water to be Collected in CP5 (Lake A54)	Total Water to be Collected	Portion of the Water to be Collected in Tiri-1000-02
	m ³	m ³	m ³	m ³
May-27	0	0	0	0
Jun-27	0	0	0	0
Jul-27	0	0	0	0
Aug-27	0	0	0	0
Sep-27	0	0	0	0
Oct-27	918	918	561	561
Nov-27	14	14	8	8
Dec-27	18	18	11	11
Jan-28	5	5	3	3
Feb-28	0	0	0	0
Mar-28	0	0	0	0
Apr-28	0	0	0	0
May-28	0	0	0	0
Jun-28	0	0	0	0
Jul-28	0	0	0	0
Aug-28	0	0	0	0
Sep-28	0	0	0	0
Oct-28	918	918	561	561
Nov-28	14	14	8	8
Dec-28	18	18	11	11

Water Balance for Open Pits																		
Date	Tiri-1						Tiri-2											
	Inflow			Outflow		Storage	Inflow				Outflow						Storage	
	Net Runoff/Run on Water from Water Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Water Pumped to CP5 and transfer to CP1	Water lost to WRF/Ore		Water Stored in Open Pit	Net Runoff/Run on Water from Water Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Net runoff from Temporary WRSF	Inflow from UG	Water Pumped to CP5	Water Lost to WRSF and Ore	To SP-1	Water Pumped to SETP		Water through Bypass
m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³	m³
May-20	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Jun-20	0	0	0	0	0	0	0	10623	7831	74	0	0	18527	0	0	0	0	0
Jul-20	0	0	0	0	0	0	0	2264	2580	1	0	2274	2571	0	0	0	0	0
Aug-20	0	0	0	0	0	0	0	2995	2810	1	0	3236	2571	0	0	0	0	0
Sep-20	0	0	0	0	0	0	0	2614	2102	0	0	2145	2571	0	0	0	0	0
Oct-20	0	0	0	0	0	0	0	2863	2111	0	0	2402	2571	0	0	0	0	0
Nov-20	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Dec-20	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Jan-21	0	0	0	0	0	0	0	0	0	0	0	17521	0	0	0	0	0	17521
Feb-21	0	0	0	0	0	0	0	0	0	0	0	15631	0	0	0	0	0	33152
Mar-21	0	0	0	0	0	0	0	0	0	0	0	17521	0	0	0	0	0	50673
Apr-21	0	0	0	0	0	0	0	0	0	0	0	17491	0	0	0	0	0	68164
May-21	0	0	0	0	0	0	0	0	0	0	0	18141	0	0	0	0	0	86305
Jun-21	0	5972	23860	28376	1457	0	455	10623	7024	74	17491	0	2795	0	0	0	0	119176
Jul-21	0	1273	7860	8951	182	0	-684	2264	2273	1	19071	0	349	0	0	0	0	141752
Aug-21	0	1684	8563	10065	182	0	-279	2995	2420	1	19071	0	349	0	0	0	0	165612
Sep-21	0	1469	6404	7692	182	0	89	2614	1746	0	0	0	349	0	0	0	0	169711
Oct-21	0	1610	6431	7859	182	0	734	2863	1707	0	0	0	349	0	0	0	0	174666
Nov-21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	174666
Dec-21	0	0	0	0	0	0	0	0	0	0	0	19691	0	0	0	0	0	194357
Jan-22	0	0	0	0	0	0	0	0	0	0	0	21232	0	0	0	0	0	215588
Feb-22	0	0	0	0	0	0	0	0	0	0	0	18982	0	0	0	0	0	234570
Mar-22	0	0	0	0	0	0	0	0	0	0	0	21232	0	0	0	0	0	255801
Apr-22	0	0	0	0	0	0	0	0	0	0	0	20482	0	0	0	0	0	276283
May-22	0	0	0	0	0	0	0	0	0	0	0	21232	0	0	0	0	0	297515
Jun-22	0	5972	23860	7550	22283	0	1048	10623	5971	74	20482	0	3510	0	0	0	0	332202
Jul-22	0	1273	7860	6348	2785	0	-1419	2264	1945	1	0	0	439	0	0	657	0	333897
Aug-22	0	1684	8563	7462	2785	0	-505	2995	2103	1	0	0	439	0	69841	93000	175211	
Sep-22	0	1469	6404	5088	2785	0	118	2614	1632	0	22282	0	439	0	88861	90000	22556	
Oct-22	0	1610	6431	5256	2785	0	494	2863	1839	0	23092	0	439	0	0	0	0	50405
Nov-22	0	0	0	0	0	0	0	0	0	0	0	22282	0	0	0	0	0	72686
Dec-22	0	0	0	0	0	0	0	0	0	0	0	23092	0	0	0	0	0	95778
Jan-23	0	0	0	0	0	0	0	0	0	0	0	24016	0	0	0	0	0	119794
Feb-23	0	0	0	0	0	0	0	0	0	0	0	21496	0	0	0	0	0	141290
Mar-23	0	0	0	0	0	0	0	0	0	0	0	24016	0	0	0	0	0	165306
Apr-23	0	0	0	0	0	0	0	0	0	0	0	23176	0	0	0	0	0	188483
May-23	0	0	0	0	0	0	0	0	0	0	0	24016	0	0	0	0	0	212499
Jun-23	0	5972	30356	14000	22328	0	910	10623	6216	74	23176	0	0	0	39573	45000	168924	
Jul-23	0	1273	10000	8482	2791	0	-1163	2264	2059	1	24016	0	0	0	93662	93000	9440	
Aug-23	0	1684	10894	9787	2791	0	-238	2995	2477	1	24016	0	0	0	38691	0	0	0
Sep-23	0	1469	8148	6826	2791	0	0	2614	2054	0	23176	0	0	19940	7905	0	0	0
Oct-23	0	1610	8182	7001	2791	0	0	2863	2111	0	24016	0	0	0	0	0	0	28990
Nov-23	0	0	0	0	0	0	0	0	0	0	0	23176	0	0	0	0	0	52166
Dec-23	0	0	0	0	0	0	0	0	0	0	0	24016	0	0	0	0	0	76182
Jan-24	0	0	0	0	0	0	0	0	0	0	0	24319	0	0	0	0	0	100501
Feb-24	0	0	0	0	0	0	0	0	0	0	0	22619	0	0	0	0	0	123120
Mar-24	0	0	0	0	0	0	0	0	0	0	0	24319	0	0	0	0	0	147438
Apr-24	0	0	0	0	0	0	0	0	0	0	0	23469	0	0	0	0	0	170907
May-24	0	0	0	0	0	0	0	0	0	0	0	24319	0	0	0	0	0	195225
Jun-24	0	5972	30356	0	48989	0	876	10623	6276	74	23469	0	0	44052	45000	164790	0	0
Jul-24	0	1273	10000	5149	6124	0	-1037	2264	2116	1	24319	0	0	0	93662	81490	0	0
Aug-24	0	1684	10894	6455	6124	0	0	2995	2592	1	24319	0	0	0	29907	0	0	0
Sep-24	0	1469	8148	3494	6124	0	0	2614	2102	0	23469	0	0	19940	8245	0	0	0
Oct-24	0	1610	8182	3668	6124	0	0	2863	2111	0	24319	0	0	0	0	0	0	29292
Nov-24	0	0	0	0	0	0	0	0	0	0	0	23469	0	0	0	0	0	52761
Dec-24	0	0	0	0	0	0	0	0	0	0	0	24319	0	0	0	0	0	77079
Jan-25	0	0	0	0	0	0	0	0	0	0	0	27061	0	0	0	0	0	104141
Feb-25	0	0	0	0	0	0	0	0	0	0	0	24271	0	0	0	0	0	128412
Mar-25	0	0	0	0	0	0	0	0	0	0	0	27061	0	0	0	0	0	155474
Apr-25	0	0	0	0	0	0	0	0	0	0	0	26131	0	0	0	0	0	181605
May-25	0	0	0	0	0	0	0	0	0	0	0	27061	0	0	0	0	0	208667
Jun-25	0	5972	30356	0	41784	0	900	10623	6234	0	26131	0	0	44052	45000	163502	0	0
Jul-25	0	1273	10000	6050	5223	0	-1149	2264	2066	0	27061	0	0	0	93662	93000	7082	0
Aug-25	0	1684	10894	7355	5223	0	-233	2995	2484	0	27061	0	0	0	39391	0	0	0
Sep-25	0	1469	8148	4394	5223	0	0	2614	2056	0	26131	0	0	19940	10862	0	0	0
Oct-25	0	1610	8182	4569	5223	0	0	2863	2111	0	27061	0	0	0	0	0	0	32035
Nov-25	0	0	0	0	0	0	0	0	0	0	0	26131	0	0	0	0	0	58167
Dec-25	0	0	0	0	0	0	0	0	0	0	0	27061	0	0	0	0	0	85228
Jan-26	0	0	0	0	0	0	0	0	0	0	0	27822	0	0	0	0	0	113050
Feb-26	0	0	0	0	0	0	0	0	0	0	0	24972	0	0	0	0	0	138022
Mar-26	0	0	0	0	0	0	0	0	0	0	0	27822	0	0	0	0	0	165844
Apr-26	0	0	0	0	0	0	0	0	0	0	0	26872	0	0	0	0	0	192716
May-26	0	0	0	0	0	0	0	0	0	0	0	27822	0	0	0	0	0	220539
Jun-26	0	5972	30356	9231	27097	0	921	10623	6196	0	26872	0	0	0	44052	45000	176098	0
Jul-26	0	1273	10000	7886	3387	0	-1182	2264	2051	0	27822	0	0	0	93662	93000	20391	0
Aug-26	0	1684	10894	9191	3387	0	-256	2995	2452	0	27822	0	0	0	53404	0	0	0
Sep-26	0	1469	8148	6230	3387	0	0	2614	2040	0	26872	0	0	19940	11586	0	0	0
Oct-26	0	1610	8182	6405	3387	0	0	2863	2111	0	27822	0	0	0	0	0	0	32796
Nov-26	0	0	0	0	0	0	0	0	0	0	0	26872	0	0	0	0	0	59668

Water Balance for Open Pits

Date	Tiri-1						Tiri-2										
	Inflow			Outflow		Storage	Inflow					Outflow					Storage
	Net Runoff/Run on Water from Water Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Water Pumped to CP5 and transfer to CP1	Water lost to WRF/Ore	Water Stored in Open Pit	Net Runoff/Run on Water from Water Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Net runoff from Temporary WRSF	Inflow from UG	Water Pumped to CP5	Water Lost to WRSF and Ore	To SP-1	Water Pumped to SETP	Water through Bypass	Water Stored in Open Pit
	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³
Dec-26	0	0	0	0	0	0	0	0	0	0	27822	0	0	0	0	0	87490
Jan-27	0	0	0	0	0	0	0	0	0	0	26040	0	0	0	0	0	113530
Feb-27	0	0	0	0	0	0	0	0	0	0	23520	0	0	0	0	0	137050
Mar-27	0	0	0	0	0	0	0	0	0	0	26040	0	0	0	0	0	163090
Apr-27	0	0	0	0	0	0	0	0	0	0	25200	0	0	0	0	0	188290
May-27	0	0	0	0	0	0	0	0	0	0	26040	0	0	0	0	0	214330
Jun-27	0	5972	30356	0	0	36328	912	10623	6213	0	25200	0	0	0	44052	45000	168225
Jul-27	-200	1273	9910	0	0	47311	-1164	2264	2059	0	26040	0	0	0	93662	93000	10762
Aug-27	-204	1684	10609	0	0	59400	-239	2995	2475	0	26040	0	0	0	42034	0	0
Sep-27	90	1469	7788	0	0	68747	0	2614	2053	0	25200	0	0	19940	9927	0	0
Oct-27	859	1610	7710	0	0	78925	0	2863	2111	0	26040	0	0	0	0	0	31014
Nov-27	0	0	0	0	0	78925	0	0	0	0	25200	0	0	0	0	0	56214
Dec-27	0	0	0	0	0	78925	0	0	0	0	26040	0	0	0	0	0	82254
Jan-28	0	0	0	0	0	78925	0	0	0	0	26970	0	0	0	0	0	109224
Feb-28	0	0	0	0	0	78925	0	0	0	0	25230	0	0	0	0	0	134454
Mar-28	0	0	0	0	0	78925	0	0	0	0	26970	0	0	0	0	0	161424
Apr-28	0	0	0	0	0	78925	0	0	0	0	26100	0	0	0	0	0	187524
May-28	0	0	0	0	0	78925	0	0	0	0	26970	0	0	0	0	0	214494
Jun-28	2380	5972	26133	0	0	113411	911	10623	6214	0	26100	0	0	0	0	0	258342
Jul-28	-3247	1273	8547	0	0	119984	-1270	2264	2011	0	26970	0	0	0	0	0	288318
Aug-28	-1196	1684	9220	0	0	129692	-468	2995	2155	0	26970	0	0	0	0	0	319970
Sep-28	337	1469	6800	0	0	138299	128	2614	1591	0	26100	0	0	19885	0	0	330518
Oct-28	2893	1610	6591	0	0	149392	957	2863	1584	0	26970	0	0	0	0	0	362892
Nov-28	0	0	0	0	0	149392	0	0	0	0	26100	0	0	0	0	0	388992
Dec-28	0	0	0	0	0	149392	0	0	0	0	26970	0	0	0	0	0	415962

Water Balance for CP3					
Date	Inflow				Outflow
	Net Runoff/Run on Water from Pond Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Net Runoff/Seepage Water from a Portion of TSF to CP3	Water Pumped from CP3 to Site Area Ditch, then Flowing into CP1
	m ³	m ³	m ³	m ³	m ³
May-20	0	0	0	0	0
Jun-20	258	7856	0	18640	26754
Jul-20	-337	1675	0	6184	7522
Aug-20	-117	2215	0	6731	8829
Sep-20	31	1933	0	5051	7014
Oct-20	224	2118	0	5072	7413
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	258	7856	0	18640	26754
Jul-21	-337	1675	0	6184	7522
Aug-21	-117	2215	0	6731	8829
Sep-21	31	1933	0	5051	7014
Oct-21	224	2118	0	5072	7413
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	258	7856	0	18640	26754
Jul-22	-337	1675	0	6184	7522
Aug-22	-117	2215	0	6731	8829
Sep-22	31	1933	0	5051	7014
Oct-22	224	2118	0	5072	7413
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	258	7856	0	18640	26754
Jul-23	-337	1675	0	6184	7522
Aug-23	-117	2215	0	6731	8829
Sep-23	31	1933	0	5051	7014
Oct-23	224	2118	0	5072	7413
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	258	7856	0	18640	26754
Jul-24	-337	1675	0	6184	7522
Aug-24	-117	2215	0	6731	8829
Sep-24	31	1933	0	5051	7014
Oct-24	224	2118	0	5072	7413
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0
Jun-25	258	7856	0	18640	26754
Jul-25	-337	1675	0	6184	7522
Aug-25	-117	2215	0	6731	8829
Sep-25	31	1933	0	5051	7014
Oct-25	224	2118	0	5072	7413
Nov-25	0	0	0	0	0
Dec-25	0	0	0	0	0
Jan-26	0	0	0	0	0
Feb-26	0	0	0	0	0
Mar-26	0	0	0	0	0
Apr-26	0	0	0	0	0
May-26	0	0	0	0	0
Jun-26	258	7856	0	18640	26754
Jul-26	-337	1675	0	6184	7522
Aug-26	-117	2215	0	6731	8829
Sep-26	31	1933	0	5051	7014
Oct-26	224	2118	0	5072	7413
Nov-26	0	0	0	0	0
Dec-26	0	0	0	0	0
Jan-27	0	0	0	0	0
Feb-27	0	0	0	0	0
Mar-27	0	0	0	0	0
Apr-27	0	0	0	0	0
May-27	0	0	0	0	0
Jun-27	258	7856	0	18640	26754
Jul-27	-337	1675	0	6184	7522
Aug-27	-117	2215	0	6731	8829
Sep-27	31	1933	0	5051	7014
Oct-27	224	2118	0	5072	7413
Nov-27	0	0	0	0	0
Dec-27	0	0	0	0	0
Jan-28	0	0	0	0	0
Feb-28	0	0	0	0	0
Mar-28	0	0	0	0	0
Apr-28	0	0	0	0	0
May-28	0	0	0	0	0
Jun-28	258	7856	0	18640	26754
Jul-28	-337	1675	0	6184	7522

Water Balance for CP4					
Date	Inflow				Outflow
	Net Runoff/Run on Water from Pond Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground	Net Runoff/Seepage Water from a Portion of WRSF to CP4	Water pumped from CP4 to Site Area Ditch, then Flowing into CP1
	m ³	m ³	m ³	m ³	m ³
May-20	0	0	0	0	0
Jun-20	465	25239	59	528	26291
Jul-20	-608	5388	19	8	4799
Aug-20	-212	7117	21	10	6937
Sep-20	55	6210	16	3	6284
Oct-20	404	6803	16	0	7223
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	465	20101	76	952	21594
Jul-21	-608	4285	25	14	3716
Aug-21	-212	5668	27	19	5503
Sep-21	55	4946	20	3	5027
Oct-21	404	5418	21	0	5843
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	465	14964	94	1375	16898
Jul-22	-608	3190	31	20	2633
Aug-22	-212	4219	34	27	4069
Sep-22	55	3682	25	8	3770
Oct-22	404	4033	25	0	4463
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	465	14964	94	1375	16898
Jul-23	-608	3190	31	20	2633
Aug-23	-212	4219	34	27	4069
Sep-23	55	3682	25	8	3770
Oct-23	404	4033	25	0	4463
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	465	14964	94	1375	16898
Jul-24	-608	3190	31	20	2633
Aug-24	-212	4219	34	27	4069
Sep-24	55	3682	25	8	3770
Oct-24	404	4033	25	0	4463
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0
Jun-25	465	14964	94	1375	16898
Jul-25	-608	3190	31	20	2633
Aug-25	-212	4219	34	27	4069
Sep-25	55	3682	25	8	3770
Oct-25	404	4033	25	0	4463
Nov-25	0	0	0	0	0
Dec-25	0	0	0	0	0
Jan-26	0	0	0	0	0
Feb-26	0	0	0	0	0
Mar-26	0	0	0	0	0
Apr-26	0	0	0	0	0
May-26	0	0	0	0	0
Jun-26	465	14964	94	1375	16898
Jul-26	-608	3190	31	20	2633
Aug-26	-212	4219	34	27	4069
Sep-26	55	3682	25	8	3770
Oct-26	404	4033	25	0	4463
Nov-26	0	0	0	0	0
Dec-26	0	0	0	0	0
Jan-27	0	0	0	0	0
Feb-27	0	0	0	0	0
Mar-27	0	0	0	0	0
Apr-27	0	0	0	0	0
May-27	0	0	0	0	0
Jun-27	465	14964	94	1375	16898
Jul-27	-608	3190	31	20	2633
Aug-27	-212	4219	34	27	4069
Sep-27	55	3682	25	8	3770
Oct-27	404	4033	25	0	4463
Nov-27	0	0	0	0	0
Dec-27	0	0	0	0	0
Jan-28	0	0	0	0	0
Feb-28	0	0	0	0	0
Mar-28	0	0	0	0	0
Apr-28	0	0	0	0	0
May-28	0	0	0	0	0
Jun-28	465	14964	94	1375	16898
Jul-28	-608	3190	31	20	2633

Water Balance for CP3					
Date	Inflow				Outflow
	Net Runoff/Run on Water from Pond Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Net Runoff/Seepage Water from a Portion of TSF to CP3	Water Pumped from CP3 to Site Area Ditch, then Flowing into CP1
	m ³	m ³	m ³	m ³	m ³
Aug-28	-117	2215	0	6731	8829
Sep-28	31	1933	0	5051	7014
Oct-28	224	2118	0	5072	7413
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

Water Balance for CP4					
Date	Inflow				Outflow
	Net Runoff/Run on Water from Pond Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground	Net Runoff/Seepage Water from a Portion of WRSF1 to CP4	Water pumped from CP4 to Site Area Ditch, then Flowing into CP1
	m ³	m ³	m ³	m ³	m ³
Aug-28	-212	4219	34	27	4069
Sep-28	55	3682	25	8	3770
Oct-28	404	4033	25	0	4463
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

Water Balance for CP5													
Date	Inflow											Outflow	
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground Surface with Vegetation	Net Runoff/Seepage Water from a Portion of WRSF1 to CP5	Net Runoff/Runon Water from Other Disturbed Ground	Water Pumped from Trl_1000_01 Open Pit to CP5	Water Pumped from Trl_1000_02 Open Pit to CP5	Water Pumped from Wesmeg_0 2/04 Open Pit to CP5	Treated Water from SWTP to CP5	Water Pumped from Downstream of D-CP5 to CP5	Water Pumped from Portal No 1 into CP5	Seepage Water from "A" Area into CP5	Water Pumped to CP1	Water Pumped from CP5 to RO Plant for Treatment
	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³
Aug-28	-1266	9891	7	3054	0	0		0			0	11686	0
Sep-28	331	8630	2	2284	0	0		0			0	11248	0
Oct-28	2420	9454	0	2293	0	0		0			0	14168	0
Nov-28	0	0	0	0	0	0		0			0	0	0
Dec-28	0	0	0	0	0	0		0			0	0	0

Water Balance for CP6					
Date	Inflow				Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Net Runoff/Seepage Water from WRSF3 and WRSF3 Exten.	Water Pumped from CP6 to CP1
	m ³	m ³	m ³	m ³	m ³
Aug-28	-399	3392	73	55	3120
Sep-28	104	2960	84	16	3134
Oct-28	763	3242	84	0	4059
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

Water Balance for CP2					
Date	Inflow				Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Net Runoff/Seepage Water from WRSF3 and WRSF3 Exten.	Water Pumped from CP7 to CP1
	m3	m3	m3	m3	m3
Aug-28	-399	12963	0	43	12607
Sep-28	104	11311	0	12	11428
Oct-28	763	12391	0	0	13153
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

Water Balance for P Area					
Date	Inflow			Outflow	
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Pumped to CP5	Water Seepage into CP5
	m ³	m ³	m ³	m ³	m ³
Aug-28					
Sep-28					
Oct-28					
Nov-28					
Dec-28					

Water Balance for Landfarm				
Date	Inflow			Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Disturbed Ground Surface	Snow Melting	Pre-Treated (Oil) Water from Landfarm/Biopile to CP1 though site area ditch
	m ³	m ³	m ³	m ³
May-20	0	0	0	0
Jun-20	13	1117	500	1630
Jul-20	-17	368	0	351
Aug-20	-6	401	0	395
Sep-20	2	300	0	301
Oct-20	11	301	0	312
Nov-20	0	0	0	0
Dec-20	0	0	0	0
Jan-21	0	0	0	0
Feb-21	0	0	0	0
Mar-21	0	0	0	0
Apr-21	0	0	0	0
May-21	0	0	0	0
Jun-21	13	1117	500	1630
Jul-21	-17	368	0	351
Aug-21	-6	401	0	395
Sep-21	2	300	0	301
Oct-21	11	301	0	312
Nov-21	0	0	0	0
Dec-21	0	0	0	0
Jan-22	0	0	0	0
Feb-22	0	0	0	0
Mar-22	0	0	0	0
Apr-22	0	0	0	0
May-22	0	0	0	0
Jun-22	13	3510	500	4023
Jul-22	-17	1156	0	1139
Aug-22	-6	1260	0	1254
Sep-22	2	942	0	944
Oct-22	11	946	0	957
Nov-22	0	0	0	0
Dec-22	0	0	0	0
Jan-23	0	0	0	0
Feb-23	0	0	0	0
Mar-23	0	0	0	0
Apr-23	0	0	0	0
May-23	0	0	0	0
Jun-23	13	3510	500	4023
Jul-23	-17	1156	0	1139
Aug-23	-6	1260	0	1254
Sep-23	2	942	0	944
Oct-23	11	946	0	957
Nov-23	0	0	0	0
Dec-23	0	0	0	0
Jan-24	0	0	0	0
Feb-24	0	0	0	0
Mar-24	0	0	0	0
Apr-24	0	0	0	0

Water Balance for Landfill			
Date	Inflow		Outflow
	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Disturbed Ground Surface	Water from Landfill to CP1 though site area ditch
	m ³	m ³	m ³
May-20	0	0	0
Jun-20	0	1512	1512
Jul-20	0	498	498
Aug-20	0	543	543
Sep-20	0	406	406
Oct-20	0	407	407
Nov-20	0	0	0
Dec-20	0	0	0
Jan-21	0	0	0
Feb-21	0	0	0
Mar-21	0	0	0
Apr-21	0	0	0
May-21	0	0	0
Jun-21	0	1512	1512
Jul-21	0	498	498
Aug-21	0	543	543
Sep-21	0	406	406
Oct-21	0	407	407
Nov-21	0	0	0
Dec-21	0	0	0
Jan-22	0	0	0
Feb-22	0	0	0
Mar-22	0	0	0
Apr-22	0	0	0
May-22	0	0	0
Jun-22	0	1512	1512
Jul-22	0	498	498
Aug-22	0	543	543
Sep-22	0	406	406
Oct-22	0	407	407
Nov-22	0	0	0
Dec-22	0	0	0
Jan-23	0	0	0
Feb-23	0	0	0
Mar-23	0	0	0
Apr-23	0	0	0
May-23	0	0	0
Jun-23	0	1512	1512
Jul-23	0	498	498
Aug-23	0	543	543
Sep-23	0	406	406
Oct-23	0	407	407
Nov-23	0	0	0
Dec-23	0	0	0
Jan-24	0	0	0
Feb-24	0	0	0
Mar-24	0	0	0
Apr-24	0	0	0

Water Balance for Landfarm				
Date	Inflow			Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Disturbed Ground Surface	Snow Melting	Pre-Treated (Oil) Water from Landfarm/Biopile to CP1 though site area ditch
	m ³	m ³	m ³	m ³
May-24	0	0	0	0
Jun-24	13	3510	500	4023
Jul-24	-17	1156	0	1139
Aug-24	-6	1260	0	1254
Sep-24	2	942	0	944
Oct-24	11	946	0	957
Nov-24	0	0	0	0
Dec-24	0	0	0	0
Jan-25	0	0	0	0
Feb-25	0	0	0	0
Mar-25	0	0	0	0
Apr-25	0	0	0	0
May-25	0	0	0	0
Jun-25	13	3510	500	4023
Jul-25	-17	1156	0	1139
Aug-25	-6	1260	0	1254
Sep-25	2	942	0	944
Oct-25	11	946	0	957
Nov-25	0	0	0	0
Dec-25	0	0	0	0
Jan-26	0	0	0	0
Feb-26	0	0	0	0
Mar-26	0	0	0	0
Apr-26	0	0	0	0
May-26	0	0	0	0
Jun-26	13	3510	500	4023
Jul-26	-17	1156	0	1139
Aug-26	-6	1260	0	1254
Sep-26	2	942	0	944
Oct-26	11	946	0	957
Nov-26	0	0	0	0
Dec-26	0	0	0	0
Jan-27	0	0	0	0
Feb-27	0	0	0	0
Mar-27	0	0	0	0
Apr-27	0	0	0	0
May-27	0	0	0	0
Jun-27	13	3510	500	4023
Jul-27	-17	1156	0	1139
Aug-27	-6	1260	0	1254
Sep-27	2	942	0	944
Oct-27	11	946	0	957
Nov-27	0	0	0	0
Dec-27	0	0	0	0
Jan-28	0	0	0	0
Feb-28	0	0	0	0
Mar-28	0	0	0	0
Apr-28	0	0	0	0

Water Balance for Landfill			
Date	Inflow		Outflow
	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Disturbed Ground Surface	Water from Landfill to CP1 though site area ditch
	m ³	m ³	m ³
May-24	0	0	0
Jun-24	0	1512	1512
Jul-24	0	498	498
Aug-24	0	543	543
Sep-24	0	406	406
Oct-24	0	407	407
Nov-24	0	0	0
Dec-24	0	0	0
Jan-25	0	0	0
Feb-25	0	0	0
Mar-25	0	0	0
Apr-25	0	0	0
May-25	0	0	0
Jun-25	0	1512	1512
Jul-25	0	498	498
Aug-25	0	543	543
Sep-25	0	406	406
Oct-25	0	407	407
Nov-25	0	0	0
Dec-25	0	0	0
Jan-26	0	0	0
Feb-26	0	0	0
Mar-26	0	0	0
Apr-26	0	0	0
May-26	0	0	0
Jun-26	0	1512	1512
Jul-26	0	498	498
Aug-26	0	543	543
Sep-26	0	406	406
Oct-26	0	407	407
Nov-26	0	0	0
Dec-26	0	0	0
Jan-27	0	0	0
Feb-27	0	0	0
Mar-27	0	0	0
Apr-27	0	0	0
May-27	0	0	0
Jun-27	0	1512	1512
Jul-27	0	498	498
Aug-27	0	543	543
Sep-27	0	406	406
Oct-27	0	407	407
Nov-27	0	0	0
Dec-27	0	0	0
Jan-28	0	0	0
Feb-28	0	0	0
Mar-28	0	0	0
Apr-28	0	0	0

Water Balance for Landfarm				
Date	Inflow			Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Disturbed Ground Surface	Snow Melting	Pre-Treated (Oil) Water from Landfarm/Biopile to CP1 through site area ditch
	m ³	m ³	m ³	m ³
May-28	0	0	0	0
Jun-28	13	3510	500	4023
Jul-28	-17	1156	0	1139
Aug-28	-6	1260	0	1254
Sep-28	2	942	0	944
Oct-28	11	946	0	957
Nov-28	0	0	0	0
Dec-28	0	0	0	0

Water Balance for Landfill			
Date	Inflow		Outflow
	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Disturbed Ground Surface	Water from Landfill to CP1 through site area ditch
	m ³	m ³	m ³
May-28	0	0	0
Jun-28	0	1512	1512
Jul-28	0	498	498
Aug-28	0	543	543
Sep-28	0	406	406
Oct-28	0	407	407
Nov-28	0	0	0
Dec-28	0	0	0

Water Balance for EWTP

Date	Inflow			Outflow	
	Water from CP1 to EWTP	Water from CP5 to EWTP	RO Premeate To EWTP	Water from EWTP to SP3	Discharge to Meliadine Lake
	m ³	m ³	m ³		m ³
May-20	0	0	0	0	0
Jun-20	330000	0	0	0	330000
Jul-20	413012	0	0	12000	401012
Aug-20	51331	0	0	24800	26531
Sep-20	78361	0	0	24000	54361
Oct-20	0	0	0	0	0
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	199726	0	0	0	199726
Jul-21	302927	0	0	12000	290927
Aug-21	50228	0	0	24800	25428
Sep-21	81626	0	0	24000	57626
Oct-21	0	0	0	0	0
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	201115	0	0	90000	111115
Jul-22	275162	0	0	186000	89162
Aug-22	45487	0	0	45487	0
Sep-22	76444	0	0	76444	0
Oct-22	0	0	0	0	0
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	191532	0	0	90000	101532
Jul-23	281612	0	0	186000	95612
Aug-23	47622	0	0	38461	9161
Sep-23	78770	0	0	27905	50865
Oct-23	0	0	0	0	0
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0

Water Balance for EWTP

Date	Inflow			Outflow	
	Water from CP1 to EWTP	Water from CP5 to EWTP	RO Preemate To EWTP	Water from EWTP to SP3	Discharge to Meliadine Lake
	m ³	m ³	m ³		m ³
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	195151	0	0	90000	105151
Jul-24	316826	0	0	174490	142336
Aug-24	53041	0	0	29677	23364
Sep-24	88116	0	0	28245	59871
Oct-24	0	0	0	0	0
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0
Jun-25	213039	0	0	90000	123039
Jul-25	317767	0	0	186000	131767
Aug-25	54251	0	0	39160	15091
Sep-25	89354	0	0	30862	58492
Oct-25	0	0	0	0	0
Nov-25	0	0	0	0	0
Dec-25	0	0	0	0	0
Jan-26	0	0	0	0	0
Feb-26	0	0	0	0	0
Mar-26	0	0	0	0	0
Apr-26	0	0	0	0	0
May-26	0	0	0	0	0
Jun-26	215346	0	0	90000	125346
Jul-26	326998	0	0	186000	140998
Aug-26	56087	0	0	53174	2913
Sep-26	91190	0	0	31586	59604
Oct-26	0	0	0	0	0
Nov-26	0	0	0	0	0
Dec-26	0	0	0	0	0
Jan-27	0	0	0	0	0
Feb-27	0	0	0	0	0
Mar-27	0	0	0	0	0
Apr-27	0	0	0	0	0
May-27	0	0	0	0	0
Jun-27	219018	0	0	90000	129018
Jul-27	317767	0	0	186000	131767
Aug-27	48201	0	0	41804	6398

Water Balance for EWTP

Date	Inflow			Outflow	
	Water from CP1 to EWTP	Water from CP5 to EWTP	RO Premeate To EWTP	Water from EWTP to SP3	Discharge to Meliadine Lake
	m ³	m ³	m ³		m ³
Sep-27	81999	0	0	29927	52072
Oct-27	0	0	0	0	0
Nov-27	0	0	0	0	0
Dec-27	0	0	0	0	0
Jan-28	0	0	0	0	0
Feb-28	0	0	0	0	0
Mar-28	0	0	0	0	0
Apr-28	0	0	0	0	0
May-28	0	0	0	0	0
Jun-28	206520	0	0	206520	0
Jul-28	317767	0	0	317767	0
Aug-28	48201	0	0	48201	0
Sep-28	81999	0	0	81999	0
Oct-28	0	0	0	0	0
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

APPENDIX C

**Average Monthly Concentrations,
Average Year (Base Case)
Scenario**

Appendix C
Average Year Scenario
CP2 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
Jun 2024	63	0.014	2.1	0.037	0.011	0.0012	0.00028	0.001	0.0037
Jul 2024	145	0.049	12	0.2	0.059	0.003	0.00046	0.0022	0.0082
Aug 2024	112	0.036	7.9	0.14	0.041	0.0023	0.00038	0.0017	0.0064
Sep 2024	113	0.036	8.2	0.14	0.042	0.0023	0.00038	0.0017	0.0065
Oct 2024	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Nov 2024	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Dec 2024	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Jan 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Feb 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Mar 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Apr 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
May 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Jun 2025	84	0.018	3.3	0.059	0.018	0.0014	0.00031	0.0012	0.0043
Jul 2025	97	0.026	5.3	0.091	0.028	0.0018	0.00034	0.0014	0.0051
Aug 2025	101	0.029	6.1	0.11	0.032	0.0019	0.00035	0.0015	0.0054
Sep 2025	105	0.031	6.9	0.12	0.036	0.0021	0.00036	0.0016	0.0057
Oct 2025	86	0.023	4.7	0.082	0.025	0.0017	0.00033	0.0013	0.0048
Nov 2025	86	0.023	4.7	0.082	0.025	0.0017	0.00033	0.0013	0.0048
Dec 2025	86	0.023	4.7	0.082	0.025	0.0017	0.00033	0.0013	0.0048
Jan 2026	86	0.023	4.7	0.082	0.025	0.0017	0.00033	0.0013	0.0048
Feb 2026	86	0.023	4.7	0.082	0.025	0.0017	0.00033	0.0013	0.0048
Mar 2026	86	0.023	4.7	0.082	0.025	0.0017	0.00033	0.0013	0.0048
Apr 2026	86	0.023	4.7	0.082	0.025	0.0017	0.00033	0.0013	0.0048
May 2026	86	0.023	4.7	0.082	0.025	0.0017	0.00033	0.0013	0.0048
Jun 2026	81	0.017	3.0	0.054	0.016	0.0014	0.0003	0.0011	0.0041
Jul 2026	96	0.025	5.0	0.087	0.027	0.0017	0.00034	0.0014	0.0049
Aug 2026	100	0.028	5.9	0.1	0.031	0.0019	0.00035	0.0015	0.0053
Sep 2026	104	0.031	6.8	0.12	0.035	0.002	0.00036	0.0016	0.0056
Oct 2026	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Nov 2026	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Dec 2026	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Jan 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Feb 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Mar 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Apr 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
May 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Jun 2027	81	0.017	3.0	0.053	0.016	0.0014	0.0003	0.0011	0.004
Jul 2027	95	0.024	5.0	0.087	0.026	0.0017	0.00034	0.0014	0.0049
Aug 2027	100	0.028	5.9	0.1	0.031	0.0019	0.00035	0.0015	0.0053
Sep 2027	104	0.031	6.7	0.12	0.035	0.002	0.00036	0.0016	0.0056
Oct 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Nov 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Dec 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Jan 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Feb 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Mar 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Apr 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
May 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Jun 2028	81	0.017	3.0	0.053	0.016	0.0014	0.0003	0.0011	0.004
Jul 2028	95	0.024	5.0	0.087	0.026	0.0017	0.00034	0.0014	0.0049
Aug 2028	100	0.028	5.9	0.1	0.031	0.0019	0.00035	0.0015	0.0053
Sep 2028	104	0.031	6.7	0.12	0.035	0.002	0.00036	0.0016	0.0056
Oct 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Nov 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Dec 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
CP3 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	854	0.18	4.6	0.016	0.064	0.0055	0.0011	0.022	0.027
Jun 2020	418	0.088	3.2	0.04	0.098	0.003	0.00061	0.01	0.014
Jul 2020	359	0.076	4.2	0.082	0.19	0.0029	0.00059	0.0079	0.012
Aug 2020	302	0.064	4.7	0.11	0.24	0.0027	0.00055	0.006	0.011
Sep 2020	278	0.059	5.4	0.14	0.3	0.0028	0.00056	0.005	0.01
Oct 2020	256	0.055	5.9	0.15	0.34	0.0028	0.00056	0.0041	0.0096
Nov 2020	256	0.055	5.9	0.15	0.34	0.0028	0.00056	0.0041	0.0096
Dec 2020	256	0.055	5.9	0.15	0.34	0.0028	0.00056	0.0041	0.0096
Jan 2021	256	0.055	5.9	0.15	0.34	0.0028	0.00056	0.0041	0.0096
Feb 2021	256	0.055	5.9	0.15	0.34	0.0028	0.00056	0.0041	0.0096
Mar 2021	256	0.055	5.9	0.15	0.34	0.0028	0.00056	0.0041	0.0096
Apr 2021	256	0.055	5.9	0.15	0.34	0.0028	0.00056	0.0041	0.0096
May 2021	256	0.055	5.9	0.15	0.34	0.0028	0.00056	0.0041	0.0096
Jun 2021	148	0.033	3.7	0.1	0.22	0.0018	0.00037	0.0022	0.0066
Jul 2021	153	0.037	4.5	0.13	0.27	0.002	0.00042	0.0021	0.0081
Aug 2021	152	0.039	4.8	0.14	0.3	0.0021	0.00044	0.0019	0.0088
Sep 2021	160	0.042	5.4	0.16	0.34	0.0023	0.00049	0.0019	0.0099
Oct 2021	164	0.044	5.8	0.17	0.36	0.0024	0.00051	0.0018	0.011
Nov 2021	164	0.044	5.8	0.17	0.36	0.0024	0.00051	0.0018	0.011
Dec 2021	164	0.044	5.8	0.17	0.36	0.0024	0.00051	0.0018	0.011
Jan 2022	164	0.044	5.8	0.17	0.36	0.0024	0.00051	0.0018	0.011
Feb 2022	164	0.044	5.8	0.17	0.36	0.0024	0.00051	0.0018	0.011
Mar 2022	164	0.044	5.8	0.17	0.36	0.0024	0.00051	0.0018	0.011
Apr 2022	164	0.044	5.8	0.17	0.36	0.0024	0.00051	0.0018	0.011
May 2022	164	0.044	5.8	0.17	0.36	0.0024	0.00051	0.0018	0.011
Jun 2022	105	0.028	3.7	0.1	0.22	0.0016	0.00034	0.0012	0.0067
Jul 2022	120	0.032	4.5	0.12	0.26	0.0018	0.00037	0.0013	0.0076
Aug 2022	126	0.034	4.9	0.13	0.27	0.0019	0.00039	0.0013	0.0079
Sep 2022	138	0.037	5.5	0.15	0.3	0.0021	0.00042	0.0014	0.0086
Oct 2022	146	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0015	0.0091
Nov 2022	146	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0015	0.0091
Dec 2022	146	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0015	0.0091
Jan 2023	146	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0015	0.0091
Feb 2023	146	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0015	0.0091
Mar 2023	146	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0015	0.0091
Apr 2023	146	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0015	0.0091
May 2023	146	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0015	0.0091
Jun 2023	97	0.026	3.7	0.1	0.21	0.0015	0.00032	0.001	0.0064
Jul 2023	114	0.032	4.5	0.12	0.26	0.0018	0.00038	0.0012	0.0079
Aug 2023	123	0.035	4.8	0.13	0.29	0.0019	0.00041	0.0012	0.0088
Sep 2023	136	0.039	5.4	0.15	0.32	0.0021	0.00045	0.0014	0.0099
Oct 2023	145	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Nov 2023	145	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Dec 2023	145	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Jan 2024	145	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Feb 2024	145	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Mar 2024	145	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Apr 2024	145	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
May 2024	145	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Jun 2024	99	0.025	3.7	0.1	0.21	0.0015	0.00032	0.00099	0.0059
Jul 2024	121	0.027	4.6	0.12	0.26	0.0017	0.00035	0.0011	0.0055
Aug 2024	131	0.028	5.0	0.13	0.28	0.0018	0.00036	0.0012	0.0051
Sep 2024	147	0.03	5.7	0.15	0.31	0.002	0.00039	0.0013	0.005
Oct 2024	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Nov 2024	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Dec 2024	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Jan 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Feb 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Mar 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Apr 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
May 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Jun 2025	105	0.02	3.9	0.1	0.2	0.0014	0.00028	0.00095	0.0033
Jul 2025	124	0.024	4.7	0.12	0.25	0.0017	0.00031	0.0011	0.0035
Aug 2025	133	0.025	5.1	0.13	0.26	0.0018	0.00033	0.0012	0.0036
Sep 2025	148	0.028	5.8	0.15	0.3	0.002	0.00036	0.0013	0.0038
Oct 2025	157	0.03	6.2	0.16	0.31	0.0021	0.00038	0.0013	0.004
Nov 2025	157	0.03	6.2	0.16	0.31	0.0021	0.00038	0.0013	0.004
Dec 2025	157	0.03	6.2	0.16	0.31	0.0021	0.00038	0.0013	0.004
Jan 2026	157	0.03	6.2	0.16	0.31	0.0021	0.00038	0.0013	0.004
Feb 2026	157	0.03	6.2	0.16	0.31	0.0021	0.00038	0.0013	0.004
Mar 2026	157	0.03	6.2	0.16	0.31	0.0021	0.00038	0.0013	0.004
Apr 2026	157	0.03	6.2	0.16	0.31	0.0021	0.00038	0.0013	0.004
May 2026	157	0.03	6.2	0.16	0.31	0.0021	0.00038	0.0013	0.004
Jun 2026	106	0.019	3.9	0.1	0.2	0.0014	0.00027	0.00094	0.0028
Jul 2026	126	0.023	4.8	0.12	0.25	0.0017	0.00032	0.0011	0.0032
Aug 2026	136	0.025	5.1	0.13	0.28	0.0018	0.00034	0.0012	0.0034
Sep 2026	152	0.028	5.8	0.15	0.31	0.002	0.00038	0.0013	0.0037
Oct 2026	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0039
Nov 2026	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0039
Dec 2026	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0039
Jan 2027	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0039
Feb 2027	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0039
Mar 2027	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0039
Apr 2027	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0039
May 2027	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0039
Jun 2027	108	0.019	3.9	0.1	0.21	0.0014	0.00028	0.00094	0.0028
Jul 2027	128	0.023	4.8	0.13	0.26	0.0017	0.00032	0.0011	0.0031
Aug 2027	137	0.025	5.1	0.14	0.28	0.0018	0.00034	0.0012	0.0033
Sep 2027	153	0.028	5.8	0.15	0.32	0.002	0.00038	0.0013	0.0036
Oct 2027	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Nov 2027	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Dec 2027	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Jan 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Feb 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Mar 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Apr 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
May 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Jun 2028	108	0.019	3.9	0.1	0.21	0.0014	0.00028	0.00094	0.0028
Jul 2028	128	0.023	4.8	0.13	0.26	0.0017	0.00032	0.0011	0.0031
Aug 2028	137	0.025	5.1	0.14	0.28	0.0018	0.00034	0.0012	0.0033
Sep 2028	153	0.028	5.8	0.15	0.32	0.002	0.00038	0.0013	0.0036
Oct 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Nov 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Dec 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
CP4 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	977	0.065	0.91	0.0064	0.0056	0.0029	0.00013	0.015	0.0033
Jun 2020	496	0.035	0.9	0.014	0.0047	0.0018	0.00022	0.0072	0.0037
Jul 2020	418	0.034	1.6	0.028	0.0071	0.0019	0.00026	0.0061	0.0046
Aug 2020	331	0.032	2.1	0.037	0.0084	0.0018	0.00029	0.0048	0.0052
Sep 2020	266	0.031	2.4	0.045	0.0096	0.0018	0.0003	0.004	0.0056
Oct 2020	210	0.024	1.8	0.034	0.0073	0.0015	0.00029	0.0032	0.0049
Nov 2020	210	0.024	1.8	0.034	0.0073	0.0015	0.00029	0.0032	0.0049
Dec 2020	210	0.024	1.8	0.034	0.0073	0.0015	0.00029	0.0032	0.0049
Jan 2021	210	0.024	1.8	0.034	0.0073	0.0015	0.00029	0.0032	0.0049
Feb 2021	210	0.024	1.8	0.034	0.0073	0.0015	0.00029	0.0032	0.0049
Mar 2021	210	0.024	1.8	0.034	0.0073	0.0015	0.00029	0.0032	0.0049
Apr 2021	210	0.024	1.8	0.034	0.0073	0.0015	0.00029	0.0032	0.0049
May 2021	210	0.024	1.8	0.034	0.0073	0.0015	0.00029	0.0032	0.0049
Jun 2021	147	0.022	1.8	0.035	0.0051	0.0014	0.00031	0.0021	0.0061
Jul 2021	141	0.032	3.2	0.059	0.0062	0.0017	0.00037	0.0021	0.0094
Aug 2021	129	0.038	4.0	0.074	0.0067	0.0019	0.0004	0.0021	0.012
Sep 2021	117	0.043	4.7	0.087	0.0072	0.002	0.00043	0.0021	0.013
Oct 2021	102	0.035	3.7	0.068	0.0058	0.0018	0.00039	0.0018	0.011
Nov 2021	102	0.035	3.7	0.068	0.0058	0.0018	0.00039	0.0018	0.011
Dec 2021	102	0.035	3.7	0.068	0.0058	0.0018	0.00039	0.0018	0.011
Jan 2022	102	0.035	3.7	0.068	0.0058	0.0018	0.00039	0.0018	0.011
Feb 2022	102	0.035	3.7	0.068	0.0058	0.0018	0.00039	0.0018	0.011
Mar 2022	102	0.035	3.7	0.068	0.0058	0.0018	0.00039	0.0018	0.011
Apr 2022	102	0.035	3.7	0.068	0.0058	0.0018	0.00039	0.0018	0.011
May 2022	102	0.035	3.7	0.068	0.0058	0.0018	0.00039	0.0018	0.011
Jun 2022	110	0.03	3.7	0.068	0.01	0.0016	0.00037	0.0015	0.0089
Jul 2022	124	0.04	5.9	0.11	0.02	0.0021	0.00042	0.0018	0.011
Aug 2022	131	0.046	7.4	0.13	0.026	0.0024	0.00045	0.0019	0.012
Sep 2022	133	0.052	8.8	0.16	0.032	0.0026	0.00047	0.0021	0.013
Oct 2022	119	0.044	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Nov 2022	119	0.044	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Dec 2022	119	0.044	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Jan 2023	119	0.044	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Feb 2023	119	0.044	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Mar 2023	119	0.044	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Apr 2023	119	0.044	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
May 2023	119	0.044	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Jun 2023	145	0.033	5.6	0.1	0.023	0.0019	0.00039	0.0015	0.008
Jul 2023	156	0.04	7.7	0.14	0.035	0.0023	0.00042	0.0018	0.0086
Aug 2023	159	0.044	9.0	0.16	0.042	0.0025	0.00044	0.0019	0.0087
Sep 2023	158	0.048	10	0.18	0.049	0.0027	0.00045	0.002	0.0088
Oct 2023	139	0.041	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Nov 2023	139	0.041	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Dec 2023	139	0.041	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Jan 2024	139	0.041	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Feb 2024	139	0.041	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Mar 2024	139	0.041	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Apr 2024	139	0.041	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
May 2024	139	0.041	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Jun 2024	169	0.031	6.3	0.11	0.031	0.0019	0.00038	0.0015	0.0062
Jul 2024	175	0.039	8.3	0.15	0.041	0.0023	0.00041	0.0017	0.007
Aug 2024	173	0.043	9.5	0.17	0.047	0.0025	0.00043	0.0019	0.0073
Sep 2024	168	0.047	11	0.19	0.053	0.0027	0.00045	0.002	0.0077
Oct 2024	147	0.04	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Nov 2024	147	0.04	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Dec 2024	147	0.04	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Jan 2025	147	0.04	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Feb 2025	147	0.04	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Mar 2025	147	0.04	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Apr 2025	147	0.04	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
May 2025	147	0.04	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Jun 2025	172	0.031	6.4	0.12	0.032	0.002	0.00037	0.0015	0.0057
Jul 2025	178	0.039	8.4	0.15	0.042	0.0023	0.00041	0.0017	0.0065
Aug 2025	174	0.043	9.6	0.17	0.048	0.0026	0.00043	0.0019	0.007
Sep 2025	169	0.047	11	0.19	0.054	0.0027	0.00044	0.002	0.0074
Oct 2025	147	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0066
Nov 2025	147	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0066
Dec 2025	147	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0066
Jan 2026	147	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0066
Feb 2026	147	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0066
Mar 2026	147	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0066
Apr 2026	147	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0066
May 2026	147	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0066
Jun 2026	173	0.031	6.5	0.12	0.033	0.002	0.00037	0.0015	0.0055
Jul 2026	177	0.039	8.5	0.15	0.043	0.0023	0.00041	0.0017	0.0064
Aug 2026	173	0.043	9.6	0.17	0.049	0.0026	0.00043	0.0019	0.0069
Sep 2026	168	0.047	11	0.19	0.054	0.0028	0.00044	0.002	0.0073
Oct 2026	146	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Nov 2026	146	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Dec 2026	146	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Jan 2027	146	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Feb 2027	146	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Mar 2027	146	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Apr 2027	146	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
May 2027	146	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Jun 2027	172	0.031	6.5	0.12	0.033	0.002	0.00037	0.0015	0.0055
Jul 2027	176	0.039	8.5	0.15	0.043	0.0023	0.00041	0.0017	0.0064
Aug 2027	172	0.043	9.6	0.17	0.049	0.0026	0.00043	0.0019	0.0068
Sep 2027	167	0.047	11	0.19	0.054	0.0028	0.00044	0.002	0.0073
Oct 2027	145	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Nov 2027	145	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Dec 2027	145	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Jan 2028	145	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Feb 2028	145	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Mar 2028	145	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Apr 2028	145	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
May 2028	145	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Jun 2028	171	0.031	6.5	0.12	0.033	0.002	0.00037	0.0015	0.0055
Jul 2028	175	0.039	8.5	0.15	0.043	0.0023	0.00041	0.0017	0.0064
Aug 2028	171	0.043	9.6	0.17	0.049	0.0026	0.00043	0.0019	0.0068
Sep 2028	166	0.047	11	0.19	0.054	0.0028	0.00044	0.002	0.0073
Oct 2028	144	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Nov 2028	144	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065
Dec 2028	144	0.04	8.8	0.16	0.044	0.0024	0.00041	0.0018	0.0065

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
CP5 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	7153	0.067	18	0.025	0.0043	0.0067	0.0017	0.038	0.042
Jun 2020	2357	0.028	7.5	0.026	0.0029	0.0027	0.00087	0.012	0.017
Jul 2020	2289	0.031	9.8	0.06	0.0052	0.0026	0.0011	0.011	0.019
Aug 2020	1524	0.025	7.1	0.069	0.0058	0.0021	0.00098	0.0068	0.013
Sep 2020	943	0.02	5.2	0.07	0.0058	0.0017	0.00085	0.0044	0.01
Oct 2020	558	0.015	3.6	0.062	0.0045	0.0013	0.00073	0.0027	0.0074
Nov 2020	558	0.015	3.6	0.062	0.0045	0.0013	0.00073	0.0027	0.0074
Dec 2020	558	0.015	3.6	0.062	0.0045	0.0013	0.00073	0.0027	0.0074
Jan 2021	558	0.015	3.6	0.062	0.0045	0.0013	0.00073	0.0027	0.0074
Feb 2021	558	0.015	3.6	0.062	0.0045	0.0013	0.00073	0.0027	0.0074
Mar 2021	558	0.015	3.6	0.062	0.0045	0.0013	0.00073	0.0027	0.0074
Apr 2021	558	0.015	3.6	0.062	0.0045	0.0013	0.00073	0.0027	0.0074
May 2021	558	0.015	3.6	0.062	0.0045	0.0013	0.00073	0.0027	0.0074
Jun 2021	310	0.012	5.0	0.083	0.0052	0.00099	0.00084	0.0016	0.0062
Jul 2021	650	0.019	6.7	0.13	0.011	0.0013	0.0011	0.0019	0.0086
Aug 2021	683	0.02	6.7	0.13	0.012	0.0013	0.0011	0.0018	0.0087
Sep 2021	449	0.021	6.4	0.13	0.013	0.0013	0.001	0.0017	0.0086
Oct 2021	313	0.018	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Nov 2021	313	0.018	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Dec 2021	313	0.018	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Jan 2022	313	0.018	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Feb 2022	313	0.018	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Mar 2022	313	0.018	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Apr 2022	313	0.018	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
May 2022	313	0.018	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Jun 2022	257	0.013	3.2	0.1	0.0069	0.0011	0.0010	0.0016	0.0069
Jul 2022	495	0.019	5.4	0.14	0.013	0.0014	0.0012	0.0019	0.0087
Aug 2022	518	0.02	5.9	0.14	0.013	0.0014	0.0011	0.0019	0.0085
Sep 2022	361	0.021	5.7	0.13	0.014	0.0014	0.001	0.0018	0.0083
Oct 2022	256	0.017	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Nov 2022	256	0.017	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Dec 2022	256	0.017	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Jan 2023	256	0.017	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Feb 2023	256	0.017	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Mar 2023	256	0.017	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Apr 2023	256	0.017	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
May 2023	256	0.017	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Jun 2023	193	0.012	3.9	0.097	0.0072	0.001	0.00092	0.0015	0.0063
Jul 2023	356	0.019	6.2	0.13	0.014	0.0013	0.0011	0.0018	0.0079
Aug 2023	366	0.02	6.7	0.13	0.015	0.0013	0.0010	0.0017	0.0077
Sep 2023	254	0.02	6.4	0.13	0.016	0.0014	0.00093	0.0017	0.0075
Oct 2023	183	0.018	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Nov 2023	183	0.018	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Dec 2023	183	0.018	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Jan 2024	183	0.018	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Feb 2024	183	0.018	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Mar 2024	183	0.018	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Apr 2024	183	0.018	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
May 2024	183	0.018	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Jun 2024	183	0.013	2.0	0.11	0.0076	0.0012	0.0011	0.0017	0.0072
Jul 2024	323	0.019	4.4	0.15	0.013	0.0015	0.0013	0.002	0.0088
Aug 2024	331	0.019	5.2	0.15	0.014	0.0014	0.0012	0.0019	0.0084
Sep 2024	243	0.019	4.9	0.14	0.015	0.0014	0.0011	0.0019	0.0081
Oct 2024	177	0.016	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Nov 2024	177	0.016	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Dec 2024	177	0.016	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Jan 2025	177	0.016	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Feb 2025	177	0.016	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Mar 2025	177	0.016	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Apr 2025	177	0.016	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
May 2025	177	0.016	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Jun 2025	164	0.013	1.6	0.12	0.0073	0.0012	0.0012	0.0018	0.0076
Jul 2025	272	0.019	4.4	0.16	0.013	0.0015	0.0013	0.0021	0.0091
Aug 2025	274	0.02	5.4	0.15	0.014	0.0014	0.0012	0.002	0.0087
Sep 2025	200	0.02	5.2	0.15	0.015	0.0014	0.0012	0.0019	0.0083
Oct 2025	146	0.017	4.3	0.12	0.012	0.0012	0.001	0.0017	0.0074
Nov 2025	146	0.017	4.3	0.12	0.012	0.0012	0.001	0.0017	0.0074
Dec 2025	146	0.017	4.3	0.12	0.012	0.0012	0.001	0.0017	0.0074
Jan 2026	146	0.017	4.3	0.12	0.012	0.0012	0.001	0.0017	0.0074
Feb 2026	146	0.017	4.3	0.12	0.012	0.0012	0.001	0.0017	0.0074
Mar 2026	146	0.017	4.3	0.12	0.012	0.0012	0.001	0.0017	0.0074
Apr 2026	146	0.017	4.3	0.12	0.012	0.0012	0.001	0.0017	0.0074
May 2026	146	0.017	4.3	0.12	0.012	0.0012	0.001	0.0017	0.0074
Jun 2026	121	0.013	3.1	0.11	0.0074	0.0011	0.0011	0.0017	0.007
Jul 2026	199	0.019	5.7	0.15	0.014	0.0014	0.0012	0.0019	0.0085
Aug 2026	201	0.02	6.3	0.14	0.015	0.0014	0.0011	0.0018	0.0082
Sep 2026	148	0.021	6.1	0.14	0.016	0.0014	0.001	0.0018	0.008
Oct 2026	110	0.018	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Nov 2026	110	0.018	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Dec 2026	110	0.018	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Jan 2027	110	0.018	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Feb 2027	110	0.018	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Mar 2027	110	0.018	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Apr 2027	110	0.018	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
May 2027	110	0.018	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Jun 2027	112	0.013	1.9	0.12	0.0077	0.0012	0.0012	0.0018	0.0076
Jul 2027	209	0.018	2.4	0.17	0.012	0.0016	0.0017	0.0025	0.01
Aug 2027	231	0.019	2.2	0.18	0.012	0.0016	0.0017	0.0025	0.01
Sep 2027	180	0.018	2.1	0.17	0.012	0.0015	0.0016	0.0024	0.0098
Oct 2027	133	0.014	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Nov 2027	133	0.014	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Dec 2027	133	0.014	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Jan 2028	133	0.014	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Feb 2028	133	0.014	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Mar 2028	133	0.014	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Apr 2028	133	0.014	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
May 2028	133	0.014	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Jun 2028	107	0.012	0.93	0.13	0.0065	0.0012	0.0013	0.002	0.008
Jul 2028	179	0.017	1.7	0.18	0.011	0.0016	0.0017	0.0026	0.01
Aug 2028	191	0.018	1.8	0.18	0.012	0.0016	0.0018	0.0026	0.011
Sep 2028	150	0.018	1.9	0.17	0.012	0.0015	0.0016	0.0024	0.0099
Oct 2028	112	0.014	1.2	0.14	0.008	0.0013	0.0014	0.0021	0.0085
Nov 2028	112	0.014	1.2	0.14	0.008	0.0013	0.0014	0.0021	0.0085
Dec 2028	112	0.014	1.2	0.14	0.008	0.0013	0.0014	0.0021	0.0085

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
CP6 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	977	0.065	0.91	0.0064	0.0056	0.0029	0.00013	0.015	0.0033
Jun 2020	650	0.056	3.6	0.057	0.017	0.0027	0.00021	0.01	0.0052
Jul 2020	653	0.074	7.9	0.13	0.036	0.0035	0.0003	0.01	0.0087
Aug 2020	621	0.086	11	0.19	0.051	0.004	0.00037	0.0099	0.011
Sep 2020	592	0.096	14	0.25	0.065	0.0045	0.00043	0.0094	0.014
Oct 2020	520	0.084	13	0.22	0.056	0.004	0.0004	0.0083	0.012
Nov 2020	520	0.084	13	0.22	0.056	0.004	0.0004	0.0083	0.012
Dec 2020	520	0.084	13	0.22	0.056	0.004	0.0004	0.0083	0.012
Jan 2021	520	0.084	13	0.22	0.056	0.004	0.0004	0.0083	0.012
Feb 2021	520	0.084	13	0.22	0.056	0.004	0.0004	0.0083	0.012
Mar 2021	520	0.084	13	0.22	0.056	0.004	0.0004	0.0083	0.012
Apr 2021	520	0.084	13	0.22	0.056	0.004	0.0004	0.0083	0.012
May 2021	520	0.084	13	0.22	0.056	0.004	0.0004	0.0083	0.012
Jun 2021	367	0.066	11	0.19	0.052	0.0034	0.00037	0.0058	0.0099
Jul 2021	390	0.08	15	0.26	0.073	0.0042	0.00044	0.0061	0.012
Aug 2021	392	0.089	18	0.31	0.089	0.0047	0.00048	0.0061	0.012
Sep 2021	392	0.097	20	0.36	0.1	0.0051	0.00052	0.0061	0.013
Oct 2021	346	0.085	18	0.31	0.089	0.0045	0.00048	0.0054	0.012
Nov 2021	346	0.085	18	0.31	0.089	0.0045	0.00048	0.0054	0.012
Dec 2021	346	0.085	18	0.31	0.089	0.0045	0.00048	0.0054	0.012
Jan 2022	346	0.085	18	0.31	0.089	0.0045	0.00048	0.0054	0.012
Feb 2022	346	0.085	18	0.31	0.089	0.0045	0.00048	0.0054	0.012
Mar 2022	346	0.085	18	0.31	0.089	0.0045	0.00048	0.0054	0.012
Apr 2022	346	0.085	18	0.31	0.089	0.0045	0.00048	0.0054	0.012
May 2022	346	0.085	18	0.31	0.089	0.0045	0.00048	0.0054	0.012
Jun 2022	240	0.075	14	0.24	0.061	0.0037	0.00046	0.004	0.014
Jul 2022	244	0.1	17	0.3	0.064	0.0045	0.00058	0.0044	0.022
Aug 2022	235	0.12	19	0.34	0.063	0.005	0.00066	0.0046	0.029
Sep 2022	227	0.13	21	0.37	0.063	0.0054	0.00073	0.0047	0.034
Oct 2022	203	0.12	18	0.32	0.055	0.0048	0.00067	0.0042	0.03
Nov 2022	203	0.12	18	0.32	0.055	0.0048	0.00067	0.0042	0.03
Dec 2022	203	0.12	18	0.32	0.055	0.0048	0.00067	0.0042	0.03
Jan 2023	203	0.12	18	0.32	0.055	0.0048	0.00067	0.0042	0.03
Feb 2023	203	0.12	18	0.32	0.055	0.0048	0.00067	0.0042	0.03
Mar 2023	203	0.12	18	0.32	0.055	0.0048	0.00067	0.0042	0.03
Apr 2023	203	0.12	18	0.32	0.055	0.0048	0.00067	0.0042	0.03
May 2023	203	0.12	18	0.32	0.055	0.0048	0.00067	0.0042	0.03
Jun 2023	145	0.097	14	0.25	0.036	0.0039	0.00059	0.0033	0.027
Jul 2023	148	0.13	18	0.3	0.036	0.0047	0.00072	0.0038	0.036
Aug 2023	144	0.14	19	0.34	0.034	0.0052	0.0008	0.004	0.043
Sep 2023	139	0.16	21	0.37	0.032	0.0056	0.00087	0.0043	0.048
Oct 2023	126	0.14	18	0.32	0.028	0.005	0.00079	0.0038	0.043
Nov 2023	126	0.14	18	0.32	0.028	0.005	0.00079	0.0038	0.043
Dec 2023	126	0.14	18	0.32	0.028	0.005	0.00079	0.0038	0.043
Jan 2024	126	0.14	18	0.32	0.028	0.005	0.00079	0.0038	0.043
Feb 2024	126	0.14	18	0.32	0.028	0.005	0.00079	0.0038	0.043
Mar 2024	126	0.14	18	0.32	0.028	0.005	0.00079	0.0038	0.043
Apr 2024	126	0.14	18	0.32	0.028	0.005	0.00079	0.0038	0.043
May 2024	126	0.14	18	0.32	0.028	0.005	0.00079	0.0038	0.043
Jun 2024	120	0.1	15	0.25	0.033	0.0039	0.00064	0.003	0.029
Jul 2024	157	0.11	18	0.32	0.054	0.0045	0.0007	0.0034	0.03
Aug 2024	184	0.12	21	0.36	0.07	0.0049	0.00073	0.0036	0.029
Sep 2024	203	0.12	23	0.39	0.084	0.0052	0.00074	0.0038	0.028
Oct 2024	183	0.11	20	0.34	0.073	0.0046	0.00068	0.0034	0.024
Nov 2024	183	0.11	20	0.34	0.073	0.0046	0.00068	0.0034	0.024
Dec 2024	183	0.11	20	0.34	0.073	0.0046	0.00068	0.0034	0.024
Jan 2025	183	0.11	20	0.34	0.073	0.0046	0.00068	0.0034	0.024
Feb 2025	183	0.11	20	0.34	0.073	0.0046	0.00068	0.0034	0.024
Mar 2025	183	0.11	20	0.34	0.073	0.0046	0.00068	0.0034	0.024
Apr 2025	183	0.11	20	0.34	0.073	0.0046	0.00068	0.0034	0.024
May 2025	183	0.11	20	0.34	0.073	0.0046	0.00068	0.0034	0.024
Jun 2025	178	0.079	15	0.27	0.062	0.0036	0.00057	0.0027	0.017
Jul 2025	210	0.091	19	0.33	0.081	0.0043	0.00064	0.0031	0.019
Aug 2025	228	0.098	21	0.37	0.095	0.0047	0.00067	0.0034	0.019
Sep 2025	241	0.1	23	0.4	0.11	0.005	0.00069	0.0036	0.019
Oct 2025	216	0.091	20	0.35	0.093	0.0044	0.00064	0.0032	0.016
Nov 2025	216	0.091	20	0.35	0.093	0.0044	0.00064	0.0032	0.016
Dec 2025	216	0.091	20	0.35	0.093	0.0044	0.00064	0.0032	0.016
Jan 2026	216	0.091	20	0.35	0.093	0.0044	0.00064	0.0032	0.016
Feb 2026	216	0.091	20	0.35	0.093	0.0044	0.00064	0.0032	0.016
Mar 2026	216	0.091	20	0.35	0.093	0.0044	0.00064	0.0032	0.016
Apr 2026	216	0.091	20	0.35	0.093	0.0044	0.00064	0.0032	0.016
May 2026	216	0.091	20	0.35	0.093	0.0044	0.00064	0.0032	0.016
Jun 2026	198	0.07	16	0.27	0.074	0.0036	0.00054	0.0026	0.012
Jul 2026	227	0.083	19	0.34	0.093	0.0042	0.00061	0.003	0.014
Aug 2026	243	0.09	22	0.37	0.1	0.0046	0.00064	0.0033	0.014
Sep 2026	254	0.097	24	0.41	0.12	0.0049	0.00067	0.0035	0.015
Oct 2026	227	0.085	21	0.36	0.1	0.0044	0.00062	0.0031	0.013
Nov 2026	227	0.085	21	0.36	0.1	0.0044	0.00062	0.0031	0.013
Dec 2026	227	0.085	21	0.36	0.1	0.0044	0.00062	0.0031	0.013
Jan 2027	227	0.085	21	0.36	0.1	0.0044	0.00062	0.0031	0.013
Feb 2027	227	0.085	21	0.36	0.1	0.0044	0.00062	0.0031	0.013
Mar 2027	227	0.085	21	0.36	0.1	0.0044	0.00062	0.0031	0.013
Apr 2027	227	0.085	21	0.36	0.1	0.0044	0.00062	0.0031	0.013
May 2027	227	0.085	21	0.36	0.1	0.0044	0.00062	0.0031	0.013
Jun 2027	204	0.066	16	0.28	0.079	0.0035	0.00053	0.0025	0.01
Jul 2027	233	0.079	20	0.34	0.097	0.0042	0.0006	0.003	0.012
Aug 2027	248	0.087	22	0.38	0.11	0.0046	0.00063	0.0032	0.013
Sep 2027	258	0.094	24	0.41	0.12	0.0049	0.00066	0.0034	0.013
Oct 2027	230	0.082	21	0.36	0.1	0.0043	0.00061	0.0031	0.012
Nov 2027	230	0.082	21	0.36	0.1	0.0043	0.00061	0.0031	0.012
Dec 2027	230	0.082	21	0.36	0.1	0.0043	0.00061	0.0031	0.012
Jan 2028	230	0.082	21	0.36	0.1	0.0043	0.00061	0.0031	0.012
Feb 2028	230	0.082	21	0.36	0.1	0.0043	0.00061	0.0031	0.012
Mar 2028	230	0.082	21	0.36	0.1	0.0043	0.00061	0.0031	0.012
Apr 2028	230	0.082	21	0.36	0.1	0.0043	0.00061	0.0031	0.012
May 2028	230	0.082	21	0.36	0.1	0.0043	0.00061	0.0031	0.012
Jun 2028	206	0.064	16	0.28	0.081	0.0035	0.00052	0.0025	0.0095
Jul 2028	234	0.078	20	0.34	0.099	0.0042	0.00059	0.0029	0.011
Aug 2028	248	0.086	22	0.38	0.11	0.0045	0.00063	0.0032	0.012
Sep 2028	258	0.093	24	0.41	0.12	0.0049	0.00065	0.0034	0.013
Oct 2028	230	0.081	21	0.36	0.11	0.0043	0.00061	0.0031	0.011
Nov 2028	230	0.081	21	0.36	0.11	0.0043	0.00061	0.0031	0.011
Dec 2028	230	0.081	21	0.36	0.11	0.0043	0.00061	0.0031	0.011

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
P-Area Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	10950	0.073	36	0.03	0.0059	0.0047	0.002	0.028	0.05
Jun 2020	3060	0.042	19	0.054	0.0045	0.0028	0.0015	0.015	0.029
Jul 2020	3933	0.047	19	0.13	0.0069	0.0033	0.0022	0.016	0.033
Aug 2020	3703	0.024	1.4	0.38	0.012	0.0022	0.0038	0.0049	0.02
Sep 2020	844	0.016	0.91	0.24	0.0078	0.0014	0.0024	0.0031	0.013
Oct 2020	741	0.013	0.8	0.21	0.0068	0.0012	0.0021	0.0027	0.011

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
Tiri-1 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	-	-	-	-	-	-	-	-	-
Jun 2020	-	-	-	-	-	-	-	-	-
Jul 2020	-	-	-	-	-	-	-	-	-
Aug 2020	-	-	-	-	-	-	-	-	-
Sep 2020	-	-	-	-	-	-	-	-	-
Oct 2020	-	-	-	-	-	-	-	-	-
Nov 2020	-	-	-	-	-	-	-	-	-
Dec 2020	-	-	-	-	-	-	-	-	-
Jan 2021	-	-	-	-	-	-	-	-	-
Feb 2021	-	-	-	-	-	-	-	-	-
Mar 2021	-	-	-	-	-	-	-	-	-
Apr 2021	-	-	-	-	-	-	-	-	-
May 2021	-	-	-	-	-	-	-	-	-
Jun 2021	21	0.0083	13	0.028	0.0067	0.00047	0.000082	0.00035	0.0019
Jul 2021	42	0.024	13	0.09	0.021	0.0011	0.00013	0.0007	0.0047
Aug 2021	39	0.021	13	0.08	0.019	0.001	0.00012	0.00066	0.0043
Sep 2021	50	0.028	13	0.1	0.025	0.0013	0.00015	0.00083	0.0055
Oct 2021	50	0.027	13	0.1	0.024	0.0013	0.00015	0.00083	0.0054
Nov 2021	-	-	-	-	-	-	-	-	-
Dec 2021	-	-	-	-	-	-	-	-	-
Jan 2022	-	-	-	-	-	-	-	-	-
Feb 2022	-	-	-	-	-	-	-	-	-
Mar 2022	-	-	-	-	-	-	-	-	-
Apr 2022	-	-	-	-	-	-	-	-	-
May 2022	-	-	-	-	-	-	-	-	-
Jun 2022	21	0.0083	13	0.028	0.0067	0.00047	0.000082	0.00035	0.0019
Jul 2022	42	0.024	13	0.09	0.021	0.0011	0.00013	0.0007	0.0047
Aug 2022	39	0.021	13	0.08	0.019	0.001	0.00012	0.00066	0.0043
Sep 2022	50	0.028	13	0.1	0.025	0.0013	0.00015	0.00083	0.0055
Oct 2022	50	0.027	13	0.1	0.024	0.0013	0.00015	0.00083	0.0054
Nov 2022	-	-	-	-	-	-	-	-	-
Dec 2022	-	-	-	-	-	-	-	-	-
Jan 2023	-	-	-	-	-	-	-	-	-
Feb 2023	-	-	-	-	-	-	-	-	-
Mar 2023	-	-	-	-	-	-	-	-	-
Apr 2023	-	-	-	-	-	-	-	-	-
May 2023	-	-	-	-	-	-	-	-	-
Jun 2023	19	0.0084	13	0.029	0.0069	0.00045	0.000073	0.00032	0.0019
Jul 2023	42	0.024	13	0.092	0.022	0.0011	0.00012	0.00069	0.0047
Aug 2023	39	0.022	13	0.083	0.02	0.001	0.00012	0.00065	0.0043
Sep 2023	50	0.029	13	0.11	0.026	0.0013	0.00015	0.00083	0.0056
Oct 2023	50	0.028	13	0.11	0.025	0.0013	0.00015	0.00083	0.0055
Nov 2023	-	-	-	-	-	-	-	-	-
Dec 2023	-	-	-	-	-	-	-	-	-
Jan 2024	-	-	-	-	-	-	-	-	-
Feb 2024	-	-	-	-	-	-	-	-	-
Mar 2024	-	-	-	-	-	-	-	-	-
Apr 2024	-	-	-	-	-	-	-	-	-
May 2024	-	-	-	-	-	-	-	-	-
Jun 2024	19	0.0084	13	0.029	0.0069	0.00045	0.000073	0.00032	0.0019
Jul 2024	42	0.024	13	0.092	0.022	0.0011	0.00012	0.00069	0.0047
Aug 2024	39	0.022	13	0.083	0.02	0.001	0.00012	0.00065	0.0043
Sep 2024	50	0.029	13	0.11	0.026	0.0013	0.00015	0.00083	0.0056
Oct 2024	50	0.028	13	0.11	0.025	0.0013	0.00015	0.00083	0.0055
Nov 2024	-	-	-	-	-	-	-	-	-
Dec 2024	-	-	-	-	-	-	-	-	-
Jan 2025	-	-	-	-	-	-	-	-	-
Feb 2025	-	-	-	-	-	-	-	-	-
Mar 2025	-	-	-	-	-	-	-	-	-
Apr 2025	-	-	-	-	-	-	-	-	-
May 2025	-	-	-	-	-	-	-	-	-
Jun 2025	19	0.0084	13	0.029	0.0069	0.00045	0.000073	0.00032	0.0019
Jul 2025	42	0.024	13	0.092	0.022	0.0011	0.00012	0.00069	0.0047
Aug 2025	39	0.022	13	0.083	0.02	0.001	0.00012	0.00065	0.0043
Sep 2025	50	0.029	13	0.11	0.026	0.0013	0.00015	0.00083	0.0056
Oct 2025	50	0.028	13	0.11	0.025	0.0013	0.00015	0.00083	0.0055
Nov 2025	-	-	-	-	-	-	-	-	-
Dec 2025	-	-	-	-	-	-	-	-	-
Jan 2026	-	-	-	-	-	-	-	-	-
Feb 2026	-	-	-	-	-	-	-	-	-
Mar 2026	-	-	-	-	-	-	-	-	-
Apr 2026	-	-	-	-	-	-	-	-	-
May 2026	-	-	-	-	-	-	-	-	-
Jun 2026	19	0.0084	13	0.029	0.0069	0.00045	0.000073	0.00032	0.0019
Jul 2026	42	0.024	13	0.092	0.022	0.0011	0.00012	0.00069	0.0047
Aug 2026	39	0.022	13	0.083	0.02	0.001	0.00012	0.00065	0.0043
Sep 2026	50	0.029	13	0.11	0.026	0.0013	0.00015	0.00083	0.0056
Oct 2026	50	0.028	13	0.11	0.025	0.0013	0.00015	0.00083	0.0055
Nov 2026	-	-	-	-	-	-	-	-	-
Dec 2026	-	-	-	-	-	-	-	-	-
Jan 2027	-	-	-	-	-	-	-	-	-
Feb 2027	-	-	-	-	-	-	-	-	-
Mar 2027	-	-	-	-	-	-	-	-	-
Apr 2027	-	-	-	-	-	-	-	-	-
May 2027	-	-	-	-	-	-	-	-	-
Jun 2027	9.7	0.0042	13	0.015	0.0035	0.00023	0.000036	0.00016	0.00093
Jul 2027	13	0.0066	13	0.024	0.0057	0.00033	0.000047	0.00023	0.0014
Aug 2027	16	0.0078	13	0.029	0.0068	0.00038	0.000052	0.00026	0.0016
Sep 2027	17	0.0087	13	0.032	0.0075	0.00042	0.000056	0.00028	0.0018
Oct 2027	18	0.0093	13	0.034	0.0081	0.00045	0.000059	0.0003	0.0019
Nov 2027	18	0.0093	13	0.034	0.0081	0.00045	0.000059	0.0003	0.0019
Dec 2027	18	0.0093	13	0.034	0.0081	0.00045	0.000059	0.0003	0.0019
Jan 2028	18	0.0093	13	0.034	0.0081	0.00045	0.000059	0.0003	0.0019
Feb 2028	18	0.0093	13	0.034	0.0081	0.00045	0.000059	0.0003	0.0019
Mar 2028	18	0.0093	13	0.034	0.0081	0.00045	0.000059	0.0003	0.0019
Apr 2028	18	0.0093	13	0.034	0.0081	0.00045	0.000059	0.0003	0.0019
May 2028	18	0.0093	13	0.034	0.0081	0.00045	0.000059	0.0003	0.0019
Jun 2028	18	0.0092	13	0.034	0.008	0.00045	0.000059	0.0003	0.0019
Jul 2028	18	0.0094	13	0.034	0.0082	0.00045	0.00006	0.0003	0.0019
Aug 2028	18	0.0095	13	0.035	0.0083	0.00046	0.000061	0.00031	0.0019
Sep 2028	19	0.0096	13	0.035	0.0084	0.00046	0.000061	0.00031	0.002
Oct 2028	19	0.0097	13	0.036	0.0084	0.00047	0.000062	0.00031	0.002
Nov 2028	19	0.0097	13	0.036	0.0084	0.00047	0.000062	0.00031	0.002
Dec 2028	19	0.0097	13	0.036	0.0084	0.00047	0.000062	0.00031	0.002

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
Tiri-2 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Dissolved Cyanide	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	0.5	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	-	-	-	-	-	-	-	-	-	-
Jun 2020	36	0.011	0.0013	13	0.024	0.0038	0.0008	0.00018	0.00061	0.0031
Jul 2020	53	0.03	0.0011	13	0.084	0.013	0.0015	0.00022	0.0009	0.0063
Aug 2020	50	0.026	0.0012	13	0.071	0.011	0.0014	0.00022	0.00085	0.0057
Sep 2020	58	0.031	0.0012	13	0.087	0.013	0.0016	0.00024	0.00098	0.0067
Oct 2020	53	0.027	0.0013	13	0.071	0.0094	0.0014	0.00023	0.00089	0.006

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
CP1 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	1293	0.079	4.3	0.0039	0.0019	0.00084	0.00023	0.004	0.0086
Jun 2020	1198	0.093	3.8	0.042	0.012	0.0011	0.00057	0.0045	0.0093
Jul 2020	1338	0.13	4.0	0.06	0.023	0.0013	0.00072	0.0048	0.01
Aug 2020	1443	0.19	4.0	0.093	0.043	0.0015	0.00095	0.0048	0.011
Sep 2020	1291	0.24	4.0	0.11	0.057	0.0016	0.001	0.0046	0.011
Oct 2020	1101	0.26	3.7	0.12	0.066	0.0016	0.0011	0.0041	0.01
Nov 2020	1096	0.33	3.7	0.12	0.065	0.0016	0.0011	0.0041	0.01
Dec 2020	1091	0.39	3.7	0.12	0.065	0.0016	0.0011	0.004	0.01
Jan 2021	1086	0.46	3.6	0.11	0.064	0.0016	0.001	0.004	0.01
Feb 2021	1082	0.52	3.6	0.11	0.063	0.0016	0.001	0.004	0.01
Mar 2021	1078	0.59	3.6	0.11	0.063	0.0016	0.001	0.004	0.01
Apr 2021	1073	0.65	3.6	0.11	0.062	0.0016	0.001	0.0039	0.010
May 2021	1069	0.71	3.5	0.11	0.061	0.0015	0.001	0.0039	0.0099
Jun 2021	826	0.46	3.4	0.13	0.055	0.0015	0.0011	0.0033	0.0096
Jul 2021	933	0.47	3.7	0.15	0.065	0.0016	0.0013	0.0034	0.01
Aug 2021	1018	0.45	4.0	0.17	0.076	0.0017	0.0014	0.0033	0.011
Sep 2021	914	0.44	4.2	0.17	0.084	0.0018	0.0014	0.0032	0.012
Oct 2021	787	0.41	4.1	0.17	0.087	0.0017	0.0014	0.0029	0.011
Nov 2021	785	0.48	4.1	0.17	0.086	0.0017	0.0014	0.0029	0.011
Dec 2021	784	0.54	4.0	0.17	0.085	0.0017	0.0013	0.0029	0.011
Jan 2022	782	0.61	4.0	0.17	0.084	0.0017	0.0013	0.0029	0.011
Feb 2022	781	0.67	4.0	0.16	0.083	0.0017	0.0013	0.0029	0.011
Mar 2022	780	0.73	4.0	0.16	0.082	0.0017	0.0013	0.0028	0.011
Apr 2022	778	0.79	3.9	0.16	0.082	0.0017	0.0013	0.0028	0.011
May 2022	777	0.85	3.9	0.16	0.081	0.0017	0.0013	0.0028	0.011
Jun 2022	645	0.56	3.8	0.16	0.068	0.0016	0.0013	0.0026	0.01
Jul 2022	734	0.57	4.1	0.18	0.076	0.0017	0.0014	0.0028	0.011
Aug 2022	805	0.53	4.6	0.19	0.083	0.0018	0.0015	0.0028	0.012
Sep 2022	738	0.51	4.8	0.19	0.088	0.0019	0.0015	0.0028	0.012
Oct 2022	647	0.47	4.7	0.19	0.088	0.0018	0.0014	0.0027	0.011
Nov 2022	647	0.54	4.6	0.18	0.087	0.0018	0.0014	0.0026	0.011
Dec 2022	647	0.61	4.6	0.18	0.086	0.0018	0.0014	0.0026	0.011
Jan 2023	648	0.67	4.5	0.18	0.085	0.0018	0.0014	0.0026	0.011
Feb 2023	648	0.73	4.5	0.18	0.084	0.0018	0.0014	0.0026	0.011
Mar 2023	648	0.8	4.5	0.18	0.083	0.0018	0.0014	0.0026	0.011
Apr 2023	648	0.86	4.4	0.17	0.082	0.0017	0.0013	0.0026	0.011
May 2023	648	0.92	4.4	0.17	0.081	0.0017	0.0013	0.0025	0.011
Jun 2023	537	0.59	4.2	0.17	0.068	0.0016	0.0013	0.0024	0.011
Jul 2023	604	0.6	4.5	0.18	0.077	0.0018	0.0014	0.0026	0.011
Aug 2023	653	0.55	4.9	0.19	0.086	0.0018	0.0015	0.0027	0.012
Sep 2023	600	0.52	5.2	0.2	0.092	0.0019	0.0015	0.0027	0.012
Oct 2023	528	0.48	5.0	0.19	0.092	0.0018	0.0014	0.0025	0.012
Nov 2023	529	0.54	4.9	0.19	0.091	0.0018	0.0014	0.0025	0.012
Dec 2023	531	0.61	4.9	0.18	0.09	0.0018	0.0014	0.0025	0.012
Jan 2024	532	0.68	4.9	0.18	0.089	0.0018	0.0014	0.0025	0.011
Feb 2024	533	0.74	4.8	0.18	0.089	0.0018	0.0014	0.0025	0.011
Mar 2024	534	0.8	4.8	0.18	0.088	0.0018	0.0013	0.0024	0.011
Apr 2024	535	0.86	4.7	0.18	0.087	0.0018	0.0013	0.0024	0.011
May 2024	537	0.92	4.7	0.18	0.086	0.0018	0.0013	0.0024	0.011
Jun 2024	432	0.57	4.2	0.16	0.068	0.0016	0.0013	0.0023	0.01
Jul 2024	480	0.57	4.5	0.18	0.076	0.0018	0.0014	0.0024	0.011
Aug 2024	514	0.52	5.0	0.19	0.082	0.0019	0.0014	0.0025	0.011
Sep 2024	474	0.49	5.2	0.19	0.087	0.0019	0.0014	0.0025	0.011
Oct 2024	418	0.44	5.0	0.18	0.086	0.0018	0.0013	0.0024	0.01
Nov 2024	421	0.5	5.0	0.18	0.086	0.0018	0.0013	0.0024	0.01
Dec 2024	423	0.57	4.9	0.18	0.085	0.0018	0.0013	0.0024	0.01
Jan 2025	425	0.63	4.9	0.18	0.084	0.0018	0.0013	0.0024	0.01
Feb 2025	427	0.69	4.9	0.18	0.083	0.0018	0.0013	0.0024	0.010
Mar 2025	430	0.75	4.8	0.17	0.082	0.0018	0.0013	0.0023	0.0099
Apr 2025	432	0.81	4.8	0.17	0.081	0.0018	0.0012	0.0023	0.0099
May 2025	434	0.87	4.8	0.17	0.081	0.0018	0.0012	0.0023	0.0098
Jun 2025	365	0.54	4.3	0.16	0.066	0.0017	0.0012	0.0022	0.0092
Jul 2025	404	0.55	4.6	0.18	0.073	0.0018	0.0013	0.0024	0.0097
Aug 2025	431	0.5	5.0	0.19	0.079	0.0019	0.0014	0.0025	0.01
Sep 2025	401	0.47	5.2	0.19	0.083	0.0019	0.0014	0.0025	0.0099
Oct 2025	358	0.42	5.0	0.18	0.083	0.0018	0.0013	0.0024	0.0094
Nov 2025	361	0.49	5.0	0.18	0.082	0.0018	0.0013	0.0024	0.0093
Dec 2025	364	0.55	4.9	0.18	0.081	0.0018	0.0013	0.0023	0.0093
Jan 2026	367	0.62	4.9	0.18	0.08	0.0018	0.0013	0.0023	0.0093
Feb 2026	369	0.67	4.8	0.17	0.079	0.0018	0.0013	0.0023	0.0092
Mar 2026	372	0.74	4.8	0.17	0.078	0.0018	0.0012	0.0023	0.0092
Apr 2026	375	0.79	4.8	0.17	0.078	0.0018	0.0012	0.0023	0.0091
May 2026	377	0.85	4.7	0.17	0.077	0.0017	0.0012	0.0023	0.0091
Jun 2026	320	0.53	4.3	0.16	0.064	0.0016	0.0012	0.0022	0.0086
Jul 2026	351	0.53	4.6	0.17	0.071	0.0017	0.0013	0.0023	0.0091
Aug 2026	371	0.48	5.1	0.19	0.079	0.0018	0.0014	0.0024	0.0095
Sep 2026	348	0.46	5.3	0.19	0.085	0.0019	0.0013	0.0024	0.0095
Oct 2026	312	0.41	5.1	0.18	0.085	0.0018	0.0013	0.0023	0.009
Nov 2026	316	0.48	5.1	0.18	0.084	0.0018	0.0013	0.0023	0.0089
Dec 2026	319	0.54	5.0	0.18	0.083	0.0018	0.0013	0.0023	0.0089
Jan 2027	322	0.61	5.0	0.17	0.082	0.0018	0.0012	0.0023	0.0089
Feb 2027	325	0.66	5.0	0.17	0.081	0.0018	0.0012	0.0023	0.0088
Mar 2027	328	0.72	4.9	0.17	0.081	0.0017	0.0012	0.0023	0.0088
Apr 2027	331	0.78	4.9	0.17	0.08	0.0017	0.0012	0.0023	0.0087
May 2027	335	0.84	4.9	0.17	0.079	0.0017	0.0012	0.0022	0.0087
Jun 2027	291	0.53	4.4	0.16	0.066	0.0016	0.0012	0.0022	0.0084
Jul 2027	319	0.54	4.6	0.18	0.074	0.0017	0.0013	0.0023	0.009
Aug 2027	340	0.5	4.9	0.19	0.083	0.0019	0.0014	0.0025	0.0095
Sep 2027	324	0.47	5.1	0.19	0.089	0.0019	0.0014	0.0025	0.0095
Oct 2027	296	0.43	4.8	0.19	0.089	0.0018	0.0013	0.0024	0.0091
Nov 2027	299	0.5	4.7	0.18	0.088	0.0018	0.0013	0.0024	0.009
Dec 2027	303	0.57	4.7	0.18	0.087	0.0018	0.0013	0.0024	0.009
Jan 2028	307	0.63	4.7	0.18	0.087	0.0018	0.0013	0.0024	0.0089
Feb 2028	310	0.69	4.6	0.18	0.086	0.0018	0.0013	0.0023	0.0089
Mar 2028	313	0.75	4.6	0.18	0.085	0.0018	0.0013	0.0023	0.0089
Apr 2028	317	0.81	4.6	0.17	0.084	0.0018	0.0013	0.0023	0.0088
May 2028	320	0.87	4.5	0.17	0.083	0.0018	0.0012	0.0023	0.0088
Jun 2028	270	0.54	4.1	0.16	0.068	0.0017	0.0012	0.0022	0.0085
Jul 2028	293	0.55	4.4	0.18	0.076	0.0018	0.0013	0.0024	0.009
Aug 2028	310	0.51	4.7	0.19	0.085	0.0019	0.0014	0.0025	0.0095
Sep 2028	297	0.48	4.9	0.2	0.091	0.0019	0.0014	0.0025	0.0095
Oct 2028	272	0.44	4.6	0.19	0.09	0.0018	0.0013	0.0024	0.0091
Nov 2028	276	0.5	4.6	0.18	0.089	0.0018	0.0013	0.0024	0.009
Dec 2028	276	0.5	4.6	0.18	0.089	0.0018	0.0013	0.0024	0.009

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
EWTP Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	-	-	-	-	-	-	-	-	-
Jun 2020	1198	0.093	3.8	0.042	0.012	0.0011	0.00057	0.0045	0.0093
Jul 2020	1338	0.13	4.0	0.06	0.023	0.0013	0.00072	0.0048	0.01
Aug 2020	1443	0.19	4.0	0.093	0.043	0.0015	0.00095	0.0048	0.011
Sep 2020	1291	0.24	4.0	0.11	0.057	0.0016	0.001	0.0046	0.011
Oct 2020	-	-	-	-	-	-	-	-	-
Nov 2020	-	-	-	-	-	-	-	-	-
Dec 2020	-	-	-	-	-	-	-	-	-
Jan 2021	-	-	-	-	-	-	-	-	-
Feb 2021	-	-	-	-	-	-	-	-	-
Mar 2021	-	-	-	-	-	-	-	-	-
Apr 2021	-	-	-	-	-	-	-	-	-
May 2021	-	-	-	-	-	-	-	-	-
Jun 2021	826	0.46	3.4	0.13	0.055	0.0015	0.0011	0.0033	0.0096
Jul 2021	933	0.47	3.7	0.15	0.065	0.0016	0.0013	0.0034	0.01
Aug 2021	1018	0.45	4.0	0.17	0.076	0.0017	0.0014	0.0033	0.011
Sep 2021	914	0.44	4.2	0.17	0.084	0.0018	0.0014	0.0032	0.012
Oct 2021	-	-	-	-	-	-	-	-	-
Nov 2021	-	-	-	-	-	-	-	-	-
Dec 2021	-	-	-	-	-	-	-	-	-
Jan 2022	-	-	-	-	-	-	-	-	-
Feb 2022	-	-	-	-	-	-	-	-	-
Mar 2022	-	-	-	-	-	-	-	-	-
Apr 2022	-	-	-	-	-	-	-	-	-
May 2022	-	-	-	-	-	-	-	-	-
Jun 2022	645	0.56	3.8	0.16	0.068	0.0016	0.0013	0.0026	0.01
Jul 2022	734	0.57	4.1	0.18	0.076	0.0017	0.0014	0.0028	0.011
Aug 2022	805	0.53	4.6	0.19	0.083	0.0018	0.0015	0.0028	0.012
Sep 2022	738	0.51	4.8	0.19	0.088	0.0019	0.0015	0.0028	0.012
Oct 2022	-	-	-	-	-	-	-	-	-
Nov 2022	-	-	-	-	-	-	-	-	-
Dec 2022	-	-	-	-	-	-	-	-	-
Jan 2023	-	-	-	-	-	-	-	-	-
Feb 2023	-	-	-	-	-	-	-	-	-
Mar 2023	-	-	-	-	-	-	-	-	-
Apr 2023	-	-	-	-	-	-	-	-	-
May 2023	-	-	-	-	-	-	-	-	-
Jun 2023	537	0.59	4.2	0.17	0.068	0.0016	0.0013	0.0024	0.011
Jul 2023	604	0.6	4.5	0.18	0.077	0.0018	0.0014	0.0026	0.011
Aug 2023	653	0.55	4.9	0.19	0.086	0.0018	0.0015	0.0027	0.012
Sep 2023	600	0.52	5.2	0.2	0.092	0.0019	0.0015	0.0027	0.012
Oct 2023	-	-	-	-	-	-	-	-	-
Nov 2023	-	-	-	-	-	-	-	-	-
Dec 2023	-	-	-	-	-	-	-	-	-
Jan 2024	-	-	-	-	-	-	-	-	-
Feb 2024	-	-	-	-	-	-	-	-	-
Mar 2024	-	-	-	-	-	-	-	-	-
Apr 2024	-	-	-	-	-	-	-	-	-
May 2024	-	-	-	-	-	-	-	-	-
Jun 2024	432	0.57	4.2	0.16	0.068	0.0016	0.0013	0.0023	0.01
Jul 2024	480	0.57	4.5	0.18	0.076	0.0018	0.0014	0.0024	0.011
Aug 2024	514	0.52	5.0	0.19	0.082	0.0019	0.0014	0.0025	0.011
Sep 2024	474	0.49	5.2	0.19	0.087	0.0019	0.0014	0.0025	0.011
Oct 2024	-	-	-	-	-	-	-	-	-
Nov 2024	-	-	-	-	-	-	-	-	-
Dec 2024	-	-	-	-	-	-	-	-	-
Jan 2025	-	-	-	-	-	-	-	-	-
Feb 2025	-	-	-	-	-	-	-	-	-
Mar 2025	-	-	-	-	-	-	-	-	-
Apr 2025	-	-	-	-	-	-	-	-	-
May 2025	-	-	-	-	-	-	-	-	-
Jun 2025	365	0.54	4.3	0.16	0.066	0.0017	0.0012	0.0022	0.0092
Jul 2025	404	0.55	4.6	0.18	0.073	0.0018	0.0013	0.0024	0.0097
Aug 2025	431	0.5	5.0	0.19	0.079	0.0019	0.0014	0.0025	0.01
Sep 2025	401	0.47	5.2	0.19	0.083	0.0019	0.0014	0.0025	0.0099
Oct 2025	-	-	-	-	-	-	-	-	-
Nov 2025	-	-	-	-	-	-	-	-	-
Dec 2025	-	-	-	-	-	-	-	-	-
Jan 2026	-	-	-	-	-	-	-	-	-
Feb 2026	-	-	-	-	-	-	-	-	-
Mar 2026	-	-	-	-	-	-	-	-	-
Apr 2026	-	-	-	-	-	-	-	-	-
May 2026	-	-	-	-	-	-	-	-	-
Jun 2026	320	0.53	4.3	0.16	0.064	0.0016	0.0012	0.0022	0.0086
Jul 2026	351	0.53	4.6	0.17	0.071	0.0017	0.0013	0.0023	0.0091
Aug 2026	371	0.48	5.1	0.19	0.079	0.0018	0.0014	0.0024	0.0095
Sep 2026	348	0.46	5.3	0.19	0.085	0.0019	0.0013	0.0024	0.0095
Oct 2026	-	-	-	-	-	-	-	-	-
Nov 2026	-	-	-	-	-	-	-	-	-
Dec 2026	-	-	-	-	-	-	-	-	-
Jan 2027	-	-	-	-	-	-	-	-	-
Feb 2027	-	-	-	-	-	-	-	-	-
Mar 2027	-	-	-	-	-	-	-	-	-
Apr 2027	-	-	-	-	-	-	-	-	-
May 2027	-	-	-	-	-	-	-	-	-
Jun 2027	291	0.53	4.4	0.16	0.066	0.0016	0.0012	0.0022	0.0084
Jul 2027	319	0.54	4.6	0.18	0.074	0.0017	0.0013	0.0023	0.009
Aug 2027	340	0.5	4.9	0.19	0.083	0.0019	0.0014	0.0025	0.0095
Sep 2027	324	0.47	5.1	0.19	0.089	0.0019	0.0014	0.0025	0.0095
Oct 2027	-	-	-	-	-	-	-	-	-
Nov 2027	-	-	-	-	-	-	-	-	-
Dec 2027	-	-	-	-	-	-	-	-	-
Jan 2028	-	-	-	-	-	-	-	-	-
Feb 2028	-	-	-	-	-	-	-	-	-
Mar 2028	-	-	-	-	-	-	-	-	-
Apr 2028	-	-	-	-	-	-	-	-	-
May 2028	-	-	-	-	-	-	-	-	-
Jun 2028	270	0.54	4.1	0.16	0.068	0.0017	0.0012	0.0022	0.0085
Jul 2028	293	0.55	4.4	0.18	0.076	0.0018	0.0013	0.0024	0.009
Aug 2028	310	0.51	4.7	0.19	0.085	0.0019	0.0014	0.0025	0.0095
Sep 2028	297	0.48	4.9	0.2	0.091	0.0019	0.0014	0.0025	0.0095
Oct 2028	-	-	-	-	-	-	-	-	-
Nov 2028	-	-	-	-	-	-	-	-	-
Dec 2028	-	-	-	-	-	-	-	-	-

0.1 Denotes a value above the discharge criteria

Appendix C
Average Year Scenario
EWTP Average Monthly Total Concentrations

Date	Total Dissolved Solids	Total Phosphorus	Total Ammonia	Total Aluminum	Total Arsenic	Total Copper	Total Lead	Total Nickel	Total Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	-	-	-	-	-	-	-	-	-
Jun 2020	1198	0.16	3.8	0.26	0.013	0.0016	0.00057	0.0045	0.029
Jul 2020	1338	0.2	4.0	0.28	0.024	0.0017	0.00072	0.0048	0.03
Aug 2020	1443	0.26	4.0	0.32	0.044	0.0019	0.00095	0.0048	0.031
Sep 2020	1291	0.3	4.0	0.33	0.058	0.002	0.001	0.0046	0.031
Oct 2020	-	-	-	-	-	-	-	-	-
Nov 2020	-	-	-	-	-	-	-	-	-
Dec 2020	-	-	-	-	-	-	-	-	-
Jan 2021	-	-	-	-	-	-	-	-	-
Feb 2021	-	-	-	-	-	-	-	-	-
Mar 2021	-	-	-	-	-	-	-	-	-
Apr 2021	-	-	-	-	-	-	-	-	-
May 2021	-	-	-	-	-	-	-	-	-
Jun 2021	826	0.52	3.4	0.35	0.056	0.0019	0.0011	0.0033	0.03
Jul 2021	933	0.54	3.7	0.37	0.066	0.002	0.0013	0.0034	0.031
Aug 2021	1018	0.51	4.0	0.39	0.077	0.0021	0.0014	0.0033	0.031
Sep 2021	914	0.5	4.2	0.4	0.085	0.0022	0.0014	0.0032	0.032
Oct 2021	-	-	-	-	-	-	-	-	-
Nov 2021	-	-	-	-	-	-	-	-	-
Dec 2021	-	-	-	-	-	-	-	-	-
Jan 2022	-	-	-	-	-	-	-	-	-
Feb 2022	-	-	-	-	-	-	-	-	-
Mar 2022	-	-	-	-	-	-	-	-	-
Apr 2022	-	-	-	-	-	-	-	-	-
May 2022	-	-	-	-	-	-	-	-	-
Jun 2022	645	0.63	3.8	0.38	0.069	0.002	0.0013	0.0026	0.03
Jul 2022	734	0.63	4.1	0.4	0.077	0.0021	0.0014	0.0028	0.031
Aug 2022	805	0.6	4.6	0.41	0.084	0.0022	0.0015	0.0028	0.032
Sep 2022	738	0.57	4.8	0.42	0.089	0.0023	0.0015	0.0028	0.032
Oct 2022	-	-	-	-	-	-	-	-	-
Nov 2022	-	-	-	-	-	-	-	-	-
Dec 2022	-	-	-	-	-	-	-	-	-
Jan 2023	-	-	-	-	-	-	-	-	-
Feb 2023	-	-	-	-	-	-	-	-	-
Mar 2023	-	-	-	-	-	-	-	-	-
Apr 2023	-	-	-	-	-	-	-	-	-
May 2023	-	-	-	-	-	-	-	-	-
Jun 2023	537	0.66	4.2	0.39	0.069	0.0021	0.0013	0.0024	0.031
Jul 2023	604	0.66	4.5	0.4	0.078	0.0022	0.0014	0.0026	0.031
Aug 2023	653	0.61	4.9	0.42	0.087	0.0023	0.0015	0.0027	0.032
Sep 2023	600	0.59	5.2	0.42	0.093	0.0023	0.0015	0.0027	0.032
Oct 2023	-	-	-	-	-	-	-	-	-
Nov 2023	-	-	-	-	-	-	-	-	-
Dec 2023	-	-	-	-	-	-	-	-	-
Jan 2024	-	-	-	-	-	-	-	-	-
Feb 2024	-	-	-	-	-	-	-	-	-
Mar 2024	-	-	-	-	-	-	-	-	-
Apr 2024	-	-	-	-	-	-	-	-	-
May 2024	-	-	-	-	-	-	-	-	-
Jun 2024	432	0.63	4.2	0.39	0.069	0.0021	0.0013	0.0023	0.03
Jul 2024	480	0.63	4.5	0.4	0.077	0.0022	0.0014	0.0024	0.031
Aug 2024	514	0.58	5.0	0.41	0.083	0.0023	0.0014	0.0025	0.031
Sep 2024	474	0.55	5.2	0.42	0.088	0.0023	0.0014	0.0025	0.031
Oct 2024	-	-	-	-	-	-	-	-	-
Nov 2024	-	-	-	-	-	-	-	-	-
Dec 2024	-	-	-	-	-	-	-	-	-
Jan 2025	-	-	-	-	-	-	-	-	-
Feb 2025	-	-	-	-	-	-	-	-	-
Mar 2025	-	-	-	-	-	-	-	-	-
Apr 2025	-	-	-	-	-	-	-	-	-
May 2025	-	-	-	-	-	-	-	-	-
Jun 2025	365	0.61	4.3	0.39	0.067	0.0021	0.0012	0.0022	0.029
Jul 2025	404	0.61	4.6	0.4	0.074	0.0022	0.0013	0.0024	0.03
Aug 2025	431	0.56	5.0	0.41	0.08	0.0023	0.0014	0.0025	0.03
Sep 2025	401	0.53	5.2	0.41	0.084	0.0023	0.0014	0.0025	0.03
Oct 2025	-	-	-	-	-	-	-	-	-
Nov 2025	-	-	-	-	-	-	-	-	-
Dec 2025	-	-	-	-	-	-	-	-	-
Jan 2026	-	-	-	-	-	-	-	-	-
Feb 2026	-	-	-	-	-	-	-	-	-
Mar 2026	-	-	-	-	-	-	-	-	-
Apr 2026	-	-	-	-	-	-	-	-	-
May 2026	-	-	-	-	-	-	-	-	-
Jun 2026	320	0.59	4.3	0.38	0.065	0.002	0.0012	0.0022	0.029
Jul 2026	351	0.59	4.6	0.4	0.072	0.0021	0.0013	0.0023	0.029
Aug 2026	371	0.55	5.1	0.41	0.08	0.0022	0.0014	0.0024	0.03
Sep 2026	348	0.52	5.3	0.41	0.086	0.0023	0.0013	0.0024	0.03
Oct 2026	-	-	-	-	-	-	-	-	-
Nov 2026	-	-	-	-	-	-	-	-	-
Dec 2026	-	-	-	-	-	-	-	-	-
Jan 2027	-	-	-	-	-	-	-	-	-
Feb 2027	-	-	-	-	-	-	-	-	-
Mar 2027	-	-	-	-	-	-	-	-	-
Apr 2027	-	-	-	-	-	-	-	-	-
May 2027	-	-	-	-	-	-	-	-	-
Jun 2027	291	0.59	4.4	0.38	0.067	0.002	0.0012	0.0022	0.029
Jul 2027	319	0.6	4.6	0.4	0.075	0.0021	0.0013	0.0023	0.029
Aug 2027	340	0.56	4.9	0.41	0.084	0.0023	0.0014	0.0025	0.03
Sep 2027	324	0.54	5.1	0.42	0.09	0.0023	0.0014	0.0025	0.03
Oct 2027	-	-	-	-	-	-	-	-	-
Nov 2027	-	-	-	-	-	-	-	-	-
Dec 2027	-	-	-	-	-	-	-	-	-
Jan 2028	-	-	-	-	-	-	-	-	-
Feb 2028	-	-	-	-	-	-	-	-	-
Mar 2028	-	-	-	-	-	-	-	-	-
Apr 2028	-	-	-	-	-	-	-	-	-
May 2028	-	-	-	-	-	-	-	-	-
Jun 2028	270	0.61	4.1	0.39	0.069	0.0021	0.0012	0.0022	0.029
Jul 2028	293	0.61	4.4	0.4	0.077	0.0022	0.0013	0.0024	0.029
Aug 2028	310	0.57	4.7	0.41	0.086	0.0023	0.0014	0.0025	0.03
Sep 2028	297	0.55	4.9	0.42	0.092	0.0023	0.0014	0.0025	0.03
Oct 2028	-	-	-	-	-	-	-	-	-
Nov 2028	-	-	-	-	-	-	-	-	-
Dec 2028	-	-	-	-	-	-	-	-	-

0.1 Denotes a value above the discharge criteria

APPENDIX D

**Tabulated Water Balance Results,
Wet Years Scenario**

Water Balance for TSF

Date	Inflow		Outflow					
			The Portion to CP1			The Portion to CP3		
	Total Surface Runoff Water from TSF	Estimated Volume of Seepage through Tailings	TSF Tailings Surface Runoff Collected in CP1	TSF Waste Rock Cover Runoff Water Collected in CP1	Seepage Water through Tailings into CP1	TSF Tailings Surface Runoff Collected in CP3	TSF Waste Rock Cover Runoff Water Collected in CP3	Seepage Water through Tailings into CP3
	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³
May-20	0	0	0	0	0	0	0	0
Jun-20	60039	178	10405	21832	113	5970	21832	65
Jul-20	19777	178	3427	7192	113	1966	7192	65
Aug-20	21548	178	3734	7836	113	2143	7836	65
Sep-20	16115	178	2793	5860	113	1602	5860	65
Oct-20	16183	178	2804	5885	113	1609	5885	65
Nov-20	0	0	0	0	0	0	0	0
Dec-20	0	0	0	0	0	0	0	0
Jan-21	0	0	0	0	0	0	0	0
Feb-21	0	0	0	0	0	0	0	0
Mar-21	0	0	0	0	0	0	0	0
Apr-21	0	0	0	0	0	0	0	0
May-21	0	0	0	0	0	0	0	0
Jun-21	40112	178	6951	14586	113	3988	14586	65
Jul-21	13214	178	2290	4805	113	1314	4805	65
Aug-21	14396	178	2495	5235	113	1431	5235	65
Sep-21	10767	178	1866	3915	113	1071	3915	65
Oct-21	10812	178	1874	3932	113	1075	3932	65
Nov-21	0	0	0	0	0	0	0	0
Dec-21	0	0	0	0	0	0	0	0
Jan-22	0	0	0	0	0	0	0	0
Feb-22	0	0	0	0	0	0	0	0
Mar-22	0	0	0	0	0	0	0	0
Apr-22	0	0	0	0	0	0	0	0
May-22	0	0	0	0	0	0	0	0
Jun-22	40112	178	6951	14586	113	3988	14586	65
Jul-22	13214	178	2290	4805	113	1314	4805	65
Aug-22	14396	178	2495	5235	113	1431	5235	65
Sep-22	10767	178	1866	3915	113	1071	3915	65
Oct-22	10812	178	1874	3932	113	1075	3932	65
Nov-22	0	0	0	0	0	0	0	0
Dec-22	0	0	0	0	0	0	0	0
Jan-23	0	0	0	0	0	0	0	0
Feb-23	0	0	0	0	0	0	0	0
Mar-23	0	0	0	0	0	0	0	0
Apr-23	0	0	0	0	0	0	0	0
May-23	0	0	0	0	0	0	0	0
Jun-23	40112	178	6951	14586	113	3988	14586	65
Jul-23	13214	178	2290	4805	113	1314	4805	65
Aug-23	14396	178	2495	5235	113	1431	5235	65
Sep-23	10767	178	1866	3915	113	1071	3915	65

Water Collection from WRSF's

Date	WRSF-1				Temporary WRSF		WRSF-3		
	Total Water to be Collected	Portion of the Water to be Collected in CP5 (Lake A54)	Portion of the Water to be Collected in CP1 (Lake H17)	Portion of the Water to be Collected in CP4	Total Water to be Collected	Portion of the Water to be Collected in Tiri-1000-02	Total Water to be Collected	Portion of the Water to be Collected in CP6	Portion of the Water to be Collected in CP2
	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³
May-20	0	0	0	0	0	0	0	0	0
Jun-20	1614	210	613	791	110	0	4187	4187	0
Jul-20	24	3	9	12	2	0	62	62	0
Aug-20	32	4	12	16	2	0	82	82	0
Sep-20	9	1	4	5	1	0	24	24	0
Oct-20	0	0	0	0	0	0	0	0	0
Nov-20	0	0	0	0	0	0	0	0	0
Dec-20	0	0	0	0	0	0	0	0	0
Jan-21	0	0	0	0	0	0	0	0	0
Feb-21	0	0	0	0	0	0	0	0	0
Mar-21	0	0	0	0	0	0	0	0	0
Apr-21	0	0	0	0	0	0	0	0	0
May-21	0	0	0	0	0	0	0	0	0
Jun-21	1942	252	738	952	74	0	2797	2797	0
Jul-21	29	4	11	14	1	0	42	42	0
Aug-21	38	5	15	19	1	0	55	55	0
Sep-21	11	1	4	5	0	0	16	16	0
Oct-21	0	0	0	0	0	0	0	0	0
Nov-21	0	0	0	0	0	0	0	0	0
Dec-21	0	0	0	0	0	0	0	0	0
Jan-22	0	0	0	0	0	0	0	0	0
Feb-22	0	0	0	0	0	0	0	0	0
Mar-22	0	0	0	0	0	0	0	0	0
Apr-22	0	0	0	0	0	0	0	0	0
May-22	0	0	0	0	0	0	0	0	0
Jun-22	2806	365	1066	1375	74	0	2797	2797	0
Jul-22	42	5	16	20	1	0	42	42	0
Aug-22	55	7	21	27	1	0	55	55	0
Sep-22	16	2	6	8	0	0	16	16	0
Oct-22	0	0	0	0	0	0	0	0	0
Nov-22	0	0	0	0	0	0	0	0	0
Dec-22	0	0	0	0	0	0	0	0	0
Jan-23	0	0	0	0	0	0	0	0	0
Feb-23	0	0	0	0	0	0	0	0	0
Mar-23	0	0	0	0	0	0	0	0	0
Apr-23	0	0	0	0	0	0	0	0	0
May-23	0	0	0	0	0	0	0	0	0
Jun-23	2806	365	1066	1375	74	0	2797	2797	0
Jul-23	42	5	16	20	1	0	42	42	0
Aug-23	55	7	21	27	1	0	55	55	0
Sep-23	16	2	6	8	0	0	16	16	0

Water Collection from Ore Stockpiles

Date	OP2		OP2-Extn.	
	Total Water to be Collected	Portion of the Water to be Collected in CP5 (Lake A54)	Total Water to be Collected	Portion of the Water to be Collected in Tiri-1000-02
	m ³	m ³	m ³	m ³
May-20	0	0	0	0
Jun-20	1374	1374	0	0
Jul-20	20	20	0	0
Aug-20	27	27	0	0
Sep-20	8	8	0	0
Oct-20	0	0	0	0
Nov-20	0	0	0	0
Dec-20	0	0	0	0
Jan-21	0	0	0	0
Feb-21	0	0	0	0
Mar-21	0	0	0	0
Apr-21	0	0	0	0
May-21	0	0	0	0
Jun-21	918	918	0	0
Jul-21	14	14	0	0
Aug-21	18	18	0	0
Sep-21	5	5	0	0
Oct-21	0	0	0	0
Nov-21	0	0	0	0
Dec-21	0	0	0	0
Jan-22	0	0	0	0
Feb-22	0	0	0	0
Mar-22	0	0	0	0
Apr-22	0	0	0	0
May-22	0	0	0	0
Jun-22	918	918	561	561
Jul-22	14	14	8	8
Aug-22	18	18	11	11
Sep-22	5	5	3	3
Oct-22	0	0	0	0
Nov-22	0	0	0	0
Dec-22	0	0	0	0
Jan-23	0	0	0	0
Feb-23	0	0	0	0
Mar-23	0	0	0	0
Apr-23	0	0	0	0
May-23	0	0	0	0
Jun-23	918	918	561	561
Jul-23	14	14	8	8
Aug-23	18	18	11	11
Sep-23	5	5	3	3

Water Collection from Ore Stockpiles

Date	OP2		OP2-Extn.	
	Total Water to be Collected	Portion of the Water to be Collected in CP5 (Lake A54)	Total Water to be Collected	Portion of the Water to be Collected in Tiri-1000-02
	m ³	m ³	m ³	m ³
Oct-23	0	0	0	0
Nov-23	0	0	0	0
Dec-23	0	0	0	0
Jan-24	0	0	0	0
Feb-24	0	0	0	0
Mar-24	0	0	0	0
Apr-24	0	0	0	0
May-24	0	0	0	0
Jun-24	918	918	561	561
Jul-24	14	14	8	8
Aug-24	18	18	11	11
Sep-24	5	5	3	3
Oct-24	0	0	0	0
Nov-24	0	0	0	0
Dec-24	0	0	0	0
Jan-25	0	0	0	0
Feb-25	0	0	0	0
Mar-25	0	0	0	0
Apr-25	0	0	0	0
May-25	0	0	0	0
Jun-25	1374	1374	840	840
Jul-25	20	20	12	12
Aug-25	27	27	17	17
Sep-25	8	8	5	5
Oct-25	0	0	0	0
Nov-25	0	0	0	0
Dec-25	0	0	0	0
Jan-26	0	0	0	0
Feb-26	0	0	0	0
Mar-26	0	0	0	0
Apr-26	0	0	0	0
May-26	0	0	0	0
Jun-26	918	918	561	561
Jul-26	14	14	8	8
Aug-26	18	18	11	11
Sep-26	5	5	3	3
Oct-26	0	0	0	0
Nov-26	0	0	0	0
Dec-26	0	0	0	0
Jan-27	0	0	0	0
Feb-27	0	0	0	0

Water Collection from Ore Stockpiles

Date	OP2		OP2-Extn.	
	Total Water to be Collected	Portion of the Water to be Collected in CP5 (Lake A54)	Total Water to be Collected	Portion of the Water to be Collected in Tiri-1000-02
	m ³	m ³	m ³	m ³
Mar-27	0	0	0	0
Apr-27	0	0	0	0
May-27	0	0	0	0
Jun-27	918	918	561	561
Jul-27	14	14	8	8
Aug-27	18	18	11	11
Sep-27	5	5	3	3
Oct-27	0	0	0	0
Nov-27	0	0	0	0
Dec-27	0	0	0	0
Jan-28	0	0	0	0
Feb-28	0	0	0	0
Mar-28	0	0	0	0
Apr-28	0	0	0	0
May-28	0	0	0	0
Jun-28	918	918	561	561
Jul-28	14	14	8	8
Aug-28	18	18	11	11
Sep-28	5	5	3	3
Oct-28	0	0	0	0
Nov-28	0	0	0	0
Dec-28	0	0	0	0

Water Balance for Open Pits

Date	Tiri-1						Tiri-2										
	Inflow			Outflow		Storage	Inflow					Outflow				Storage	
	Net Runoff/Run on Water from Water Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Water Pumped to CP5 and transfer to CP1	Water lost to WRF/Ore	Water Stored in Open Pit	Net Runoff/Run on Water from Water Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Net runoff from Temporary WRSF	Inflow from UG	Water Pumped to CP5	Water Lost to WRSF and Ore	To SP-1	Water Pumped to SETP	Water through Bypass	Water Stored in Open Pit
	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³	m ³
May-20							0	0	0	0	0	0	0	0	0	0	0
Jun-20							0	15900	11721	110	0	7160	20571	0	0	0	0
Jul-20							0	3389	3861	2	0	4680	2571	0	0	0	0
Aug-20							0	4484	4207	2	0	6121	2571	0	0	0	0
Sep-20							0	3912	3146	1	0	4487	2571	0	0	0	0
Oct-20							0	4286	3159	0	0	4874	2571	0	0	0	0
Nov-20							0	0	0	0	0	0	0	0	0	0	0
Dec-20							0	0	0	0	0	0	0	0	0	0	0
Jan-21	0	0	0	0	0	0	0	0	0	0	17521	0	0	0	0	0	17521
Feb-21	0	0	0	0	0	0	0	0	0	0	15631	0	0	0	0	0	33152
Mar-21	0	0	0	0	0	0	0	0	0	0	17521	0	0	0	0	0	50673
Apr-21	0	0	0	0	0	0	0	0	0	0	17491	0	0	0	0	0	68164
May-21	0	0	0	0	0	0	0	0	0	0	18141	0	0	0	0	0	86305
Jun-21	0	5972	23860		28376	0	455	10623	7024	74	17491	0	2795	0	0	0	119176
Jul-21	0	1273	7860		8951	0	-684	2264	2273	1	19071	0	349	0	0	0	141752
Aug-21	0	1684	8563		10065	0	-279	2995	2420	1	19071	0	349	0	0	0	165612
Sep-21	0	1469	6404		7692	0	89	2614	1746	0	0	0	349	0	0	0	169711
Oct-21	0	1610	6431		7859	0	734	2863	1707	0	0	0	349	0	0	0	174666
Nov-21	0	0	0		0	0	0	0	0	0	18991	0	0	0	0	0	193657
Dec-21	0	0	0		0	0	0	0	0	0	19691	0	0	0	0	0	213348
Jan-22	0	0	0		0	0	0	0	0	0	21232	0	0	0	0	0	234579
Feb-22	0	0	0		0	0	0	0	0	0	18982	0	0	0	0	0	253561
Mar-22	0	0	0		0	0	0	0	0	0	21232	0	0	0	0	0	274793
Apr-22	0	0	0		0	0	0	0	0	0	20482	0	0	0	0	0	295274
May-22	0	0	0		0	0	0	0	0	0	21232	0	0	0	0	0	316506
Jun-22	0	5972	23860		7550	0	1074	10623	5925	74	20482	0	3510	0	0	0	351173
Jul-22	0	1273	7860		6348	0	-1454	2264	1929	1	0	0	439	0	0	15851	337624
Aug-22	0	1684	8563		7462	0	-512	2995	2093	1	0	0	439	0	69841	93000	178921
Sep-22	0	1469	6404		5088	0	118	2614	1629	0	22282	0	439	0	88861	90000	26264
Oct-22	0	1610	6431		5256	0	505	2863	1833	0	23092	0	439	0	0	0	54117
Nov-22	0	0	0		0	0	0	0	0	0	22282	0	0	0	0	0	76399
Dec-22	0	0	0		0	0	0	0	0	0	23092	0	0	0	0	0	99490
Jan-23	0	0	0		0	0	0	0	0	0	24016	0	0	0	0	0	123507
Feb-23	0	0	0		0	0	0	0	0	0	21496	0	0	0	0	0	145003
Mar-23	0	0	0		0	0	0	0	0	0	24016	0	0	0	0	0	169019
Apr-23	0	0	0		0	0	0	0	0	0	23176	0	0	0	0	0	192195
May-23	0	0	0		0	0	0	0	0	0	24016	0	0	0	0	0	216211
Jun-23	0	5972	30356		14000	0	917	10623	6204	74	23176	0	0	39573	45000	0	172632
Jul-23	0	1273	10000		8482	0	-1173	2264	2055	1	24016	0	0	93662	93000	0	13134
Aug-23	0	1684	10894		9787	0	-244	2995	2469	1	24016	0	0	42372	0	0	0
Sep-23	0	1469	8148		6826	0	0	2614	2051	0	23176	0	19940	7901	0	0	0
Oct-23	0	1610	8182		7001	0	0	2863	2111	0	24016	0	0	0	0	0	28990
Nov-23	0	0	0		0	0	0	0	0	0	23176	0	0	0	0	0	52166
Dec-23	0	0	0		0	0	0	0	0	0	24016	0	0	0	0	0	76182
Jan-24	0	0	0		0	0	0	0	0	0	24319	0	0	0	0	0	100501
Feb-24	0	0	0		0	0	0	0	0	0	22619	0	0	0	0	0	123120
Mar-24	0	0	0		0	0	0	0	0	0	24319	0	0	0	0	0	147438
Apr-24	0	0	0		0	0	0	0	0	0	23469	0	0	0	0	0	170907
May-24	0	0	0		0	0	0	0	0	0	24319	0	0	0	0	0	195225
Jun-24	0	5972	30356		0	0	876	10623	6276	74	23469	0	0	44052	45000	0	147490
Jul-24	0	1273	10000		5149	0	-1037	2264	2116	1	24319	0	0	93662	81490	0	0
Aug-24	0	1684	10894		6455	0	0	2995	2592	1	24319	0	0	29907	0	0	0
Sep-24	0	1469	8148		3494	0	0	2614	2102	0	23469	0	19940	8245	0	0	0
Oct-24	0	1610	8182		3668	0	0	2863	2111	0	24319	0	0	0	0	0	29292
Nov-24	0	0	0		0	0	0	0	0	0	23469	0	0	0	0	0	52761
Dec-24	0	0	0		0	0	0	0	0	0	24319	0	0	0	0	0	77079
Jan-25	0	0	0		0	0	0	0	0	0	27061	0	0	0	0	0	104141
Feb-25	0	0	0		0	0	0	0	0	0	24271	0	0	0	0	0	128412
Mar-25	0	0	0		0	0	0	0	0	0	27061	0	0	0	0	0	155474
Apr-25	0	0	0		0	0	0	0	0	0	26131	0	0	0	0	0	181605
May-25	0	0	0		0	0	0	0	0	0	27061	0	0	0	0	0	208667
Jun-25	0	8939	45436		12591	0	1347	15900	9331	0	26131	0	0	43801	45000	0	172575
Jul-25	0	1905	14967		11649	0	-1742	3389	3082	0	27061	0	0	93991	93000	0	17374
Aug-25	0	2521	16307		13604	0	-374	4484	3683	0	27061	0	0	52229	0	0	0
Sep-25	0	2199	12195		9171	0	0	3912	3060	0	26131	0	19910	13193	0	0	0
Oct-25	0	2409	12247		9433	0	0	4286	3159	0	27061	0	0	0	0	0	34506
Nov-25	0	0	0		0	0	0	0	0	0	26131	0	0	0	0	0	60638
Dec-25	0	0	0		0	0	0	0	0	0	27061	0	0	0	0	0	87699
Jan-26	0	0	0		0	0	0	0	0	0	27822	0	0	0	0	0	115521
Feb-26	0	0	0		0	0	0	0	0	0	24972	0	0	0	0	0	140493
Mar-26	0	0	0		0	0	0	0	0	0	27822	0	0	0	0	0	168315
Apr-26	0	0	0		0	0	0	0	0	0	26872	0	0	0	0	0	195188
May-26	0	0	0		0	0	0	0	0	0	27822	0	0	0	0	0	223010
Jun-26	0	5972	30356		9,231	0	925	10623	6189	0	26872	0	0	43834	45000	0	178785
Jul-26	0	1273	10000		7,886	0	-1189	2264	2048	0	27822	0	0	93662	93000	0	23068
Aug-26	0	1684	10894		9,191	0	-261	2995	2445	0	27822	0	0	56070	0	0	0
Sep-26	0	1469	8148		6,230	0	0	2614	2036	0	26872	0	19940	11582	0	0	0
Oct-26	0	1610	8182		6,405	0	0	2863	2111	0	27822	0	0	0	0	0	32796
Nov-26	0	0	0		0	0	0	0	0	0	26872	0	0	0	0	0	59668

Dec-26	0	0	0	0	0	0	0	0	0	27822	0	0	0	0	87490
Jan-27	0	0	0	0	0	0	0	0	0	26040	0	0	0	0	113530
Feb-27	0	0	0	0	0	0	0	0	0	23520	0	0	0	0	137050
Mar-27	0	0	0	0	0	0	0	0	0	26040	0	0	0	0	163090
Apr-27	0	0	0	0	0	0	0	0	0	25200	0	0	0	0	188290
May-27	0	0	0	0	0	0	0	0	0	26040	0	0	0	0	214330
Jun-27	0	5972	30356	36,328	912	10623	6213	0	25200	0	0	44052	45000	168225	
Jul-27	-200	1273	9910	47,311	-1164	2264	2059	0	26040	0	0	93662	93000	10762	
Aug-27	-204	1684	10609	59,400	-239	2995	2475	0	26040	0	0	42034	0	0	
Sep-27	90	1469	7788	68,747	0	2614	2053	0	25200	0	19940	9927	0	0	
Oct-27	859	1610	7710	78,925	0	2863	2111	0	26040	0	0	0	0	31014	
Nov-27	0	0	0	78,925	0	0	0	0	25200	0	0	0	0	56214	
Dec-27	0	0	0	78,925	0	0	0	0	26040	0	0	0	0	82254	
Jan-28	0	0	0	78,925	0	0	0	0	26970	0	0	0	0	109224	
Feb-28	0	0	0	78,925	0	0	0	0	25230	0	0	0	0	134454	
Mar-28	0	0	0	78,925	0	0	0	0	26970	0	0	0	0	161424	
Apr-28	0	0	0	78,925	0	0	0	0	26100	0	0	0	0	187524	
May-28	0	0	0	78,925	0	0	0	0	26970	0	0	0	0	214494	
Jun-28	2380	5972	26133	113,411	911	10623	6214	0	26100	0	0	0	0	258342	
Jul-28	-3247	1273	8547	119,984	-1270	2264	2011	0	26970	0	0	0	0	288318	
Aug-28	-1196	1684	9220	129,692	-468	2995	2155	0	26970	0	0	0	0	319970	
Sep-28	337	1469	6800	138,299	128	2614	1591	0	26100	0	19885	0	0	330518	
Oct-28	2893	1610	6591	149,392	957	2863	1584	0	26970	0	0	0	0	362892	
Nov-28	0	0	0	149,392	0	0	0	0	26100	0	0	0	0	388992	
Dec-28	0	0	0	149,392	0	0	0	0	26970	0	0	0	0	415962	

Water Balance for CP3					
Date	Inflow				Outflow
	Net Runoff/Run on Water from Pond Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Net Runoff/Seepage Water from a Portion of TSP to CP3	Water Pumped from CP3 to Site Area Ditch, then Flowing into CP1
	m ³	m ³	m ³	m ³	m ³
May-20	0	0	0	0	0
Jun-20	386	11759	0	27867	40012
Jul-20	-504	2506	0	9223	11226
Aug-20	-175	3316	0	10043	13184
Sep-20	46	2893	0	7527	10466
Oct-20	335	3170	0	7559	11064
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	258	7856	0	18640	26754
Jul-21	-337	1675	0	6184	7522
Aug-21	-117	2215	0	6731	8829
Sep-21	31	1933	0	5051	7014
Oct-21	224	2118	0	5072	7413
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	258	7856	0	18640	26754
Jul-22	-337	1675	0	6184	7522
Aug-22	-117	2215	0	6731	8829
Sep-22	31	1933	0	5051	7014
Oct-22	224	2118	0	5072	7413
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	258	7856	0	18640	26754
Jul-23	-337	1675	0	6184	7522
Aug-23	-117	2215	0	6731	8829
Sep-23	31	1933	0	5051	7014
Oct-23	224	2118	0	5072	7413
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	258	7856	0	18640	26754
Jul-24	-337	1675	0	6184	7522
Aug-24	-117	2215	0	6731	8829
Sep-24	31	1933	0	5051	7014
Oct-24	224	2118	0	5072	7413
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0
Jun-25	386	11759	0	27867	40012
Jul-25	-504	2506	0	9223	11226
Aug-25	-175	3316	0	10043	13184
Sep-25	46	2893	0	7527	10466
Oct-25	335	3170	0	7559	11064
Nov-25	0	0	0	0	0
Dec-25	0	0	0	0	0
Jan-26	0	0	0	0	0
Feb-26	0	0	0	0	0
Mar-26	0	0	0	0	0
Apr-26	0	0	0	0	0
May-26	0	0	0	0	0
Jun-26	258	7856	0	18640	26754
Jul-26	-337	1675	0	6184	7522
Aug-26	-117	2215	0	6731	8829
Sep-26	31	1933	0	5051	7014
Oct-26	224	2118	0	5072	7413
Nov-26	0	0	0	0	0
Dec-26	0	0	0	0	0
Jan-27	0	0	0	0	0
Feb-27	0	0	0	0	0
Mar-27	0	0	0	0	0
Apr-27	0	0	0	0	0
May-27	0	0	0	0	0
Jun-27	258	7856	0	18640	26754
Jul-27	-337	1675	0	6184	7522
Aug-27	-117	2215	0	6731	8829
Sep-27	31	1933	0	5051	7014
Oct-27	224	2118	0	5072	7413
Nov-27	0	0	0	0	0
Dec-27	0	0	0	0	0
Jan-28	0	0	0	0	0

Water Balance for CP4					
Date	Inflow				Outflow
	Net Runoff/Run on Water from Pond Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground	Net Runoff/Seepage Water from a Portion of WRSF1 to CP4	Water pumped from CP4 to Site Area Ditch, then Flowing into CP1
	m ³	m ³	m ³	m ³	m ³
May-20	0	0	0	0	0
Jun-20	696	37777	88	791	39332
Jul-20	-910	9223	29	12	7183
Aug-20	-317	10653	31	16	10383
Sep-20	83	9294	24	5	9405
Oct-20	605	10182	24	0	10811
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	465	20101	76	952	21594
Jul-21	-608	4285	25	14	3716
Aug-21	-212	5668	27	19	5503
Sep-21	55	4946	20	5	5027
Oct-21	404	5418	21	0	5843
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	465	14964	94	1375	16898
Jul-22	-608	3190	31	20	2633
Aug-22	-212	4219	34	27	4069
Sep-22	55	3682	25	8	3770
Oct-22	404	4033	25	0	4463
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	465	14964	94	1375	16898
Jul-23	-608	3190	31	20	2633
Aug-23	-212	4219	34	27	4069
Sep-23	55	3682	25	8	3770
Oct-23	404	4033	25	0	4463
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	465	14964	94	1375	16898
Jul-24	-608	3190	31	20	2633
Aug-24	-212	4219	34	27	4069
Sep-24	55	3682	25	8	3770
Oct-24	404	4033	25	0	4463
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0
Jun-25	696	22397	141	2058	25293
Jul-25	-910	4774	46	31	3941
Aug-25	-317	6316	51	40	6090
Sep-25	83	5511	38	12	5643
Oct-25	605	6037	38	0	6680
Nov-25	0	0	0	0	0
Dec-25	0	0	0	0	0
Jan-26	0	0	0	0	0
Feb-26	0	0	0	0	0
Mar-26	0	0	0	0	0
Apr-26	0	0	0	0	0
May-26	0	0	0	0	0
Jun-26	465	14964	94	1375	16898
Jul-26	-608	3190	31	20	2633
Aug-26	-212	4219	34	27	4069
Sep-26	55	3682	25	8	3770
Oct-26	404	4033	25	0	4463
Nov-26	0	0	0	0	0
Dec-26	0	0	0	0	0
Jan-27	0	0	0	0	0
Feb-27	0	0	0	0	0
Mar-27	0	0	0	0	0
Apr-27	0	0	0	0	0
May-27	0	0	0	0	0
Jun-27	465	14964	94	1375	16898
Jul-27	-608	3190	31	20	2633
Aug-27	-212	4219	34	27	4069
Sep-27	55	3682	25	8	3770
Oct-27	404	4033	25	0	4463
Nov-27	0	0	0	0	0
Dec-27	0	0	0	0	0
Jan-28	0	0	0	0	0

Water Balance for CP3					
Date	Inflow				Outflow
	Net Runoff/Run on Water from Pond Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground Surface	Net Runoff/Seepage Water from a Portion of TSF to CP3	Water Pumped from CP3 to Site Area Ditch, then Flowing into CP1
	m ³	m ³	m ³	m ³	m ³
Feb-28	0	0	0	0	0
Mar-28	0	0	0	0	0
Apr-28	0	0	0	0	0
May-28	0	0	0	0	0
Jun-28	258	7856	0	18640	26754
Jul-28	-337	1675	0	6184	7522
Aug-28	-117	2215	0	6731	8829
Sep-28	31	1933	0	5051	7014
Oct-28	224	2118	0	5072	7413
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

Water Balance for CP4					
Date	Inflow				Outflow
	Net Runoff/Run on Water from Pond Surface	Net Runoff/Run on Water from Natural Ground with Vegetation	Net Runoff/Run on Water from Other Disturbed Ground	Net Runoff/Seepage Water from a Portion of WRSF1 to CP4	Water pumped from CP4 to Site Area Ditch, then Flowing into CP1
	m ³	m ³	m ³	m ³	m ³
Feb-28	0	0	0	0	0
Mar-28	0	0	0	0	0
Apr-28	0	0	0	0	0
May-28	0	0	0	0	0
Jun-28	465	14964	94	1375	16898
Jul-28	-608	3190	31	20	2633
Aug-28	-212	4219	34	27	4069
Sep-28	55	3682	25	8	3770
Oct-28	404	4033	25	0	4463
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

Water Balance for CP6					
Date	Inflow				Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Net Runoff/Seepage Water from WRSF3 and WRSF3 Exten.	
	m ³	m ³	m ³	m ³	
May-20	0	0	0	0	0
Jun-20	1313	18005	0	4187	23503
Jul-20	-1715	3838	0	62	2183
Aug-20	-597	5077	0	82	4563
Sep-20	156	4430	0	24	4610
Oct-20	1141	4853	0	0	5994
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	877	12029	0	2797	15704
Jul-21	-1146	2564	0	42	1460
Aug-21	-399	3392	0	55	3048
Sep-21	104	2960	0	16	3080
Oct-21	763	3242	0	0	4005
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	877	12029	0	2797	15704
Jul-22	-1146	2564	0	42	1460
Aug-22	-399	3392	0	55	3048
Sep-22	104	2960	0	16	3080
Oct-22	763	3242	0	0	4005
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	877	12029	0	2797	15704
Jul-23	-1146	2564	0	42	1460
Aug-23	-399	3392	0	55	3048
Sep-23	104	2960	0	16	3080
Oct-23	763	3242	0	0	4005
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	877	12029	202	2779	15887
Jul-24	-1146	2564	67	41	1526
Aug-24	-399	3392	73	55	3120
Sep-24	104	2960	54	16	3134
Oct-24	763	3242	54	0	4059
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0
Jun-25	1313	18005	303	4160	23780
Jul-25	-1715	3838	100	62	2284
Aug-25	-597	5077	109	82	4671
Sep-25	156	4430	81	24	4691
Oct-25	1141	4853	82	0	6076
Nov-25	0	0	0	0	0
Dec-25	0	0	0	0	0
Jan-26	0	0	0	0	0
Feb-26	0	0	0	0	0
Mar-26	0	0	0	0	0
Apr-26	0	0	0	0	0
May-26	0	0	0	0	0
Jun-26	877	12029	202	2779	15887
Jul-26	-1146	2564	67	41	1526
Aug-26	-399	3392	73	55	3120
Sep-26	104	2960	54	16	3134
Oct-26	763	3242	54	0	4059
Nov-26	0	0	0	0	0
Dec-26	0	0	0	0	0
Jan-27	0	0	0	0	0
Feb-27	0	0	0	0	0
Mar-27	0	0	0	0	0
Apr-27	0	0	0	0	0
May-27	0	0	0	0	0
Jun-27	877	12029	202	2779	15887
Jul-27	-1146	2564	67	41	1526
Aug-27	-399	3392	73	55	3120
Sep-27	104	2960	54	16	3134
Oct-27	763	3242	54	0	4059
Nov-27	0	0	0	0	0
Dec-27	0	0	0	0	0
Jan-28	0	0	0	0	0

Water Balance for CP2					
Date	Inflow				Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Net Runoff/Seepage Water from WRSF3 and WRSF3 Exten.	
	m ³	m ³	m ³	m ³	
May-20	0	0	0	0	0
Jun-20	0	0	0	0	0
Jul-20	0	0	0	0	0
Aug-20	0	0	0	0	0
Sep-20	0	0	0	0	0
Oct-20	0	0	0	0	0
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	0	0	0	0	0
Jul-21	0	0	0	0	0
Aug-21	0	0	0	0	0
Sep-21	0	0	0	0	0
Oct-21	0	0	0	0	0
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	0	0	0	0	0
Jul-22	0	0	0	0	0
Aug-22	0	0	0	0	0
Sep-22	0	0	0	0	0
Oct-22	0	0	0	0	0
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	0	0	0	0	0
Jul-23	0	0	0	0	0
Aug-23	0	0	0	0	0
Sep-23	0	0	0	0	0
Oct-23	0	0	0	0	0
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	877	45970	0	2183	49031
Jul-24	-1146	9799	0	32	8686
Aug-24	-399	12963	0	43	12607
Sep-24	104	11311	0	12	11428
Oct-24	763	12391	0	0	13153
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0
Jun-25	1313	68808	0	3268	73388
Jul-25	-1715	14666	0	49	13000
Aug-25	-597	19403	0	64	18870
Sep-25	156	16929	0	19	17104
Oct-25	1141	18546	0	0	19688
Nov-25	0	0	0	0	0
Dec-25	0	0	0	0	0
Jan-26	0	0	0	0	0
Feb-26	0	0	0	0	0
Mar-26	0	0	0	0	0
Apr-26	0	0	0	0	0
May-26	0	0	0	0	0
Jun-26	877	45970	0	2183	49031
Jul-26	-1146	9799	0	32	8686
Aug-26	-399	12963	0	43	12607
Sep-26	104	11311	0	12	11428
Oct-26	763	12391	0	0	13153
Nov-26	0	0	0	0	0
Dec-26	0	0	0	0	0
Jan-27	0	0	0	0	0
Feb-27	0	0	0	0	0
Mar-27	0	0	0	0	0
Apr-27	0	0	0	0	0
May-27	0	0	0	0	0
Jun-27	877	45970	0	2183	49031
Jul-27	-1146	9799	0	32	8686
Aug-27	-399	12963	0	43	12607
Sep-27	104	11311	0	12	11428
Oct-27	763	12391	0	0	13153
Nov-27	0	0	0	0	0
Dec-27	0	0	0	0	0
Jan-28	0	0	0	0	0

Water Balance for P Area					
Date	Inflow			Outflow	
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Pumped to CP5	Water Seepage into CP5
	m ³	m ³	m ³		m ³
May-20	0	0	0	0	0
Jun-20	3294	6289	1398	8479	0
Jul-20	-2711	1341	1173	10217	0
Aug-20	-944	1773	1276	2107	0
Sep-20	205	1547	1123	2875	0
Oct-20	987	1695	1489	4092	0
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	0	0	0	0	0
Jul-21	0	0	0	0	0
Aug-21	0	0	0	0	0
Sep-21	0	0	0	0	0
Oct-21	0	0	0	0	0
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	0	0	0	0	0
Jul-22	0	0	0	0	0
Aug-22	0	0	0	0	0
Sep-22	0	0	0	0	0
Oct-22	0	0	0	0	0
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	0	0	0	0	0
Jul-23	0	0	0	0	0
Aug-23	0	0	0	0	0
Sep-23	0	0	0	0	0
Oct-23	0	0	0	0	0
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	877	45970	0	2183	49031
Jul-24	-1146	9799	0	32	8686
Aug-24	-399	12963	0	43	12607
Sep-24	104	11311	0	12	11428
Oct-24	763	12391	0	0	13153
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0

Water Balance for CP6					
Date	Inflow				Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Net Runoff/Seepage Water from WRSF3 and WRSF3 Exten.	Water Pumped from CP6 to CP1
	m ³	m ³	m ³	m ³	m ³
Feb-28	0	0	0	0	0
Mar-28	0	0	0	0	0
Apr-28	0	0	0	0	0
May-28	0	0	0	0	0
Jun-28	877	12029	202	2779	15887
Jul-28	-1146	2564	67	41	1526
Aug-28	-399	3392	73	55	3120
Sep-28	104	2960	54	16	3134
Oct-28	763	3242	54	0	4059
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

Water Balance for CP2					
Date	Inflow				Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Net Runoff/Seepage Water from WRSF3 and WRSF3 Exten.	Water Pumped from CP7 to CP1
	m3	m3	m3	m3	m3
Feb-28	0	0	0	0	0
Mar-28	0	0	0	0	0
Apr-28	0	0	0	0	0
May-28	0	0	0	0	0
Jun-28	877	45970	0	2183	49031
Jul-28	-1146	9799	0	32	8686
Aug-28	-399	12963	0	43	12607
Sep-28	104	11311	0	12	11428
Oct-28	763	12391	0	0	13153
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

Water Balance for P Area					
Date	Inflow			Outflow	
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Other Disturbed Ground	Pumped to CP5	Water Seepage into CP5
	m ³	m ³	m ³		m ³
Feb-28					
Mar-28					
Apr-28					
May-28					
Jun-28					
Jul-28					
Aug-28					
Sep-28					
Oct-28					
Nov-28					
Dec-28					

Water Balance for Landfarm				
Date	Inflow			Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Disturbed Ground Surface	Snow Melting	Pre-Treated (Oil) Water from Landfarm/Biopile to CP1 though site area ditch
	m ³	m ³	m ³	m ³
May-20	0	0	0	0
Jun-20	19	1672	500	2191
Jul-20	-25	551	0	525
Aug-20	-9	600	0	591
Sep-20	2	449	0	451
Oct-20	17	451	0	467
Nov-20	0	0	0	0
Dec-20	0	0	0	0
Jan-21	0	0	0	0
Feb-21	0	0	0	0
Mar-21	0	0	0	0
Apr-21	0	0	0	0
May-21	0	0	0	0
Jun-21	13	1117	500	1630
Jul-21	-17	368	0	351
Aug-21	-6	401	0	395
Sep-21	2	300	0	301
Oct-21	11	301	0	312
Nov-21	0	0	0	0
Dec-21	0	0	0	0
Jan-22	0	0	0	0
Feb-22	0	0	0	0
Mar-22	0	0	0	0
Apr-22	0	0	0	0
May-22	0	0	0	0
Jun-22	13	3510	500	4023
Jul-22	-17	1156	0	1139
Aug-22	-6	1260	0	1254
Sep-22	2	942	0	944
Oct-22	11	946	0	957
Nov-22	0	0	0	0
Dec-22	0	0	0	0
Jan-23	0	0	0	0
Feb-23	0	0	0	0
Mar-23	0	0	0	0
Apr-23	0	0	0	0
May-23	0	0	0	0
Jun-23	13	3510	500	4023
Jul-23	-17	1156	0	1139
Aug-23	-6	1260	0	1254
Sep-23	2	942	0	944
Oct-23	11	946	0	957
Nov-23	0	0	0	0
Dec-23	0	0	0	0
Jan-24	0	0	0	0
Feb-24	0	0	0	0
Mar-24	0	0	0	0
Apr-24	0	0	0	0

Water Balance for Landfill			
Date	Inflow		Outflow
	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Disturbed Ground Surface	Water from Landfill to CP1 though site area ditch
	m ³	m ³	m ³
May-20	0	0	0
Jun-20	0	2263	2263
Jul-20	0	745	745
Aug-20	0	812	812
Sep-20	0	607	607
Oct-20	0	610	610
Nov-20	0	0	0
Dec-20	0	0	0
Jan-21	0	0	0
Feb-21	0	0	0
Mar-21	0	0	0
Apr-21	0	0	0
May-21	0	0	0
Jun-21	0	1512	1512
Jul-21	0	498	498
Aug-21	0	543	543
Sep-21	0	406	406
Oct-21	0	407	407
Nov-21	0	0	0
Dec-21	0	0	0
Jan-22	0	0	0
Feb-22	0	0	0
Mar-22	0	0	0
Apr-22	0	0	0
May-22	0	0	0
Jun-22	0	1512	1512
Jul-22	0	498	498
Aug-22	0	543	543
Sep-22	0	406	406
Oct-22	0	407	407
Nov-22	0	0	0
Dec-22	0	0	0
Jan-23	0	0	0
Feb-23	0	0	0
Mar-23	0	0	0
Apr-23	0	0	0
May-23	0	0	0
Jun-23	0	1512	1512
Jul-23	0	498	498
Aug-23	0	543	543
Sep-23	0	406	406
Oct-23	0	407	407
Nov-23	0	0	0
Dec-23	0	0	0
Jan-24	0	0	0
Feb-24	0	0	0
Mar-24	0	0	0
Apr-24	0	0	0

Water Balance for Landfarm				
Date	Inflow			Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Disturbed Ground Surface	Snow Melting	Pre-Treated (Oil) Water from Landfarm/Biopile to CP1 though site area ditch
	m ³	m ³	m ³	m ³
May-24	0	0	0	0
Jun-24	13	3510	500	4023
Jul-24	-17	1156	0	1139
Aug-24	-6	1260	0	1254
Sep-24	2	942	0	944
Oct-24	11	946	0	957
Nov-24	0	0	0	0
Dec-24	0	0	0	0
Jan-25	0	0	0	0
Feb-25	0	0	0	0
Mar-25	0	0	0	0
Apr-25	0	0	0	0
May-25	0	0	0	0
Jun-25	19	5253	500	5773
Jul-25	-25	1730	0	1705
Aug-25	-9	1885	0	1877
Sep-25	2	1410	0	1412
Oct-25	17	1416	0	1433
Nov-25	0	0	0	0
Dec-25	0	0	0	0
Jan-26	0	0	0	0
Feb-26	0	0	0	0
Mar-26	0	0	0	0
Apr-26	0	0	0	0
May-26	0	0	0	0
Jun-26	13	3510	500	4023
Jul-26	-17	1156	0	1139
Aug-26	-6	1260	0	1254
Sep-26	2	942	0	944
Oct-26	11	946	0	957
Nov-26	0	0	0	0
Dec-26	0	0	0	0
Jan-27	0	0	0	0
Feb-27	0	0	0	0
Mar-27	0	0	0	0
Apr-27	0	0	0	0
May-27	0	0	0	0
Jun-27	13	3510	500	4023
Jul-27	-17	1156	0	1139
Aug-27	-6	1260	0	1254
Sep-27	2	942	0	944
Oct-27	11	946	0	957
Nov-27	0	0	0	0
Dec-27	0	0	0	0
Jan-28	0	0	0	0
Feb-28	0	0	0	0
Mar-28	0	0	0	0
Apr-28	0	0	0	0

Water Balance for Landfill			
Date	Inflow		Outflow
	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Disturbed Ground Surface	Water from Landfill to CP1 though site area ditch
	m ³	m ³	m ³
May-24	0	0	0
Jun-24	0	1512	1512
Jul-24	0	498	498
Aug-24	0	543	543
Sep-24	0	406	406
Oct-24	0	407	407
Nov-24	0	0	0
Dec-24	0	0	0
Jan-25	0	0	0
Feb-25	0	0	0
Mar-25	0	0	0
Apr-25	0	0	0
May-25	0	0	0
Jun-25	0	2263	2263
Jul-25	0	745	745
Aug-25	0	812	812
Sep-25	0	607	607
Oct-25	0	610	610
Nov-25	0	0	0
Dec-25	0	0	0
Jan-26	0	0	0
Feb-26	0	0	0
Mar-26	0	0	0
Apr-26	0	0	0
May-26	0	0	0
Jun-26	0	1512	1512
Jul-26	0	498	498
Aug-26	0	543	543
Sep-26	0	406	406
Oct-26	0	407	407
Nov-26	0	0	0
Dec-26	0	0	0
Jan-27	0	0	0
Feb-27	0	0	0
Mar-27	0	0	0
Apr-27	0	0	0
May-27	0	0	0
Jun-27	0	1512	1512
Jul-27	0	498	498
Aug-27	0	543	543
Sep-27	0	406	406
Oct-27	0	407	407
Nov-27	0	0	0
Dec-27	0	0	0
Jan-28	0	0	0
Feb-28	0	0	0
Mar-28	0	0	0
Apr-28	0	0	0

Water Balance for Landfarm				
Date	Inflow			Outflow
	Net Runoff/Runon Water from Pond Surface	Net Runoff/Runon Water from Disturbed Ground Surface	Snow Melting	Pre-Treated (Oil) Water from Landfarm/Biopile to CP1 through site area ditch
	m ³	m ³	m ³	m ³
May-28	0	0	0	0
Jun-28	13	3510	500	4023
Jul-28	-17	1156	0	1139
Aug-28	-6	1260	0	1254
Sep-28	2	942	0	944
Oct-28	11	946	0	957
Nov-28	0	0	0	0
Dec-28	0	0	0	0

Water Balance for Landfill			
Date	Inflow		Outflow
	Net Runoff/Runon Water from Natural Ground with Vegetation	Net Runoff/Runon Water from Disturbed Ground Surface	Water from Landfill to CP1 through site area ditch
	m ³	m ³	m ³
May-28	0	0	0
Jun-28	0	1512	1512
Jul-28	0	498	498
Aug-28	0	543	543
Sep-28	0	406	406
Oct-28	0	407	407
Nov-28	0	0	0
Dec-28	0	0	0

Water Balance for EWTP

Date	Inflow			Outflow	
	Water from CP1 to EWTP	Water from CP5 to EWTP	RO Premeate To EWTP	Water from EWTP to SP3	Discharge to Meliadine Lake
	m ³	m ³	m ³		m ³
May-20	0	0	0	0	0
Jun-20	330000	0	0	0	330000
Jul-20	558736	0	0	12000	546736
Aug-20	76202	0	0	24800	51402
Sep-20	116387	0	0	24000	92387
Oct-20	0	0	0	0	0
Nov-20	0	0	0	0	0
Dec-20	0	0	0	0	0
Jan-21	0	0	0	0	0
Feb-21	0	0	0	0	0
Mar-21	0	0	0	0	0
Apr-21	0	0	0	0	0
May-21	0	0	0	0	0
Jun-21	282879	0	0	0	282879
Jul-21	302927	0	0	12000	290927
Aug-21	50228	0	0	24800	25428
Sep-21	81626	0	0	24000	57626
Oct-21	0	0	0	0	0
Nov-21	0	0	0	0	0
Dec-21	0	0	0	0	0
Jan-22	0	0	0	0	0
Feb-22	0	0	0	0	0
Mar-22	0	0	0	0	0
Apr-22	0	0	0	0	0
May-22	0	0	0	0	0
Jun-22	201115	0	0	90000	111115
Jul-22	275162	0	0	186000	89162
Aug-22	45487	0	0	45487	0
Sep-22	76444	0	0	76444	0
Oct-22	0	0	0	0	0
Nov-22	0	0	0	0	0
Dec-22	0	0	0	0	0
Jan-23	0	0	0	0	0
Feb-23	0	0	0	0	0
Mar-23	0	0	0	0	0
Apr-23	0	0	0	0	0
May-23	0	0	0	0	0
Jun-23	191532	0	0	90000	101532
Jul-23	281612	0	0	186000	95612
Aug-23	47622	0	0	42142	5480
Sep-23	78770	0	0	27901	50869
Oct-23	0	0	0	0	0
Nov-23	0	0	0	0	0
Dec-23	0	0	0	0	0

Water Balance for EWTP

Date	Inflow			Outflow	
	Water from CP1 to EWTP	Water from CP5 to EWTP	RO Preemate To EWTP	Water from EWTP to SP3	Discharge to Meliadine Lake
	m ³	m ³	m ³		m ³
Jan-24	0	0	0	0	0
Feb-24	0	0	0	0	0
Mar-24	0	0	0	0	0
Apr-24	0	0	0	0	0
May-24	0	0	0	0	0
Jun-24	195151	0	0	90000	105151
Jul-24	316826	0	0	174490	142336
Aug-24	53041	0	0	29677	23364
Sep-24	88116	0	0	28245	59871
Oct-24	0	0	0	0	0
Nov-24	0	0	0	0	0
Dec-24	0	0	0	0	0
Jan-25	0	0	0	0	0
Feb-25	0	0	0	0	0
Mar-25	0	0	0	0	0
Apr-25	0	0	0	0	0
May-25	0	0	0	0	0
Jun-25	213039	0	0	90000	123039
Jul-25	485855	0	0	186000	299855
Aug-25	81608	0	0	51884	29724
Sep-25	134160	0	0	33193	100966
Oct-25	0	0	0	0	0
Nov-25	0	0	0	0	0
Dec-25	0	0	0	0	0
Jan-26	0	0	0	0	0
Feb-26	0	0	0	0	0
Mar-26	0	0	0	0	0
Apr-26	0	0	0	0	0
May-26	0	0	0	0	0
Jun-26	308893	0	0	90000	218893
Jul-26	326998	0	0	186000	140998
Aug-26	56087	0	0	55840	247
Sep-26	91190	0	0	31582	59608
Oct-26	0	0	0	0	0
Nov-26	0	0	0	0	0
Dec-26	0	0	0	0	0
Jan-27	0	0	0	0	0
Feb-27	0	0	0	0	0
Mar-27	0	0	0	0	0
Apr-27	0	0	0	0	0
May-27	0	0	0	0	0
Jun-27	219018	0	0	90000	129018
Jul-27	317767	0	0	186000	131767
Aug-27	48201	0	0	41804	6398

Water Balance for EWTP

Date	Inflow			Outflow	
	Water from CP1 to EWTP	Water from CP5 to EWTP	RO Premeate To EWTP	Water from EWTP to SP3	Discharge to Meliadine Lake
	m ³	m ³	m ³		m ³
Sep-27	81999	0	0	29927	52072
Oct-27	0	0	0	0	0
Nov-27	0	0	0	0	0
Dec-27	0	0	0	0	0
Jan-28	0	0	0	0	0
Feb-28	0	0	0	0	0
Mar-28	0	0	0	0	0
Apr-28	0	0	0	0	0
May-28	0	0	0	0	0
Jun-28	206520	0	0	206520	0
Jul-28	317767	0	0	317767	0
Aug-28	48201	0	0	48201	0
Sep-28	81999	0	0	81999	0
Oct-28	0	0	0	0	0
Nov-28	0	0	0	0	0
Dec-28	0	0	0	0	0

APPENDIX E

**Average Monthly Concentrations,
Wet Years Scenario**

Appendix E
Wet Years Scenario
CP2 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
Jun 2024	63	0.014	2.1	0.037	0.011	0.0012	0.00028	0.001	0.0037
Jul 2024	145	0.049	12	0.2	0.059	0.003	0.00046	0.0022	0.0082
Aug 2024	112	0.036	7.9	0.14	0.041	0.0023	0.00038	0.0017	0.0064
Sep 2024	113	0.036	8.2	0.14	0.042	0.0023	0.00038	0.0017	0.0065
Oct 2024	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Nov 2024	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Dec 2024	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Jan 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Feb 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Mar 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Apr 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
May 2025	92	0.027	5.6	0.096	0.029	0.0018	0.00034	0.0014	0.0054
Jun 2025	79	0.015	2.5	0.046	0.0137	0.0013	0.00029	0.00107	0.0039
Jul 2025	90	0.022	4.2	0.073	0.022	0.0016	0.00033	0.0013	0.0047
Aug 2025	90	0.023	4.6	0.081	0.025	0.0017	0.00034	0.0013	0.0049
Sep 2025	91	0.025	5.1	0.089	0.027	0.0018	0.00034	0.0014	0.005
Oct 2025	73	0.017	3.0	0.053	0.0162	0.0014	0.00031	0.00114	0.0041
Nov 2025	73	0.017	3.0	0.053	0.0162	0.0014	0.00031	0.00114	0.0041
Dec 2025	73	0.017	3.0	0.053	0.0162	0.0014	0.00031	0.00114	0.0041
Jan 2026	73	0.017	3.0	0.053	0.0162	0.0014	0.00031	0.00114	0.0041
Feb 2026	73	0.017	3.0	0.053	0.0162	0.0014	0.00031	0.00114	0.0041
Mar 2026	73	0.017	3.0	0.053	0.0162	0.0014	0.00031	0.00114	0.0041
Apr 2026	73	0.017	3.0	0.053	0.0162	0.0014	0.00031	0.00114	0.0041
May 2026	73	0.017	3.0	0.053	0.0162	0.0014	0.00031	0.00114	0.0041
Jun 2026	77	0.015	2.4	0.043	0.013	0.0013	0.00029	0.00105	0.0038
Jul 2026	92	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0048
Aug 2026	98	0.027	5.6	0.097	0.03	0.0018	0.00035	0.0014	0.0052
Sep 2026	102	0.03	6.5	0.11	0.034	0.002	0.00036	0.0015	0.0055
Oct 2026	85	0.022	4.4	0.078	0.024	0.0016	0.00032	0.0013	0.0047
Nov 2026	85	0.022	4.4	0.078	0.024	0.0016	0.00032	0.0013	0.0047
Dec 2026	85	0.022	4.4	0.078	0.024	0.0016	0.00032	0.0013	0.0047
Jan 2027	85	0.022	4.4	0.078	0.024	0.0016	0.00032	0.0013	0.0047
Feb 2027	85	0.022	4.4	0.078	0.024	0.0016	0.00032	0.0013	0.0047
Mar 2027	85	0.022	4.4	0.078	0.024	0.0016	0.00032	0.0013	0.0047
Apr 2027	85	0.022	4.4	0.078	0.024	0.0016	0.00032	0.0013	0.0047
May 2027	85	0.022	4.4	0.078	0.024	0.0016	0.00032	0.0013	0.0047
Jun 2027	81	0.017	2.9	0.052	0.016	0.0013	0.0003	0.0011	0.004
Jul 2027	95	0.024	5.0	0.086	0.026	0.0017	0.00033	0.0014	0.0049
Aug 2027	100	0.028	5.9	0.1	0.031	0.0019	0.00035	0.0015	0.0053
Sep 2027	104	0.031	6.7	0.12	0.035	0.002	0.00036	0.0015	0.0056
Oct 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Nov 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Dec 2027	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Jan 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Feb 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Mar 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Apr 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
May 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Jun 2028	81	0.017	3.0	0.053	0.016	0.0014	0.0003	0.0011	0.004
Jul 2028	95	0.024	5.0	0.087	0.026	0.0017	0.00034	0.0014	0.0049
Aug 2028	100	0.028	5.9	0.1	0.031	0.0019	0.00035	0.0015	0.0053
Sep 2028	104	0.031	6.7	0.12	0.035	0.002	0.00036	0.0016	0.0056
Oct 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Nov 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047
Dec 2028	86	0.023	4.6	0.08	0.024	0.0017	0.00033	0.0013	0.0047

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
CP3 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	854	0.18	4.6	0.016	0.06	0.0055	0.0011	0.022	0.027
Jun 2020	331	0.069	2.5	0.031	0.077	0.0024	0.00049	0.008	0.011
Jul 2020	263	0.055	3.2	0.067	0.153	0.00221	0.00045	0.0056	0.0091
Aug 2020	206	0.043	3.5	0.086	0.192	0.00199	0.00041	0.0039	0.0075
Sep 2020	185	0.039	4.0	0.106	0.234	0.00199	0.00041	0.003	0.007
Oct 2020	168	0.036	4.3	0.117	0.258	0.00197	0.00041	0.00242	0.0066
Nov 2020	168	0.036	4.3	0.117	0.26	0.002	0.00041	0.0024	0.0066
Dec 2020	168	0.036	4.3	0.12	0.26	0.002	0.00041	0.0024	0.0066
Jan 2021	168	0.036	4.3	0.12	0.26	0.002	0.00041	0.0024	0.0066
Feb 2021	168	0.036	4.3	0.12	0.26	0.002	0.00041	0.0024	0.0066
Mar 2021	168	0.036	4.3	0.12	0.26	0.002	0.00041	0.0024	0.0066
Apr 2021	168	0.036	4.3	0.12	0.26	0.002	0.00041	0.0024	0.0066
May 2021	168	0.036	4.3	0.12	0.3	0.002	0.00041	0.0024	0.0066
Jun 2021	108	0.024	3.0	0.08	0.18	0.0014	0.0003	0.0014	0.0053
Jul 2021	124	0.031	4.0	0.11	0.25	0.0017	0.00037	0.0015	0.0071
Aug 2021	131	0.034	4.5	0.13	0.28	0.0019	0.00041	0.0015	0.0081
Sep 2021	144	0.039	5.2	0.15	0.32	0.0022	0.00046	0.0016	0.0094
Oct 2021	152	0.042	5.6	0.16	0.35	0.0023	0.00049	0.0016	0.0102
Nov 2021	152	0.042	5.6	0.16	0.35	0.0023	0.00049	0.0016	0.0102
Dec 2021	152	0.042	5.6	0.16	0.35	0.0023	0.00049	0.0016	0.01
Jan 2022	152	0.042	5.6	0.16	0.35	0.0023	0.00049	0.0016	0.01
Feb 2022	152	0.042	5.6	0.16	0.35	0.0023	0.00049	0.0016	0.01
Mar 2022	152	0.042	5.6	0.16	0.35	0.0023	0.00049	0.0016	0.01
Apr 2022	152	0.042	5.6	0.16	0.35	0.0023	0.00049	0.0016	0.01
May 2022	152	0.042	5.6	0.16	0.4	0.0023	0.00049	0.0016	0.01
Jun 2022	100	0.026	3.6	0.1	0.21	0.0015	0.00033	0.0011	0.0065
Jul 2022	116	0.031	4.4	0.12	0.25	0.0018	0.00037	0.0012	0.0074
Aug 2022	123	0.033	4.8	0.13	0.27	0.0019	0.00038	0.0013	0.0078
Sep 2022	136	0.037	5.5	0.15	0.3	0.0021	0.00042	0.0014	0.0085
Oct 2022	144	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0014	0.009
Nov 2022	144	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0014	0.009
Dec 2022	144	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0014	0.009
Jan 2023	144	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0014	0.009
Feb 2023	144	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0014	0.009
Mar 2023	144	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0014	0.009
Apr 2023	144	0.039	5.9	0.16	0.32	0.0022	0.00044	0.0014	0.009
May 2023	144	0.039	5.9	0.16	0.3	0.0022	0.00044	0.0014	0.009
Jun 2023	96	0.026	3.7	0.1	0.21	0.0015	0.00032	0.001	0.0064
Jul 2023	114	0.032	4.5	0.12	0.26	0.0018	0.00038	0.0012	0.0079
Aug 2023	122	0.035	4.8	0.13	0.28	0.0019	0.00041	0.0012	0.0088
Sep 2023	136	0.039	5.4	0.15	0.32	0.0021	0.00045	0.0014	0.0099
Oct 2023	144	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Nov 2023	144	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Dec 2023	144	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Jan 2024	144	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Feb 2024	144	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Mar 2024	144	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
Apr 2024	144	0.042	5.8	0.16	0.35	0.0023	0.00048	0.0014	0.011
May 2024	144	0.042	5.8	0.16	0.3	0.0023	0.00048	0.0014	0.011
Jun 2024	99	0.025	3.7	0.1	0.21	0.0015	0.00032	0.001	0.0059
Jul 2024	121	0.027	4.6	0.12	0.26	0.0017	0.00035	0.0011	0.0055
Aug 2024	131	0.028	5.0	0.13	0.28	0.0018	0.00036	0.0012	0.0051
Sep 2024	147	0.03	5.7	0.15	0.31	0.002	0.00039	0.0013	0.005
Oct 2024	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Nov 2024	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Dec 2024	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Jan 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Feb 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Mar 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Apr 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
May 2025	158	0.031	6.1	0.16	0.33	0.0021	0.0004	0.0014	0.0049
Jun 2025	85	0.016	3.1	0.079	0.16	0.0012	0.00024	0.0008	0.0028
Jul 2025	99	0.019	3.7	0.094	0.189	0.00134	0.00026	0.00089	0.0028
Aug 2025	102	0.019	3.8	0.099	0.197	0.00139	0.00026	0.00091	0.0028
Sep 2025	113	0.021	4.3	0.11	0.218	0.00152	0.00028	0.001	0.003
Oct 2025	118	0.022	4.5	0.115	0.228	0.00159	0.0003	0.00104	0.0031
Nov 2025	118	0.022	4.5	0.115	0.23	0.0016	0.0003	0.00104	0.0031
Dec 2025	118	0.022	4.5	0.115	0.23	0.0016	0.0003	0.00104	0.0031
Jan 2026	118	0.022	4.5	0.11	0.23	0.0016	0.0003	0.001	0.0031
Feb 2026	118	0.022	4.5	0.11	0.23	0.0016	0.0003	0.001	0.0031
Mar 2026	118	0.022	4.5	0.11	0.23	0.0016	0.0003	0.001	0.0031
Apr 2026	118	0.022	4.5	0.11	0.23	0.0016	0.0003	0.001	0.0031
May 2026	118	0.022	4.5	0.11	0.23	0.0016	0.0003	0.001	0.0031
Jun 2026	88	0.016	3.2	0.08	0.16	0.0012	0.00024	0.0008	0.0024
Jul 2026	113	0.021	4.2	0.11	0.22	0.0015	0.00029	0.001	0.0029
Aug 2026	127	0.023	4.7	0.12	0.26	0.0017	0.00032	0.00108	0.0031
Sep 2026	145	0.026	5.5	0.14	0.3	0.0019	0.00036	0.0012	0.0035
Oct 2026	157	0.028	6.0	0.16	0.32	0.0021	0.00039	0.0013	0.0037
Nov 2026	157	0.028	6.0	0.16	0.32	0.0021	0.00039	0.0013	0.0037
Dec 2026	157	0.028	6.0	0.16	0.32	0.0021	0.00039	0.0013	0.0037
Jan 2027	157	0.028	6.0	0.16	0.32	0.0021	0.00039	0.0013	0.0037
Feb 2027	157	0.028	6.0	0.16	0.32	0.0021	0.00039	0.0013	0.0037
Mar 2027	157	0.028	6.0	0.16	0.32	0.0021	0.00039	0.0013	0.0037
Apr 2027	157	0.028	6.0	0.16	0.32	0.0021	0.00039	0.0013	0.0037
May 2027	157	0.028	6.0	0.16	0.3	0.0021	0.00039	0.0013	0.0037
Jun 2027	105	0.019	3.8	0.1	0.21	0.0014	0.00028	0.0009	0.0027
Jul 2027	126	0.023	4.7	0.12	0.26	0.0017	0.00032	0.0011	0.0031
Aug 2027	136	0.025	5.1	0.13	0.28	0.0018	0.00034	0.0011	0.0033
Sep 2027	152	0.027	5.8	0.15	0.32	0.002	0.00038	0.0013	0.0036
Oct 2027	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Nov 2027	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Dec 2027	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Jan 2028	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Feb 2028	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Mar 2028	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Apr 2028	162	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
May 2028	162	0.029	6.2	0.16	0.3	0.0021	0.0004	0.0013	0.0038
Jun 2028	108	0.019	3.9	0.1	0.21	0.0014	0.00028	0.0009	0.0028
Jul 2028	128	0.023	4.8	0.13	0.26	0.0017	0.00032	0.0011	0.0031
Aug 2028	137	0.025	5.1	0.14	0.28	0.0018	0.00034	0.0012	0.0033
Sep 2028	153	0.028	5.8	0.15	0.32	0.002	0.00038	0.0013	0.0036
Oct 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Nov 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038
Dec 2028	163	0.029	6.2	0.16	0.34	0.0021	0.0004	0.0013	0.0038

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
CP4 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	977	0.065	0.91	0.0064	0.0056	0.0029	0.00013	0.015	0.0033
Jun 2020	416	0.028	0.71	0.012	0.0039	0.0016	0.00023	0.0058	0.0035
Jul 2020	333	0.027	1.36	0.025	0.006	0.0016	0.00028	0.0046	0.0044
Aug 2020	248	0.025	1.7	0.031	0.0069	0.0015	0.0003	0.0034	0.0048
Sep 2020	188	0.023	1.9	0.036	0.0076	0.0015	0.00031	0.0027	0.0051
Oct 2020	141	0.017	1.25	0.025	0.0053	0.0013	0.0003	0.002	0.0044
Nov 2020	141	0.017	1.25	0.025	0.0053	0.0013	0.0003	0.002	0.0044
Dec 2020	141	0.017	1.25	0.025	0.0053	0.0013	0.0003	0.002	0.0044
Jan 2021	141	0.017	1.25	0.025	0.0053	0.0013	0.0003	0.002	0.0044
Feb 2021	141	0.017	1.25	0.025	0.0053	0.0013	0.0003	0.002	0.0044
Mar 2021	141	0.017	1.25	0.025	0.0053	0.0013	0.0003	0.002	0.0044
Apr 2021	141	0.017	1.25	0.025	0.0053	0.0013	0.0003	0.002	0.0044
May 2021	141	0.017	1.25	0.025	0.0053	0.0013	0.0003	0.002	0.0044
Jun 2021	115	0.019	1.5	0.031	0.0041	0.0013	0.00031	0.0015	0.0058
Jul 2021	116	0.029	2.9	0.055	0.0054	0.0016	0.00037	0.0017	0.0092
Aug 2021	111	0.036	3.8	0.071	0.0061	0.0018	0.0004	0.0017	0.011
Sep 2021	102	0.042	4.6	0.084	0.0067	0.002	0.00043	0.0018	0.013
Oct 2021	91	0.034	3.6	0.067	0.0054	0.0017	0.00039	0.0016	0.011
Nov 2021	91	0.034	3.6	0.067	0.0054	0.0017	0.00039	0.0016	0.011
Dec 2021	91	0.034	3.6	0.067	0.0054	0.0017	0.00039	0.0016	0.011
Jan 2022	91	0.034	3.6	0.067	0.0054	0.0017	0.00039	0.0016	0.011
Feb 2022	91	0.034	3.6	0.067	0.0054	0.0017	0.00039	0.0016	0.011
Mar 2022	91	0.034	3.6	0.067	0.0054	0.0017	0.00039	0.0016	0.011
Apr 2022	91	0.034	3.6	0.067	0.0054	0.0017	0.00039	0.0016	0.011
May 2022	91	0.034	3.6	0.067	0.0054	0.0017	0.00039	0.0016	0.011
Jun 2022	105	0.029	3.6	0.067	0.0099	0.0016	0.00037	0.0014	0.0088
Jul 2022	122	0.039	5.9	0.11	0.019	0.002	0.00042	0.0017	0.011
Aug 2022	131	0.046	7.4	0.13	0.026	0.0023	0.00045	0.0018	0.012
Sep 2022	133	0.052	8.8	0.16	0.032	0.0026	0.00047	0.002	0.013
Oct 2022	119	0.043	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Nov 2022	119	0.043	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Dec 2022	119	0.043	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Jan 2023	119	0.043	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Feb 2023	119	0.043	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Mar 2023	119	0.043	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Apr 2023	119	0.043	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
May 2023	119	0.043	7.2	0.13	0.027	0.0023	0.00044	0.0018	0.011
Jun 2023	146	0.033	5.6	0.1	0.023	0.0019	0.00039	0.0015	0.008
Jul 2023	159	0.040	7.7	0.14	0.035	0.0023	0.00042	0.0017	0.0085
Aug 2023	162	0.044	9.0	0.16	0.042	0.0025	0.00044	0.0019	0.0087
Sep 2023	161	0.048	10	0.18	0.049	0.0027	0.00045	0.002	0.0088
Oct 2023	141	0.040	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Nov 2023	141	0.040	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Dec 2023	141	0.040	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Jan 2024	141	0.040	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Feb 2024	141	0.040	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Mar 2024	141	0.040	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Apr 2024	141	0.040	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
May 2024	141	0.040	8.4	0.15	0.04	0.0024	0.00042	0.0018	0.0077
Jun 2024	171	0.031	6.2	0.11	0.031	0.0019	0.00038	0.0015	0.0062
Jul 2024	178	0.039	8.3	0.15	0.041	0.0023	0.00041	0.0017	0.007
Aug 2024	176	0.043	9.5	0.17	0.047	0.0025	0.00043	0.0019	0.0073
Sep 2024	171	0.047	11	0.19	0.053	0.0027	0.00045	0.002	0.0077
Oct 2024	149	0.040	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Nov 2024	149	0.040	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Dec 2024	149	0.040	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Jan 2025	149	0.040	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Feb 2025	149	0.040	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Mar 2025	149	0.040	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Apr 2025	149	0.040	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
May 2025	149	0.040	8.7	0.15	0.043	0.0024	0.00042	0.0018	0.0068
Jun 2025	176	0.026	5.2	0.095	0.027	0.0018	0.00036	0.0014	0.0052
Jul 2025	177	0.033	7.0	0.125	0.035	0.0021	0.0004	0.0016	0.006
Aug 2025	167	0.036	7.7	0.138	0.039	0.0022	0.00041	0.0017	0.0063
Sep 2025	156	0.039	8.5	0.15	0.043	0.0024	0.00042	0.0018	0.0065
Oct 2025	129	0.031	6.4	0.115	0.032	0.002	0.00038	0.0015	0.0056
Nov 2025	129	0.031	6.4	0.115	0.032	0.002	0.00038	0.0015	0.0056
Dec 2025	129	0.031	6.4	0.115	0.032	0.002	0.00038	0.0015	0.0056
Jan 2026	129	0.031	6.4	0.115	0.032	0.002	0.00038	0.0015	0.0056
Feb 2026	129	0.031	6.4	0.115	0.032	0.002	0.00038	0.0015	0.0056
Mar 2026	129	0.031	6.4	0.115	0.032	0.002	0.00038	0.0015	0.0056
Apr 2026	129	0.031	6.4	0.115	0.032	0.002	0.00038	0.0015	0.0056
May 2026	129	0.031	6.4	0.115	0.032	0.002	0.00038	0.0015	0.0056
Jun 2026	163	0.026	5.2	0.094	0.026	0.0017	0.00036	0.0014	0.005
Jul 2026	169	0.034	7.3	0.13	0.037	0.0021	0.0004	0.0016	0.006
Aug 2026	167	0.039	8.7	0.15	0.044	0.0024	0.00042	0.0018	0.0065
Sep 2026	163	0.044	9.9	0.17	0.05	0.0026	0.00043	0.0019	0.007
Oct 2026	142	0.037	8.1	0.14	0.041	0.0023	0.00041	0.0017	0.0062
Nov 2026	142	0.037	8.1	0.14	0.041	0.0023	0.00041	0.0017	0.0062
Dec 2026	142	0.037	8.1	0.14	0.041	0.0023	0.00041	0.0017	0.0062
Jan 2027	142	0.037	8.1	0.14	0.041	0.0023	0.00041	0.0017	0.0062
Feb 2027	142	0.037	8.1	0.14	0.041	0.0023	0.00041	0.0017	0.0062
Mar 2027	142	0.037	8.1	0.14	0.041	0.0023	0.00041	0.0017	0.0062
Apr 2027	142	0.037	8.1	0.14	0.041	0.0023	0.00041	0.0017	0.0062
May 2027	142	0.037	8.1	0.14	0.041	0.0023	0.00041	0.0017	0.0062
Jun 2027	170	0.029	6.1	0.11	0.031	0.0019	0.00037	0.0015	0.0054
Jul 2027	175	0.037	8.1	0.15	0.041	0.0023	0.00041	0.0017	0.0062
Aug 2027	171	0.042	9.4	0.17	0.047	0.0025	0.00043	0.0018	0.0067
Sep 2027	167	0.046	10	0.18	0.053	0.0027	0.00044	0.002	0.0072
Oct 2027	145	0.039	8.6	0.15	0.044	0.0024	0.00041	0.0017	0.0064
Nov 2027	145	0.039	8.6	0.15	0.044	0.0024	0.00041	0.0017	0.0064
Dec 2027	145	0.039	8.6	0.15	0.044	0.0024	0.00041	0.0017	0.0064
Jan 2028	145	0.039	8.6	0.15	0.044	0.0024	0.00041	0.0017	0.0064
Feb 2028	145	0.039	8.6	0.15	0.044	0.0024	0.00041	0.0017	0.0064
Mar 2028	145	0.039	8.6	0.15	0.044	0.0024	0.00041	0.0017	0.0064
Apr 2028	145	0.039	8.6	0.15	0.044	0.0024	0.00041	0.0017	0.0064
May 2028	145	0.039	8.6	0.15	0.044	0.0024	0.00041	0.0017	0.0064
Jun 2028	171	0.030	6.4	0.11	0.033	0.002	0.00037	0.0015	0.0054
Jul 2028	175	0.038	8.4	0.15	0.042	0.0023	0.00041	0.0017	0.0063
Aug 2028	171	0.043	9.6	0.17	0.048	0.0025	0.00043	0.0019	0.0068
Sep 2028	167	0.047	11	0.19	0.054	0.0027	0.00044	0.002	0.0072
Oct 2028	145	0.040	8.7	0.15	0.044	0.0024	0.00041	0.0018	0.0065
Nov 2028	145	0.040	8.7	0.15	0.044	0.0024	0.00041	0.0018	0.0065
Dec 2028	145	0.040	8.7	0.15	0.044	0.0024	0.00041	0.0018	0.0065

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
CP5 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	7153	18	0.025	0.0043	0.0067	0.0017	0.038	0.042
Jun 2020	1707	6.0	0.024	0.0025	0.0021	0.0007	0.0088	0.0125
Jul 2020	2010	8.7	0.064	0.005	0.0022	0.00105	0.0081	0.015
Aug 2020	1277	6.2	0.068	0.0052	0.0017	0.00088	0.0043	0.0102
Sep 2020	700	4.5	0.065	0.005	0.0014	0.00075	0.0026	0.0076
Oct 2020	404	3.3	0.057	0.0038	0.00107	0.00065	0.0017	0.0057
Nov 2020	404	3.3	0.057	0.0038	0.00107	0.00065	0.0017	0.0057
Dec 2020	404	3.3	0.057	0.0038	0.00107	0.00065	0.0017	0.0057
Jan 2021	404	3.3	0.057	0.0038	0.00107	0.00065	0.0017	0.0057
Feb 2021	404	3.3	0.057	0.0038	0.00107	0.00065	0.0017	0.0057
Mar 2021	404	3.3	0.057	0.0038	0.00107	0.00065	0.0017	0.0057
Apr 2021	404	3.3	0.057	0.0038	0.00107	0.00065	0.0017	0.0057
May 2021	404	3.3	0.057	0.0038	0.00107	0.00065	0.0017	0.0057
Jun 2021	342	4.9	0.082	0.0051	0.00095	0.00082	0.0014	0.0059
Jul 2021	822	6.7	0.13	0.011	0.0013	0.0011	0.0018	0.0085
Aug 2021	884	6.7	0.13	0.012	0.0013	0.0011	0.0018	0.0086
Sep 2021	578	6.4	0.13	0.013	0.0013	0.001	0.0017	0.0086
Oct 2021	402	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Nov 2021	402	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Dec 2021	402	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Jan 2022	402	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Feb 2022	402	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Mar 2022	402	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Apr 2022	402	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
May 2022	402	5.5	0.12	0.012	0.0012	0.0009	0.0015	0.0074
Jun 2022	328	3.2	0.1	0.0069	0.0011	0.0010	0.0016	0.0069
Jul 2022	644	5.4	0.14	0.013	0.0014	0.0012	0.0019	0.0087
Aug 2022	674	5.9	0.14	0.013	0.0014	0.0011	0.0019	0.0085
Sep 2022	465	5.7	0.13	0.014	0.0014	0.001	0.0018	0.0083
Oct 2022	326	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Nov 2022	326	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Dec 2022	326	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Jan 2023	326	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Feb 2023	326	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Mar 2023	326	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Apr 2023	326	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
May 2023	326	4.7	0.11	0.011	0.0012	0.00091	0.0016	0.0071
Jun 2023	243	3.9	0.097	0.0072	0.001	0.00092	0.0015	0.0063
Jul 2023	458	6.2	0.13	0.014	0.0013	0.0011	0.0018	0.0079
Aug 2023	472	6.7	0.13	0.015	0.0013	0.0010	0.0017	0.0077
Sep 2023	323	6.4	0.13	0.016	0.0014	0.00093	0.0017	0.0075
Oct 2023	229	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Nov 2023	229	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Dec 2023	229	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Jan 2024	229	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Feb 2024	229	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Mar 2024	229	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Apr 2024	229	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
May 2024	229	5.4	0.11	0.013	0.0012	0.00083	0.0015	0.0067
Jun 2024	227	2.0	0.11	0.0076	0.0012	0.0011	0.0017	0.0072
Jul 2024	413	4.4	0.15	0.013	0.0015	0.0013	0.002	0.0088
Aug 2024	425	5.2	0.15	0.014	0.0014	0.0012	0.0019	0.0084
Sep 2024	308	4.9	0.14	0.015	0.0014	0.0011	0.0019	0.0081
Oct 2024	222	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Nov 2024	222	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Dec 2024	222	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Jan 2025	222	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Feb 2025	222	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Mar 2025	222	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Apr 2025	222	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
May 2025	222	3.9	0.12	0.011	0.0012	0.00099	0.0016	0.0071
Jun 2025	176	2.8	0.106	0.0062	0.00107	0.00108	0.0017	0.0069
Jul 2025	339	5.9	0.14	0.0116	0.0013	0.0012	0.0019	0.0083
Aug 2025	327	6.3	0.13	0.0116	0.0012	0.0011	0.0018	0.0076
Sep 2025	206	5.8	0.12	0.012	0.0012	0.00102	0.0017	0.0073
Oct 2025	143	4.8	0.104	0.0092	0.00106	0.00089	0.0015	0.0064
Nov 2025	143	4.8	0.104	0.0092	0.00106	0.00089	0.0015	0.0064
Dec 2025	143	4.8	0.104	0.0092	0.00106	0.00089	0.0015	0.0064
Jan 2026	143	4.8	0.104	0.0092	0.00106	0.00089	0.0015	0.0064
Feb 2026	143	4.8	0.104	0.0092	0.00106	0.00089	0.0015	0.0064
Mar 2026	143	4.8	0.104	0.0092	0.00106	0.00089	0.0015	0.0064
Apr 2026	143	4.8	0.104	0.0092	0.00106	0.00089	0.0015	0.0064
May 2026	143	4.8	0.104	0.0092	0.00106	0.00089	0.0015	0.0064
Jun 2026	138	3.3	0.11	0.0068	0.0011	0.001	0.0016	0.0067
Jul 2026	244	5.8	0.14	0.014	0.0014	0.0012	0.0019	0.0084
Aug 2026	250	6.4	0.14	0.015	0.0014	0.0011	0.0018	0.0081
Sep 2026	180	6.1	0.14	0.016	0.0014	0.001	0.0018	0.0079
Oct 2026	133	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Nov 2026	133	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Dec 2026	133	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Jan 2027	133	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Feb 2027	133	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Mar 2027	133	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Apr 2027	133	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
May 2027	133	5.1	0.12	0.013	0.0012	0.00092	0.0016	0.0071
Jun 2027	133	1.9	0.12	0.0077	0.0012	0.0012	0.0018	0.0076
Jul 2027	260	2.4	0.17	0.012	0.0016	0.0016	0.0025	0.01
Aug 2027	290	2.2	0.18	0.012	0.0016	0.0017	0.0025	0.01
Sep 2027	222	2.1	0.17	0.012	0.0015	0.0016	0.0024	0.0098
Oct 2027	164	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Nov 2027	164	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Dec 2027	164	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Jan 2028	164	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Feb 2028	164	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Mar 2028	164	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Apr 2028	164	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
May 2028	164	1.3	0.14	0.0082	0.0013	0.0014	0.0021	0.0085
Jun 2028	126	0.93	0.13	0.0065	0.0012	0.0013	0.002	0.008
Jul 2028	219	1.7	0.18	0.011	0.0016	0.0017	0.0026	0.01
Aug 2028	237	1.8	0.18	0.012	0.0016	0.0018	0.0026	0.011
Sep 2028	183	1.9	0.17	0.012	0.0015	0.0016	0.0024	0.0099
Oct 2028	135	1.2	0.14	0.008	0.0013	0.0014	0.0021	0.0085
Nov 2028	135	1.2	0.14	0.008	0.0013	0.0014	0.0021	0.0085
Dec 2028	135	1.2	0.14	0.008	0.0013	0.0014	0.0021	0.0085

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
CP6 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	977	0.065	0.91	0.0064	0.0056	0.0029	0.00013	0.015	0.0033
Jun 2020	555	0.048	3.0	0.049	0.0145	0.0023	0.00021	0.0087	0.0048
Jul 2020	551	0.065	7.2	0.121	0.033	0.0031	0.0003	0.0087	0.0082
Aug 2020	507	0.074	10.2	0.17	0.046	0.0036	0.00037	0.0081	0.0106
Sep 2020	468	0.082	13	0.22	0.057	0.004	0.00042	0.0075	0.013
Oct 2020	389	0.068	10.4	0.18	0.047	0.0034	0.00039	0.0062	0.0108
Nov 2020	389	0.068	10.4	0.18	0.047	0.0034	0.00039	0.0062	0.0108
Dec 2020	389	0.068	10.4	0.18	0.047	0.0034	0.00039	0.0062	0.0108
Jan 2021	389	0.068	10.4	0.18	0.047	0.0034	0.00039	0.0062	0.0108
Feb 2021	389	0.068	10.4	0.18	0.047	0.0034	0.00039	0.0062	0.0108
Mar 2021	389	0.068	10.4	0.18	0.047	0.0034	0.00039	0.0062	0.0108
Apr 2021	389	0.068	10.4	0.18	0.047	0.0034	0.00039	0.0062	0.0108
May 2021	389	0.068	10.4	0.18	0.047	0.0034	0.00039	0.0062	0.0108
Jun 2021	285	0.056	9.6	0.17	0.046	0.003	0.00036	0.0045	0.0089
Jul 2021	312	0.071	14	0.24	0.068	0.0038	0.00043	0.0049	0.0106
Aug 2021	321	0.080	17	0.29	0.083	0.0043	0.00048	0.005	0.012
Sep 2021	329	0.089	19	0.34	0.098	0.0048	0.00051	0.0051	0.013
Oct 2021	291	0.078	17	0.3	0.085	0.0043	0.00047	0.0045	0.011
Nov 2021	291	0.078	17	0.3	0.085	0.0043	0.00047	0.0045	0.011
Dec 2021	291	0.078	17	0.3	0.085	0.0043	0.00047	0.0045	0.011
Jan 2022	291	0.078	17	0.3	0.085	0.0043	0.00047	0.0045	0.011
Feb 2022	291	0.078	17	0.3	0.085	0.0043	0.00047	0.0045	0.011
Mar 2022	291	0.078	17	0.3	0.085	0.0043	0.00047	0.0045	0.011
Apr 2022	291	0.078	17	0.3	0.085	0.0043	0.00047	0.0045	0.011
May 2022	291	0.078	17	0.3	0.085	0.0043	0.00047	0.0045	0.011
Jun 2022	205	0.070	13	0.23	0.058	0.0035	0.00046	0.0034	0.014
Jul 2022	211	0.096	17	0.29	0.061	0.0043	0.00058	0.0039	0.022
Aug 2022	206	0.11	19	0.33	0.061	0.0048	0.00066	0.0041	0.028
Sep 2022	201	0.13	21	0.36	0.061	0.0053	0.00073	0.0043	0.034
Oct 2022	180	0.11	18	0.31	0.053	0.0047	0.00066	0.0039	0.03
Nov 2022	180	0.11	18	0.31	0.053	0.0047	0.00066	0.0039	0.03
Dec 2022	180	0.11	18	0.31	0.053	0.0047	0.00066	0.0039	0.03
Jan 2023	180	0.11	18	0.31	0.053	0.0047	0.00066	0.0039	0.03
Feb 2023	180	0.11	18	0.31	0.053	0.0047	0.00066	0.0039	0.03
Mar 2023	180	0.11	18	0.31	0.053	0.0047	0.00066	0.0039	0.03
Apr 2023	180	0.11	18	0.31	0.053	0.0047	0.00066	0.0039	0.03
May 2023	180	0.11	18	0.31	0.053	0.0047	0.00066	0.0039	0.03
Jun 2023	131	0.10	14	0.24	0.035	0.0038	0.00059	0.0031	0.027
Jul 2023	134	0.12	17	0.3	0.035	0.0046	0.00071	0.0036	0.036
Aug 2023	131	0.14	19	0.33	0.033	0.0051	0.0008	0.0038	0.043
Sep 2023	128	0.16	21	0.36	0.031	0.0055	0.00087	0.0041	0.048
Oct 2023	116	0.14	18	0.32	0.027	0.0049	0.00079	0.0036	0.042
Nov 2023	116	0.14	18	0.32	0.027	0.0049	0.00079	0.0036	0.042
Dec 2023	116	0.14	18	0.32	0.027	0.0049	0.00079	0.0036	0.042
Jan 2024	116	0.14	18	0.32	0.027	0.0049	0.00079	0.0036	0.042
Feb 2024	116	0.14	18	0.32	0.027	0.0049	0.00079	0.0036	0.042
Mar 2024	116	0.14	18	0.32	0.027	0.0049	0.00079	0.0036	0.042
Apr 2024	116	0.14	18	0.32	0.027	0.0049	0.00079	0.0036	0.042
May 2024	116	0.14	18	0.32	0.027	0.0049	0.00079	0.0036	0.042
Jun 2024	115	0.10	14	0.25	0.033	0.0039	0.00064	0.0029	0.029
Jul 2024	154	0.11	18	0.32	0.054	0.0045	0.0007	0.0033	0.029
Aug 2024	183	0.12	21	0.36	0.07	0.0048	0.00073	0.0035	0.029
Sep 2024	203	0.12	23	0.39	0.084	0.0051	0.00074	0.0037	0.028
Oct 2024	183	0.10	20	0.34	0.073	0.0046	0.00068	0.0033	0.024
Nov 2024	183	0.10	20	0.34	0.073	0.0046	0.00068	0.0033	0.024
Dec 2024	183	0.10	20	0.34	0.073	0.0046	0.00068	0.0033	0.024
Jan 2025	183	0.10	20	0.34	0.073	0.0046	0.00068	0.0033	0.024
Feb 2025	183	0.10	20	0.34	0.073	0.0046	0.00068	0.0033	0.024
Mar 2025	183	0.10	20	0.34	0.073	0.0046	0.00068	0.0033	0.024
Apr 2025	183	0.10	20	0.34	0.073	0.0046	0.00068	0.0033	0.024
May 2025	183	0.10	20	0.34	0.073	0.0046	0.00068	0.0033	0.024
Jun 2025	169	0.067	13.0	0.23	0.052	0.0032	0.00053	0.0024	0.015
Jul 2025	202	0.079	16	0.29	0.07	0.0038	0.0006	0.0028	0.016
Aug 2025	217	0.083	18	0.31	0.081	0.0041	0.00062	0.0029	0.016
Sep 2025	223	0.086	19	0.34	0.089	0.0043	0.00063	0.0031	0.015
Oct 2025	191	0.071	15.8	0.28	0.073	0.0036	0.00057	0.0026	0.0131
Nov 2025	191	0.071	15.8	0.28	0.073	0.0036	0.00057	0.0026	0.0131
Dec 2025	191	0.071	15.8	0.28	0.073	0.0036	0.00057	0.0026	0.0131
Jan 2026	191	0.071	15.8	0.28	0.073	0.0036	0.00057	0.0026	0.0131
Feb 2026	191	0.071	15.8	0.28	0.073	0.0036	0.00057	0.0026	0.0131
Mar 2026	191	0.071	15.8	0.28	0.073	0.0036	0.00057	0.0026	0.0131
Apr 2026	191	0.071	15.8	0.28	0.073	0.0036	0.00057	0.0026	0.0131
May 2026	191	0.071	15.8	0.28	0.073	0.0036	0.00057	0.0026	0.0131
Jun 2026	183	0.057	12.9	0.23	0.061	0.003	0.0005	0.0022	0.0103
Jul 2026	214	0.071	17	0.29	0.081	0.0037	0.00057	0.0027	0.0118
Aug 2026	232	0.080	19	0.33	0.095	0.0042	0.00061	0.003	0.013
Sep 2026	245	0.087	21	0.37	0.106	0.0045	0.00063	0.0032	0.013
Oct 2026	219	0.077	19	0.32	0.093	0.004	0.00059	0.0029	0.0118
Nov 2026	219	0.077	19	0.32	0.093	0.004	0.00059	0.0029	0.0118
Dec 2026	219	0.077	19	0.32	0.093	0.004	0.00059	0.0029	0.0118
Jan 2027	219	0.077	19	0.32	0.093	0.004	0.00059	0.0029	0.0118
Feb 2027	219	0.077	19	0.32	0.093	0.004	0.00059	0.0029	0.0118
Mar 2027	219	0.077	19	0.32	0.093	0.004	0.00059	0.0029	0.0118
Apr 2027	219	0.077	19	0.32	0.093	0.004	0.00059	0.0029	0.0118
May 2027	219	0.077	19	0.32	0.093	0.004	0.00059	0.0029	0.0118
Jun 2027	200	0.061	15	0.26	0.074	0.0033	0.00051	0.0024	0.0095
Jul 2027	229	0.074	18	0.32	0.093	0.004	0.00058	0.0028	0.011
Aug 2027	245	0.083	21	0.36	0.105	0.0044	0.00062	0.0031	0.012
Sep 2027	256	0.090	23	0.4	0.12	0.0047	0.00064	0.0033	0.012
Oct 2027	228	0.079	20	0.34	0.101	0.0042	0.0006	0.003	0.011
Nov 2027	228	0.079	20	0.34	0.101	0.0042	0.0006	0.003	0.011
Dec 2027	228	0.079	20	0.34	0.101	0.0042	0.0006	0.003	0.011
Jan 2028	228	0.079	20	0.34	0.101	0.0042	0.0006	0.003	0.011
Feb 2028	228	0.079	20	0.34	0.101	0.0042	0.0006	0.003	0.011
Mar 2028	228	0.079	20	0.34	0.101	0.0042	0.0006	0.003	0.011
Apr 2028	228	0.079	20	0.34	0.101	0.0042	0.0006	0.003	0.011
May 2028	228	0.079	20	0.34	0.101	0.0042	0.0006	0.003	0.011
Jun 2028	205	0.062	15	0.27	0.079	0.0034	0.00052	0.0025	0.0092
Jul 2028	234	0.076	19	0.33	0.097	0.0041	0.00058	0.0029	0.011
Aug 2028	248	0.084	21	0.37	0.11	0.0045	0.00062	0.0032	0.012
Sep 2028	259	0.091	23	0.4	0.12	0.0048	0.00065	0.0034	0.012
Oct 2028	230	0.080	20	0.35	0.1	0.0043	0.0006	0.003	0.011
Nov 2028	230	0.080	20	0.35	0.1	0.0043	0.0006	0.003	0.011
Dec 2028	230	0.080	20	0.35	0.1	0.0043	0.0006	0.003	0.011

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
P-Area Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	10950	36	0.03	0.0059	0.0047	0.002	0.028	0.05
Jun 2020	3060	15	0.059	0.0042	0.0024	0.0014	0.0125	0.024
Jul 2020	4169	16	0.13	0.0065	0.0029	0.0021	0.0137	0.028
Aug 2020	4923	1.4	0.38	0.012	0.0022	0.0038	0.0049	0.02
Sep 2020	1116	0.91	0.24	0.0078	0.0014	0.0024	0.0031	0.013
Oct 2020	982	0.8	0.21	0.0068	0.0012	0.0021	0.0027	0.011

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
Tiri-1 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	-	-	-	-	-	-	-	-	-
Jun 2020	-	-	-	-	-	-	-	-	-
Jul 2020	-	-	-	-	-	-	-	-	-
Aug 2020	-	-	-	-	-	-	-	-	-
Sep 2020	-	-	-	-	-	-	-	-	-
Oct 2020	-	-	-	-	-	-	-	-	-
Nov 2020	-	-	-	-	-	-	-	-	-
Dec 2020	-	-	-	-	-	-	-	-	-
Jan 2021	-	-	-	-	-	-	-	-	-
Feb 2021	-	-	-	-	-	-	-	-	-
Mar 2021	-	-	-	-	-	-	-	-	-
Apr 2021	-	-	-	-	-	-	-	-	-
May 2021	-	-	-	-	-	-	-	-	-
Jun 2021	21	0.0083	13	0.028	0.0067	0.00047	0.000082	0.00035	0.0019
Jul 2021	42	0.024	13	0.09	0.021	0.0011	0.00013	0.0007	0.0047
Aug 2021	39	0.021	13	0.08	0.019	0.001	0.00012	0.00066	0.0043
Sep 2021	50	0.028	13	0.1	0.025	0.0013	0.00015	0.00083	0.0055
Oct 2021	50	0.027	13	0.1	0.024	0.0013	0.00015	0.00083	0.0054
Nov 2021	-	-	-	-	-	-	-	-	-
Dec 2021	-	-	-	-	-	-	-	-	-
Jan 2022	-	-	-	-	-	-	-	-	-
Feb 2022	-	-	-	-	-	-	-	-	-
Mar 2022	-	-	-	-	-	-	-	-	-
Apr 2022	-	-	-	-	-	-	-	-	-
May 2022	-	-	-	-	-	-	-	-	-
Jun 2022	21	0.0083	13	0.028	0.0067	0.00047	0.000082	0.00035	0.0019
Jul 2022	42	0.024	13	0.09	0.021	0.0011	0.00013	0.0007	0.0047
Aug 2022	39	0.021	13	0.08	0.019	0.001	0.00012	0.00066	0.0043
Sep 2022	50	0.028	13	0.1	0.025	0.0013	0.00015	0.00083	0.0055
Oct 2022	50	0.027	13	0.1	0.024	0.0013	0.00015	0.00083	0.0054
Nov 2022	-	-	-	-	-	-	-	-	-
Dec 2022	-	-	-	-	-	-	-	-	-
Jan 2023	-	-	-	-	-	-	-	-	-
Feb 2023	-	-	-	-	-	-	-	-	-
Mar 2023	-	-	-	-	-	-	-	-	-
Apr 2023	-	-	-	-	-	-	-	-	-
May 2023	-	-	-	-	-	-	-	-	-
Jun 2023	19	0.0084	13	0.029	0.0069	0.00045	0.000073	0.00032	0.0019
Jul 2023	42	0.024	13	0.092	0.022	0.0011	0.00012	0.00069	0.0047
Aug 2023	39	0.022	13	0.083	0.02	0.001	0.00012	0.00065	0.0043
Sep 2023	50	0.029	13	0.11	0.026	0.0013	0.00015	0.00083	0.0056
Oct 2023	50	0.028	13	0.11	0.025	0.0013	0.00015	0.00083	0.0055
Nov 2023	-	-	-	-	-	-	-	-	-
Dec 2023	-	-	-	-	-	-	-	-	-
Jan 2024	-	-	-	-	-	-	-	-	-
Feb 2024	-	-	-	-	-	-	-	-	-
Mar 2024	-	-	-	-	-	-	-	-	-
Apr 2024	-	-	-	-	-	-	-	-	-
May 2024	-	-	-	-	-	-	-	-	-
Jun 2024	19	0.0084	13	0.029	0.0069	0.00045	0.000073	0.00032	0.0019
Jul 2024	42	0.024	13	0.092	0.022	0.0011	0.00012	0.00069	0.0047
Aug 2024	39	0.022	13	0.083	0.02	0.001	0.00012	0.00065	0.0043
Sep 2024	50	0.029	13	0.11	0.026	0.0013	0.00015	0.00083	0.0056
Oct 2024	50	0.028	13	0.11	0.025	0.0013	0.00015	0.00083	0.0055
Nov 2024	-	-	-	-	-	-	-	-	-
Dec 2024	-	-	-	-	-	-	-	-	-
Jan 2025	-	-	-	-	-	-	-	-	-
Feb 2025	-	-	-	-	-	-	-	-	-
Mar 2025	-	-	-	-	-	-	-	-	-
Apr 2025	-	-	-	-	-	-	-	-	-
May 2025	-	-	-	-	-	-	-	-	-
Jun 2025	16	0.006	13	0.0197	0.0047	0.00035	0.000064	0.00026	0.00141
Jul 2025	30	0.017	13	0.062	0.0147	0.00076	0.000091	0.00049	0.0033
Aug 2025	28	0.015	13	0.056	0.0132	0.00071	0.00009	0.00047	0.003
Sep 2025	36	0.019	13	0.073	0.017	0.00091	0.000112	0.0006	0.0039
Oct 2025	36	0.019	13	0.071	0.017	0.00091	0.000114	0.0006	0.0039
Nov 2025	-	-	-	-	-	-	-	-	-
Dec 2025	-	-	-	-	-	-	-	-	-
Jan 2026	-	-	-	-	-	-	-	-	-
Feb 2026	-	-	-	-	-	-	-	-	-
Mar 2026	-	-	-	-	-	-	-	-	-
Apr 2026	-	-	-	-	-	-	-	-	-
May 2026	-	-	-	-	-	-	-	-	-
Jun 2026	19	0.0084	13	0.029	0.0069	0.00045	0.000073	0.00032	0.0019
Jul 2026	42	0.024	13	0.092	0.022	0.0011	0.00012	0.00069	0.0047
Aug 2026	39	0.022	13	0.083	0.02	0.001	0.00012	0.00065	0.0043
Sep 2026	50	0.029	13	0.11	0.026	0.0013	0.00015	0.00083	0.0056
Oct 2026	50	0.028	13	0.11	0.025	0.0013	0.00015	0.00083	0.0055
Nov 2026	-	-	-	-	-	-	-	-	-
Dec 2026	-	-	-	-	-	-	-	-	-
Jan 2027	-	-	-	-	-	-	-	-	-
Feb 2027	-	-	-	-	-	-	-	-	-
Mar 2027	-	-	-	-	-	-	-	-	-
Apr 2027	-	-	-	-	-	-	-	-	-
May 2027	-	-	-	-	-	-	-	-	-
Jun 2027	19	0.0084	13	0.029	0.0069	0.00045	0.000073	0.00032	0.0019
Jul 2027	25	0.012	13	0.044	0.01	0.00061	0.000085	0.00041	0.0025
Aug 2027	27	0.013	13	0.049	0.012	0.00066	0.000089	0.00044	0.0028
Sep 2027	28	0.014	13	0.053	0.013	0.0007	0.000092	0.00047	0.0029
Oct 2027	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
Nov 2027	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
Dec 2027	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
Jan 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
Feb 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
Mar 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
Apr 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
May 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
Jun 2028	28	0.015	13	0.054	0.013	0.00071	0.000094	0.00047	0.003
Jul 2028	29	0.015	13	0.054	0.013	0.00071	0.000094	0.00048	0.003
Aug 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.003
Sep 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.0031
Oct 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.0031
Nov 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.0031
Dec 2028	29	0.015	13	0.055	0.013	0.00072	0.000095	0.00048	0.0031

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
Tiri-2 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	-	-	-	-	-	-	-	-	-
Jun 2020	34	0.0085	13	0.017	0.0027	0.0007	0.00017	0.00057	0.0026
Jul 2020	43	0.021	13	0.06	0.009	0.0011	0.00019	0.0007	0.0047
Aug 2020	42	0.018	13	0.05	0.007	0.0011	0.00019	0.0007	0.004
Sep 2020	48	0.022	13	0.06	0.009	0.0012	0.00021	0.0008	0.005
Oct 2020	45	0.019	13	0.05	0.006	0.0011	0.00021	0.0008	0.005

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
CP1 Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	1293	0.08	4	0.004	0.0019	0.0008	0.00023	0.004	0.009
Jun 2020	1175	0.082	3.5	0.052	0.012	0.0012	0.0007	0.0043	0.009
Jul 2020	1402	0.11	3.7	0.071	0.021	0.0013	0.0008	0.0045	0.01
Aug 2020	1628	0.16	3.6	0.11	0.037	0.0015	0.0011	0.0043	0.011
Sep 2020	1406	0.19	3.5	0.12	0.049	0.0015	0.0012	0.004	0.01
Oct 2020	1151	0.2	3.2	0.12	0.054	0.0015	0.0011	0.0035	0.01
Nov 2020	1146	0.25	3.2	0.12	0.053	0.0015	0.0011	0.0034	0.01
Dec 2020	1142	0.31	3.2	0.12	0.053	0.0015	0.0011	0.0034	0.009
Jan 2021	1138	0.37	3.1	0.12	0.052	0.0015	0.0011	0.0034	0.009
Feb 2021	1134	0.42	3.1	0.12	0.052	0.0015	0.0011	0.0034	0.009
Mar 2021	1130	0.47	3.1	0.12	0.052	0.0015	0.0011	0.0034	0.009
Apr 2021	1126	0.53	3.1	0.12	0.051	0.0014	0.0011	0.0033	0.009
May 2021	1122	0.58	3.1	0.12	0.051	0.0014	0.0011	0.0033	0.009
Jun 2021	921	0.4	3.1	0.13	0.048	0.0014	0.0012	0.0029	0.009
Jul 2021	1071	0.42	3.4	0.15	0.058	0.0015	0.0013	0.003	0.01
Aug 2021	1211	0.41	3.8	0.17	0.07	0.0016	0.0014	0.003	0.011
Sep 2021	1092	0.41	4.0	0.17	0.079	0.0017	0.0014	0.0029	0.011
Oct 2021	942	0.39	3.9	0.17	0.083	0.0017	0.0014	0.0027	0.011
Nov 2021	939	0.45	3.9	0.17	0.082	0.0017	0.0014	0.0027	0.011
Dec 2021	936	0.52	3.9	0.17	0.081	0.0017	0.0014	0.0027	0.011
Jan 2022	933	0.59	3.8	0.17	0.08	0.0016	0.0013	0.0027	0.011
Feb 2022	930	0.65	3.8	0.16	0.079	0.0016	0.0013	0.0027	0.011
Mar 2022	927	0.71	3.8	0.16	0.079	0.0016	0.0013	0.0026	0.011
Apr 2022	925	0.77	3.8	0.16	0.078	0.0016	0.0013	0.0026	0.01
May 2022	922	0.83	3.7	0.16	0.077	0.0016	0.0013	0.0026	0.01
Jun 2022	767	0.55	3.7	0.16	0.066	0.0016	0.0013	0.0025	0.01
Jul 2022	883	0.56	4.0	0.17	0.074	0.0017	0.0014	0.0026	0.011
Aug 2022	983	0.52	4.5	0.19	0.081	0.0018	0.0015	0.0027	0.012
Sep 2022	898	0.5	4.7	0.19	0.086	0.0018	0.0015	0.0027	0.012
Oct 2022	784	0.46	4.6	0.18	0.086	0.0018	0.0014	0.0026	0.011
Nov 2022	783	0.53	4.6	0.18	0.085	0.0018	0.0014	0.0026	0.011
Dec 2022	781	0.6	4.5	0.18	0.085	0.0018	0.0014	0.0025	0.011
Jan 2023	780	0.67	4.5	0.18	0.084	0.0018	0.0014	0.0025	0.011
Feb 2023	779	0.73	4.4	0.18	0.083	0.0017	0.0014	0.0025	0.011
Mar 2023	777	0.79	4.4	0.18	0.082	0.0017	0.0014	0.0025	0.011
Apr 2023	776	0.85	4.4	0.17	0.081	0.0017	0.0013	0.0025	0.011
May 2023	775	0.91	4.3	0.17	0.08	0.0017	0.0013	0.0025	0.011
Jun 2023	638	0.59	4.2	0.17	0.067	0.0016	0.0013	0.0024	0.011
Jul 2023	725	0.59	4.5	0.18	0.077	0.0017	0.0014	0.0025	0.011
Aug 2023	793	0.55	4.9	0.19	0.085	0.0018	0.0015	0.0026	0.012
Sep 2023	725	0.52	5.1	0.2	0.092	0.0019	0.0015	0.0026	0.012
Oct 2023	634	0.48	5.0	0.19	0.092	0.0018	0.0014	0.0025	0.012
Nov 2023	634	0.54	4.9	0.19	0.091	0.0018	0.0014	0.0025	0.012
Dec 2023	634	0.61	4.9	0.18	0.09	0.0018	0.0014	0.0025	0.011
Jan 2024	634	0.68	4.8	0.18	0.089	0.0018	0.0014	0.0025	0.011
Feb 2024	634	0.74	4.8	0.18	0.088	0.0018	0.0014	0.0024	0.011
Mar 2024	635	0.8	4.8	0.18	0.087	0.0018	0.0013	0.0024	0.011
Apr 2024	635	0.86	4.7	0.18	0.086	0.0018	0.0013	0.0024	0.011
May 2024	635	0.92	4.7	0.18	0.086	0.0017	0.0013	0.0024	0.011
Jun 2024	506	0.57	4.1	0.16	0.068	0.0016	0.0013	0.0023	0.01
Jul 2024	567	0.57	4.5	0.18	0.076	0.0018	0.0014	0.0024	0.011
Aug 2024	612	0.52	5.0	0.19	0.082	0.0019	0.0014	0.0025	0.011
Sep 2024	561	0.49	5.2	0.19	0.087	0.0019	0.0014	0.0025	0.011
Oct 2024	492	0.44	5.0	0.18	0.086	0.0018	0.0013	0.0024	0.01
Nov 2024	493	0.5	5.0	0.18	0.085	0.0018	0.0013	0.0024	0.01
Dec 2024	495	0.57	4.9	0.18	0.085	0.0018	0.0013	0.0024	0.01
Jan 2025	496	0.63	4.9	0.18	0.084	0.0018	0.0013	0.0024	0.01
Feb 2025	498	0.69	4.9	0.18	0.083	0.0018	0.0013	0.0023	0.010
Mar 2025	499	0.75	4.8	0.17	0.082	0.0018	0.0013	0.0023	0.0099
Apr 2025	501	0.81	4.8	0.17	0.081	0.0018	0.0012	0.0023	0.0099
May 2025	502	0.87	4.8	0.17	0.081	0.0018	0.0012	0.0023	0.0098
Jun 2025	388	0.45	4.0	0.16	0.056	0.0016	0.0012	0.0022	0.0089
Jul 2025	453	0.44	4.3	0.17	0.062	0.0017	0.0013	0.0023	0.0095
Aug 2025	496	0.38	4.7	0.18	0.064	0.0017	0.0014	0.0024	0.0097
Sep 2025	443	0.34	4.8	0.18	0.066	0.0017	0.0014	0.0024	0.0095
Oct 2025	377	0.3	4.5	0.17	0.063	0.0016	0.0013	0.0022	0.0088
Nov 2025	379	0.35	4.5	0.16	0.062	0.0016	0.0013	0.0022	0.0088
Dec 2025	381	0.41	4.4	0.16	0.062	0.0016	0.0012	0.0022	0.0087
Jan 2026	384	0.46	4.4	0.16	0.061	0.0016	0.0012	0.0022	0.0087
Feb 2026	386	0.51	4.4	0.16	0.061	0.0016	0.0012	0.0022	0.0087
Mar 2026	388	0.56	4.4	0.16	0.061	0.0016	0.0012	0.0022	0.0086
Apr 2026	390	0.61	4.3	0.16	0.06	0.0016	0.0012	0.0022	0.0086
May 2026	392	0.66	4.3	0.16	0.06	0.0016	0.0012	0.0022	0.0086
Jun 2026	343	0.44	4.0	0.15	0.053	0.0015	0.0012	0.0021	0.0083
Jul 2026	382	0.45	4.3	0.16	0.061	0.0016	0.0013	0.0023	0.0088
Aug 2026	412	0.43	4.8	0.18	0.07	0.0017	0.0013	0.0024	0.0092
Sep 2026	385	0.41	5.1	0.18	0.078	0.0018	0.0013	0.0024	0.0092
Oct 2026	344	0.38	4.9	0.17	0.079	0.0017	0.0013	0.0023	0.0088
Nov 2026	347	0.44	4.8	0.17	0.078	0.0017	0.0013	0.0023	0.0087
Dec 2026	351	0.51	4.8	0.17	0.077	0.0017	0.0012	0.0023	0.0087
Jan 2027	354	0.57	4.8	0.17	0.077	0.0017	0.0012	0.0022	0.0087
Feb 2027	356	0.63	4.7	0.17	0.076	0.0017	0.0012	0.0022	0.0086
Mar 2027	359	0.69	4.7	0.17	0.075	0.0017	0.0012	0.0022	0.0086
Apr 2027	362	0.75	4.7	0.16	0.075	0.0017	0.0012	0.0022	0.0086
May 2027	365	0.81	4.6	0.16	0.074	0.0017	0.0012	0.0022	0.0085
Jun 2027	316	0.51	4.2	0.16	0.063	0.0016	0.0012	0.0022	0.0083
Jul 2027	350	0.52	4.4	0.17	0.071	0.0017	0.0013	0.0023	0.0089
Aug 2027	378	0.49	4.7	0.19	0.081	0.0018	0.0014	0.0025	0.0094
Sep 2027	359	0.46	4.9	0.19	0.087	0.0019	0.0014	0.0025	0.0094
Oct 2027	325	0.43	4.7	0.18	0.088	0.0018	0.0013	0.0024	0.009
Nov 2027	328	0.49	4.6	0.18	0.087	0.0018	0.0013	0.0024	0.009
Dec 2027	332	0.56	4.6	0.18	0.086	0.0018	0.0013	0.0024	0.0089
Jan 2028	335	0.62	4.6	0.18	0.085	0.0018	0.0013	0.0023	0.0089
Feb 2028	338	0.68	4.5	0.18	0.084	0.0018	0.0013	0.0023	0.0088
Mar 2028	341	0.75	4.5	0.17	0.083	0.0018	0.0013	0.0023	0.0088
Apr 2028	344	0.8	4.5	0.17	0.082	0.0017	0.0013	0.0023	0.0088
May 2028	347	0.86	4.4	0.17	0.082	0.0017	0.0012	0.0023	0.0087
Jun 2028	291	0.54	4.0	0.16	0.067	0.0016	0.0012	0.0022	0.0084
Jul 2028	319	0.55	4.3	0.18	0.076	0.0017	0.0013	0.0024	0.009
Aug 2028	340	0.51	4.6	0.19	0.084	0.0019	0.0014	0.0025	0.0095
Sep 2028	325	0.48	4.8	0.19	0.09	0.0019	0.0014	0.0025	0.0095
Oct 2028	296	0.44	4.6	0.19	0.09	0.0018	0.0013	0.0024	0.0091
Nov 2028	299	0.5	4.6	0.18	0.089	0.0018	0.0013	0.0024	0.009
Dec 2028	299	0.5	4.6	0.18	0.089	0.0018	0.0013	0.0024	0.009

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
EWTP Average Monthly Dissolved Concentrations

Date	Total Dissolved Solids	Dissolved Phosphorus	Total Ammonia	Dissolved Aluminum	Dissolved Arsenic	Dissolved Copper	Dissolved Lead	Dissolved Nickel	Dissolved Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	-	-	-	-	-	-	-	-	-
Jun 2020	1175	0.082	3.5	0.052	0.012	0.0012	0.0007	0.0043	0.009
Jul 2020	1402	0.11	3.7	0.071	0.021	0.0013	0.0008	0.0045	0.01
Aug 2020	1628	0.16	3.6	0.11	0.037	0.0015	0.0011	0.0043	0.011
Sep 2020	1406	0.19	3.5	0.12	0.049	0.0015	0.0012	0.004	0.01
Oct 2020	-	-	-	-	-	-	-	-	-
Nov 2020	-	-	-	-	-	-	-	-	-
Dec 2020	-	-	-	-	-	-	-	-	-
Jan 2021	-	-	-	-	-	-	-	-	-
Feb 2021	-	-	-	-	-	-	-	-	-
Mar 2021	-	-	-	-	-	-	-	-	-
Apr 2021	-	-	-	-	-	-	-	-	-
May 2021	-	-	-	-	-	-	-	-	-
Jun 2021	921	0.4	3.1	0.13	0.048	0.0014	0.0012	0.0029	0.009
Jul 2021	1071	0.42	3.4	0.15	0.058	0.0015	0.0013	0.003	0.01
Aug 2021	1211	0.41	3.8	0.17	0.07	0.0016	0.0014	0.003	0.011
Sep 2021	1092	0.41	4.0	0.17	0.079	0.0017	0.0014	0.0029	0.011
Oct 2021	-	-	-	-	-	-	-	-	-
Nov 2021	-	-	-	-	-	-	-	-	-
Dec 2021	-	-	-	-	-	-	-	-	-
Jan 2022	-	-	-	-	-	-	-	-	-
Feb 2022	-	-	-	-	-	-	-	-	-
Mar 2022	-	-	-	-	-	-	-	-	-
Apr 2022	-	-	-	-	-	-	-	-	-
May 2022	-	-	-	-	-	-	-	-	-
Jun 2022	767	0.55	3.7	0.16	0.066	0.0016	0.0013	0.0025	0.01
Jul 2022	883	0.56	4.0	0.17	0.074	0.0017	0.0014	0.0026	0.011
Aug 2022	983	0.52	4.5	0.19	0.081	0.0018	0.0015	0.0027	0.012
Sep 2022	898	0.5	4.7	0.19	0.086	0.0018	0.0015	0.0027	0.012
Oct 2022	-	-	-	-	-	-	-	-	-
Nov 2022	-	-	-	-	-	-	-	-	-
Dec 2022	-	-	-	-	-	-	-	-	-
Jan 2023	-	-	-	-	-	-	-	-	-
Feb 2023	-	-	-	-	-	-	-	-	-
Mar 2023	-	-	-	-	-	-	-	-	-
Apr 2023	-	-	-	-	-	-	-	-	-
May 2023	-	-	-	-	-	-	-	-	-
Jun 2023	638	0.59	4.2	0.17	0.067	0.0016	0.0013	0.0024	0.011
Jul 2023	725	0.59	4.5	0.18	0.077	0.0017	0.0014	0.0025	0.011
Aug 2023	793	0.55	4.9	0.19	0.085	0.0018	0.0015	0.0026	0.012
Sep 2023	725	0.52	5.1	0.2	0.092	0.0019	0.0015	0.0026	0.012
Oct 2023	-	-	-	-	-	-	-	-	-
Nov 2023	-	-	-	-	-	-	-	-	-
Dec 2023	-	-	-	-	-	-	-	-	-
Jan 2024	-	-	-	-	-	-	-	-	-
Feb 2024	-	-	-	-	-	-	-	-	-
Mar 2024	-	-	-	-	-	-	-	-	-
Apr 2024	-	-	-	-	-	-	-	-	-
May 2024	-	-	-	-	-	-	-	-	-
Jun 2024	506	0.57	4.1	0.16	0.068	0.0016	0.0013	0.0023	0.01
Jul 2024	567	0.57	4.5	0.18	0.076	0.0018	0.0014	0.0024	0.011
Aug 2024	612	0.52	5.0	0.19	0.082	0.0019	0.0014	0.0025	0.011
Sep 2024	561	0.49	5.2	0.19	0.087	0.0019	0.0014	0.0025	0.011
Oct 2024	-	-	-	-	-	-	-	-	-
Nov 2024	-	-	-	-	-	-	-	-	-
Dec 2024	-	-	-	-	-	-	-	-	-
Jan 2025	-	-	-	-	-	-	-	-	-
Feb 2025	-	-	-	-	-	-	-	-	-
Mar 2025	-	-	-	-	-	-	-	-	-
Apr 2025	-	-	-	-	-	-	-	-	-
May 2025	-	-	-	-	-	-	-	-	-
Jun 2025	388	0.45	4.0	0.16	0.056	0.0016	0.0012	0.0022	0.0089
Jul 2025	453	0.44	4.3	0.17	0.062	0.0017	0.0013	0.0023	0.0095
Aug 2025	496	0.38	4.7	0.18	0.064	0.0017	0.0014	0.0024	0.0097
Sep 2025	443	0.34	4.8	0.18	0.066	0.0017	0.0014	0.0024	0.0095
Oct 2025	-	-	-	-	-	-	-	-	-
Nov 2025	-	-	-	-	-	-	-	-	-
Dec 2025	-	-	-	-	-	-	-	-	-
Jan 2026	-	-	-	-	-	-	-	-	-
Feb 2026	-	-	-	-	-	-	-	-	-
Mar 2026	-	-	-	-	-	-	-	-	-
Apr 2026	-	-	-	-	-	-	-	-	-
May 2026	-	-	-	-	-	-	-	-	-
Jun 2026	343	0.44	4.0	0.15	0.053	0.0015	0.0012	0.0021	0.0083
Jul 2026	382	0.45	4.3	0.16	0.061	0.0016	0.0013	0.0023	0.0088
Aug 2026	412	0.43	4.8	0.18	0.07	0.0017	0.0013	0.0024	0.0092
Sep 2026	385	0.41	5.1	0.18	0.078	0.0018	0.0013	0.0024	0.0092
Oct 2026	-	-	-	-	-	-	-	-	-
Nov 2026	-	-	-	-	-	-	-	-	-
Dec 2026	-	-	-	-	-	-	-	-	-
Jan 2027	-	-	-	-	-	-	-	-	-
Feb 2027	-	-	-	-	-	-	-	-	-
Mar 2027	-	-	-	-	-	-	-	-	-
Apr 2027	-	-	-	-	-	-	-	-	-
May 2027	-	-	-	-	-	-	-	-	-
Jun 2027	316	0.51	4.2	0.16	0.063	0.0016	0.0012	0.0022	0.0083
Jul 2027	350	0.52	4.4	0.17	0.071	0.0017	0.0013	0.0023	0.0089
Aug 2027	378	0.49	4.7	0.19	0.081	0.0018	0.0014	0.0025	0.0094
Sep 2027	359	0.46	4.9	0.19	0.087	0.0019	0.0014	0.0025	0.0094
Oct 2027	-	-	-	-	-	-	-	-	-
Nov 2027	-	-	-	-	-	-	-	-	-
Dec 2027	-	-	-	-	-	-	-	-	-
Jan 2028	-	-	-	-	-	-	-	-	-
Feb 2028	-	-	-	-	-	-	-	-	-
Mar 2028	-	-	-	-	-	-	-	-	-
Apr 2028	-	-	-	-	-	-	-	-	-
May 2028	-	-	-	-	-	-	-	-	-
Jun 2028	291	0.54	4.0	0.16	0.067	0.0016	0.0012	0.0022	0.0084
Jul 2028	319	0.55	4.3	0.18	0.076	0.0017	0.0013	0.0024	0.009
Aug 2028	340	0.51	4.6	0.19	0.084	0.0019	0.0014	0.0025	0.0095
Sep 2028	325	0.48	4.8	0.19	0.09	0.0019	0.0014	0.0025	0.0095
Oct 2028	-	-	-	-	-	-	-	-	-
Nov 2028	-	-	-	-	-	-	-	-	-
Dec 2028	-	-	-	-	-	-	-	-	-

0.1 Denotes a value above the discharge criteria

Appendix E
Wet Years Scenario
EWTP Average Monthly Total Concentrations

Date	Total Dissolved Solids	Total Phosphorus	Total Ammonia	Total Aluminum	Total Arsenic	Total Copper	Total Lead	Total Nickel	Total Zinc
	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
Discharge Criteria	3500	2	14	2	0.3	0.2	0.2	0.5	0.4
May 2020	-	-	-	-	-	-	-	-	-
Jun 2020	1175	0.15	3.5	0.27	0.013	0.0016	0.0007	0.0043	0.029
Jul 2020	1402	0.18	3.7	0.29	0.022	0.0017	0.0008	0.0045	0.03
Aug 2020	1628	0.22	3.6	0.33	0.039	0.0019	0.0011	0.0043	0.031
Sep 2020	1406	0.25	3.5	0.34	0.05	0.0019	0.0012	0.004	0.031
Oct 2020	-	-	-	-	-	-	-	-	-
Nov 2020	-	-	-	-	-	-	-	-	-
Dec 2020	-	-	-	-	-	-	-	-	-
Jan 2021	-	-	-	-	-	-	-	-	-
Feb 2021	-	-	-	-	-	-	-	-	-
Mar 2021	-	-	-	-	-	-	-	-	-
Apr 2021	-	-	-	-	-	-	-	-	-
May 2021	-	-	-	-	-	-	-	-	-
Jun 2021	921	0.47	3.1	0.35	0.049	0.0018	0.0012	0.0029	0.029
Jul 2021	1071	0.48	3.4	0.37	0.059	0.0019	0.0013	0.003	0.03
Aug 2021	1211	0.47	3.8	0.39	0.071	0.0021	0.0014	0.003	0.031
Sep 2021	1092	0.47	4.0	0.4	0.08	0.0021	0.0014	0.0029	0.031
Oct 2021	-	-	-	-	-	-	-	-	-
Nov 2021	-	-	-	-	-	-	-	-	-
Dec 2021	-	-	-	-	-	-	-	-	-
Jan 2022	-	-	-	-	-	-	-	-	-
Feb 2022	-	-	-	-	-	-	-	-	-
Mar 2022	-	-	-	-	-	-	-	-	-
Apr 2022	-	-	-	-	-	-	-	-	-
May 2022	-	-	-	-	-	-	-	-	-
Jun 2022	767	0.61	3.7	0.38	0.067	0.002	0.0013	0.0025	0.03
Jul 2022	883	0.62	4.0	0.4	0.075	0.0021	0.0014	0.0026	0.031
Aug 2022	983	0.59	4.5	0.41	0.082	0.0022	0.0015	0.0027	0.032
Sep 2022	898	0.57	4.7	0.42	0.088	0.0023	0.0015	0.0027	0.032
Oct 2022	-	-	-	-	-	-	-	-	-
Nov 2022	-	-	-	-	-	-	-	-	-
Dec 2022	-	-	-	-	-	-	-	-	-
Jan 2023	-	-	-	-	-	-	-	-	-
Feb 2023	-	-	-	-	-	-	-	-	-
Mar 2023	-	-	-	-	-	-	-	-	-
Apr 2023	-	-	-	-	-	-	-	-	-
May 2023	-	-	-	-	-	-	-	-	-
Jun 2023	638	0.65	4.2	0.39	0.069	0.002	0.0013	0.0024	0.031
Jul 2023	725	0.66	4.5	0.4	0.078	0.0021	0.0014	0.0025	0.031
Aug 2023	793	0.61	4.9	0.42	0.086	0.0022	0.0015	0.0026	0.032
Sep 2023	725	0.58	5.1	0.42	0.093	0.0023	0.0015	0.0026	0.032
Oct 2023	-	-	-	-	-	-	-	-	-
Nov 2023	-	-	-	-	-	-	-	-	-
Dec 2023	-	-	-	-	-	-	-	-	-
Jan 2024	-	-	-	-	-	-	-	-	-
Feb 2024	-	-	-	-	-	-	-	-	-
Mar 2024	-	-	-	-	-	-	-	-	-
Apr 2024	-	-	-	-	-	-	-	-	-
May 2024	-	-	-	-	-	-	-	-	-
Jun 2024	506	0.63	4.1	0.39	0.069	0.002	0.0013	0.0023	0.03
Jul 2024	567	0.63	4.5	0.4	0.077	0.0022	0.0014	0.0024	0.031
Aug 2024	612	0.58	5.0	0.41	0.083	0.0023	0.0014	0.0025	0.031
Sep 2024	561	0.55	5.2	0.42	0.088	0.0023	0.0014	0.0025	0.031
Oct 2024	-	-	-	-	-	-	-	-	-
Nov 2024	-	-	-	-	-	-	-	-	-
Dec 2024	-	-	-	-	-	-	-	-	-
Jan 2025	-	-	-	-	-	-	-	-	-
Feb 2025	-	-	-	-	-	-	-	-	-
Mar 2025	-	-	-	-	-	-	-	-	-
Apr 2025	-	-	-	-	-	-	-	-	-
May 2025	-	-	-	-	-	-	-	-	-
Jun 2025	388	0.51	4.0	0.38	0.057	0.002	0.0012	0.0022	0.029
Jul 2025	453	0.5	4.3	0.39	0.063	0.0021	0.0013	0.0023	0.03
Aug 2025	496	0.44	4.7	0.4	0.065	0.0021	0.0014	0.0024	0.03
Sep 2025	443	0.4	4.8	0.4	0.067	0.0021	0.0014	0.0024	0.03
Oct 2025	-	-	-	-	-	-	-	-	-
Nov 2025	-	-	-	-	-	-	-	-	-
Dec 2025	-	-	-	-	-	-	-	-	-
Jan 2026	-	-	-	-	-	-	-	-	-
Feb 2026	-	-	-	-	-	-	-	-	-
Mar 2026	-	-	-	-	-	-	-	-	-
Apr 2026	-	-	-	-	-	-	-	-	-
May 2026	-	-	-	-	-	-	-	-	-
Jun 2026	343	0.51	4.0	0.37	0.054	0.0019	0.0012	0.0021	0.028
Jul 2026	382	0.52	4.3	0.39	0.062	0.002	0.0013	0.0023	0.029
Aug 2026	412	0.49	4.8	0.4	0.071	0.0021	0.0013	0.0024	0.029
Sep 2026	385	0.47	5.1	0.4	0.079	0.0022	0.0013	0.0024	0.029
Oct 2026	-	-	-	-	-	-	-	-	-
Nov 2026	-	-	-	-	-	-	-	-	-
Dec 2026	-	-	-	-	-	-	-	-	-
Jan 2027	-	-	-	-	-	-	-	-	-
Feb 2027	-	-	-	-	-	-	-	-	-
Mar 2027	-	-	-	-	-	-	-	-	-
Apr 2027	-	-	-	-	-	-	-	-	-
May 2027	-	-	-	-	-	-	-	-	-
Jun 2027	316	0.57	4.2	0.38	0.064	0.002	0.0012	0.0022	0.028
Jul 2027	350	0.58	4.4	0.39	0.072	0.0021	0.0013	0.0023	0.029
Aug 2027	378	0.55	4.7	0.41	0.082	0.0022	0.0014	0.0025	0.03
Sep 2027	359	0.53	4.9	0.41	0.088	0.0023	0.0014	0.0025	0.03
Oct 2027	-	-	-	-	-	-	-	-	-
Nov 2027	-	-	-	-	-	-	-	-	-
Dec 2027	-	-	-	-	-	-	-	-	-
Jan 2028	-	-	-	-	-	-	-	-	-
Feb 2028	-	-	-	-	-	-	-	-	-
Mar 2028	-	-	-	-	-	-	-	-	-
Apr 2028	-	-	-	-	-	-	-	-	-
May 2028	-	-	-	-	-	-	-	-	-
Jun 2028	291	0.6	4.0	0.39	0.068	0.002	0.0012	0.0022	0.029
Jul 2028	319	0.61	4.3	0.4	0.077	0.0022	0.0013	0.0024	0.029
Aug 2028	340	0.57	4.6	0.41	0.085	0.0023	0.0014	0.0025	0.03
Sep 2028	325	0.54	4.8	0.42	0.091	0.0023	0.0014	0.0025	0.03
Oct 2028	-	-	-	-	-	-	-	-	-
Nov 2028	-	-	-	-	-	-	-	-	-
Dec 2028	-	-	-	-	-	-	-	-	-

0.1 Denotes a value above the discharge criteria



golder.com

APPENDIX D • SEDIMENT AND EROSION MANAGEMENT PLAN



AGNICO EAGLE

Meliadine Division

Sediment and Erosion Management Plan

**MARCH 2020
VERSION 2**

EXECUTIVE SUMMARY

This document presents the Sediment and Erosion management plan (the Plan) at the Meliadine Gold Project. The purpose of this Plan is to provide consolidated information on the management and monitoring of potential areas subjected to erosion. This is accomplished by reviewing the potential effects of total suspended solids (TSS) and turbidity, the Federal guidelines and the license requirements, followed by the periods and types of activities subjected to erosion, and the specific monitoring and mitigating measures.

General findings on the effects of TSS on fish and fish habitat have been listed, such as sublethal and lethal effects on fish and their eggs. Federal TSS Guidelines have been cited, distinguishing the short-term and long-term exposure thresholds. Turbidity guidelines are also discussed in the present document. The Plan presents the monitoring and mitigating actions related to three (3) specific periods of activity: Periods of construction near water – during construction and operation; periods of freshet or significant runoff events – during construction, operation and closure; periods of potential impact to waterbodies – during operation. The proposed monitoring and mitigating measures are discussed for those periods of activity.

DOCUMENT CONTROL

Version	Date (YM)	Section	Page	Revision
1	March 2019	All		Comprehensive plan
2	March 2020	2.3	5	Updated to include TSS guidelines for MEL-14 Monitoring Program Station
		3.3	7	Updated mitigation measures to include check dams

TABLE OF CONTENTS

Executive Summary **i**

ᑭᐱᑦ ᑭᐱᑦᐱᑦ **ii**

Table of Contents..... **iv**

Units **v**

Section 1 • INTRODUCTION..... **1**

Section 2 • TOTAL SUSPENDED SOLIDS/TURBIDITY EFFECTS, FEDERAL GUIDELINES AND LICENSE REQUIREMENTS..... **3**

 2.1 Effects of Total Suspended Sediments on Fish Habitat 3

 2.2 Federal Guidelines 3

 2.2.1 TSS Guidelines..... 3

 2.2.2 Turbidity Guidelines..... 4

 2.3 License Requirements for the Protection of Fish and Fish Habitat at Meliadine 5

Section 3 • SEDIMENT AND EROSION MONITORING AND MITIGATION..... **6**

 3.1 Sediment and Erosion during Specific Periods 6

 3.2 Erosion and Sediment Monitoring 6

 3.3 Mitigating Measures 7

Section 4 • REFERENCES..... **9**

Acronyms

Agnico Eagle	Agnico Eagle Mines Limited – Meliadine Division
CCME	Canadian Council of Ministers of the Environment
DFO	Fisheries and Oceans Canada
NIRB	Nunavut Impact Review Board
NTU	Nephelometric Turbidity Units
NWB	Nunavut Water Board
Plan	Sediment and Erosion Management Plan
TSS	Total Suspended Solids

UNITS

h	hour
km	kilometre
km ²	square kilometre
mg/L	milligram per litre

SECTION 1 • INTRODUCTION

Agnico Eagle Mines Limited (Agnico Eagle) is developing the Meliadine Gold Project (Project), located approximately 25 kilometres (km) north of Rankin Inlet, and 80 km southwest of Chesterfield Inlet in the Kivalliq Region of Nunavut. Situated on the western shore of Hudson Bay, the Project site is located on a peninsula between the east, south, and west basins of Meliadine Lake (63°1'23.8" N, 92°13'6.42"W), on Inuit owned lands. The Project is located within the Meliadine Lake watershed of the Wilson Water Management Area (Nunavut Water Regulations Schedule 4).

As presented in Table 1.1, there are four phases to the development of the Tiriganiaq deposit: 3.5 years construction (Q4 Year -5 to Q2 Year -1), 8.5 years mine operation (Q2 Year -1 to Year 8), 3 years closure (Year 9 to Year 11), and post-closure (Year 11 forwards).

Table 1.1 Overview of Timeline and General Activities

Phase	Year	General Activities
Construction	Year -5 to year -1	<ul style="list-style-type: none"> Construct site infrastructure Develop the underground mine ramp Stockpile ore
Operations	Year -1 to 8	<ul style="list-style-type: none"> Mining operations Stockpile ore Dry stack tailing deposition
Closure	Year 9 to 11	<ul style="list-style-type: none"> Decommission of underground mine surface opening Cover on top of tailings Decommission non-essential mine infrastructure Fill open pits with active pumping
Post-Closure	Year 11 forwards	<ul style="list-style-type: none"> Site and surrounding environment monitoring

This document presents the Sediment and Erosion Management Plan (the Plan). The purpose of this Plan is to provide consolidated information on the management and monitoring of potential areas subjected to erosion. This is accomplished by presenting first a review of the potential effects of total suspended solids (TSS) and turbidity, the Federal guidelines and the license requirements, followed by the periods and type of activities subjected to erosion, and the specific monitoring and mitigating measures.

As per Nunavut Impact Review Board (NIRB) Meliadine Project Certificate No.006 Condition 28, the Sediment and Erosion Management Plan should be developed to prevent or minimize the effects of destabilization and erosion that may occur due to Project activities. The plan should also detail sediment control plans to prevent and/or mitigate sediment loading into surface water within the Project area.

The objectives of the plan are:

- To prevent the release of sediment into streams and waterbodies during construction activities;
- To reduce and mitigate erosion and the release of sediment during operations activities;
- To specify erosion and sediment control measures that, if implemented and maintained, will help Agnico Eagle maintain compliance with the Federal Fisheries Act, specifically with Section 36(3) of the Act, which prohibits the deposition of deleterious substances into waterbodies frequented by fish; and
- To provide references to approvals, relevant standards, control plans and procedures for training, communications, investigation and corrective action, and audits that are required under the Project Agreement.

SECTION 2 • TOTAL SUSPENDED SOLIDS/TURBIDITY EFFECTS, FEDERAL GUIDELINES AND LICENSE REQUIREMENTS

2.1 Effects of Total Suspended Sediments on Fish Habitat

Suspended sediments, and associated effects on water clarity, have the potential to affect fish and fish habitat in a variety of ways, including but not limited to:

- Smothering of deposited eggs or siltation of spawning habitats;
- Smothering of benthic invertebrate communities;
- Decreased primary productivity caused by reduced light penetration;
- Reduced visibility, which may decrease feeding efficiency and/or increase predator avoidance; and
- Clogging and abrasion of gills.

Moreover, the general findings for effects of TSS on fish and fish habitat indicate the following:

- Effects of TSS depend on both the concentration of TSS and duration of exposure;
- Effects of TSS can also be influenced by the size and shape of suspended particles;
- Lethal concentration of TSS on fish over acute exposure ranges from hundreds to hundreds of thousands of mg/L;
- Sublethal effects on fish (reduced growth, changes in blood chemistry, histological changes) associated with chronic exposures tend to be exhibited at TSS concentrations ranging from the tens to hundreds of mg/L;
- There is considerable uncertainty about potential effects of low TSS concentrations over long time periods;
- Overall, the most sensitive group of aquatic organisms to TSS appears to be salmonids, and guidelines are developed to protect this group;
- Adult salmonids are generally more sensitive to short durations of high concentrations of suspended sediments than juvenile salmonids; and
- Low suspended sediment levels are known to cause egg mortality (40 %) to rainbow trout at long durations (7 mg/L at 48 days). Guidelines for long-term exposure reflect these findings.

More details are located in the report from Fisheries and Oceans Canada (DFO) on the effects of sediments on fish and their habitat (Fisheries and Oceans Canada, 1999).

2.2 Federal Guidelines

2.2.1 TSS Guidelines

The Canadian Council of Ministers of the Environment (CCME) specifies separate guidelines for TSS for clear and high flow periods. The guidelines are derived primarily from Caux *et al.* (1997), with application intended mainly for British Columbia streams. In the case of the application to the Meliadine Project lakes, the clear flow guidelines would be most relevant; even during freshet. The

lakes would not expect to see large natural fluctuations in TSS except in localized areas for short periods.

The guidelines put forth by the CCME recognize that the severity of effects of suspended sediments is a function of both the concentration of suspended sediments and the duration of exposure. Guidelines are intended to protect the most sensitive taxonomic group and the most sensitive life history stages.

Table 2.1 Existing Federal TSS Guidelines (after Agnico Eagle, 2018)

Source	Short-Term Exposure	Long-Term Exposure
CCME (1999)	Anthropogenic activities should not increase suspended sediment concentrations by more than 25 mg/L over background levels during any short-term exposure period (e.g., 24-h).	For longer term exposure (e.g., 30 days or more), average suspended sediment concentrations should not be increased by more than 5 mg/L over background levels.
MDMER (2002)	Maximum authorized concentration in a composite effluent sample = 22.5 mg/L. Maximum authorized concentration in a grab sample of effluent = 30 mg/L.	Maximum authorized monthly mean effluent concentration = 15 mg/L.

2.2.2 Turbidity Guidelines

Turbidity guidelines put forth by the CCME (1999) are based on extrapolation from the TSS guidance above, adjusted by a factor of about 3:1 (a typical average ratio for TSS: turbidity). In the case of turbidity for clear water, CCME (1999) recommends a maximum increase of 8 Nephelometric Turbidity Units (NTU) from background levels for a short-term exposure (e.g., 24-hour period), and a maximum average increase of 2 NTU from background levels for a longer term exposure (e.g., 30-day period).

CCME (1999) notes that in some cases short-term resuspension of sediments and nutrients in the water column can augment primary productivity, and in other cases, changes in light penetration may be inconsequential if a system is limited by other factors such as nutrients. The Caux *et al.* (1997) study considered effects of suspended sediment not only on fish but also on algae and zooplankton. In summary, the recommendations put forth by Caux *et al.* (1997) are based mainly on the most sensitive taxonomic group, which is salmonids.

However, research has shown that widespread, chronic turbidity can result in reduced light penetration and subsequent reductions of primary productivity (Fisheries and Oceans Canada, 1999; Canadian Council of Ministers of the Environment, 1999; Lloyd, Koenigs, & Laperriere, 1987). Consequently, water clarity is of concern at broader spatial scales and longer time frames. It should be noted that DFO's report on effects of sediment on fish and their habitat (DFO, 1999) endorses the guidelines for TSS put forth by the CCME (1999), but does not recommend following guidelines for turbidity. Rather, turbidity may be used as a surrogate for suspended sediment only when the relationship between the two parameters is established for a particular waterbody.

2.3 License Requirements for the Protection of Fish and Fish Habitat at Meliadine

The Nunavut Water Board (NWB) Type A Water License for the Meliadine Project includes:

All surface runoff and/or discharge from drainage management systems, at the Monitoring Program Stations MEL-SR-1 to MEL-SR-TBD referred to in Part I, Item 11, during the Construction/Operation of any facilities and infrastructure associated with this project, including laydown areas and All Weather Access Road, where flow may directly or indirectly enter a Water body, shall not exceed the Surface Runoff and Discharge from Drainage Management Systems quality limits in Table 2.3.

Table 2.3 Surface Runoff and Discharge from Drainage Management Systems Quality Limits

Parameter	Maximum Average Concentration	Maximum Concentration of Any Grab Sample
Total Suspended Solids (TSS) (mg/L)	50.0	100.0
Oil and Grease	No Visible Sheen	No Visible Sheen
pH	Between 6.0 and 9.5	Between 6.0 and 9.5

Additionally, the discharge of effluent from the Final Discharge Point at Monitoring Program Station MEL-14 directed to Meliadine Lake through the Meliadine Lake Diffuser shall not exceed the following TSS concentrations, in accordance with the requirements of the Type A Water License (Part F, Item 3) and MDMER (see Table 2.1 above):

- Maximum monthly mean effluent concentration: 15 mg/L;
- Maximum concentration of any grab sample of effluent: 30 mg/L.

SECTION 3 • SEDIMENT AND EROSION MONITORING AND MITIGATION

3.1 Sediment and Erosion during Specific Periods

The purpose of the Plan is to ensure that Agnico Eagle will successfully monitor signs of sedimentation and erosion and minimize its resulting effects. This plan presents the monitoring and mitigating actions related to three (3) specific periods of activity for Meliadine:

- Periods of construction near water – during construction and operation;
- Periods of freshet or significant runoff events – during construction, operation and closure;
- Periods of potential impact to waterbodies – during operation.

The construction of water management infrastructure could potentially lead to excess TSS. Therefore, erosion control methods must be considered during construction of water management infrastructure. In addition, erosion control must be considered during any dewatering activity.

The freshet season at Meliadine occurs approximately from mid-May until the end of June. In addition, there can be periods of high water flow due to rainfall events from late May – early October. As most site construction has been completed at the Meliadine site there are new areas and infrastructure that have become potentially vulnerable to excess water during the freshet season and in response to rainfall, such as, but not limited to:

- Culverts and other water management infrastructures;
- Newly constructed embankments, such as roads and berms;
- Water channels; and
- Surface runoff.

Water transfer and water discharge during operation can also lead to erosion and sedimentation.

3.2 Erosion and Sediment Monitoring

In order to monitor potential erosion and sedimentation, smaller water management infrastructure such as culverts, cross drains, surface runoff and ditches are inspected up to daily during freshet (minimum of weekly), on a monthly basis thereafter and daily after significant rain events. Larger culverts and bridges are inspected more often if they represent a risk for daily operations, for the receiving environment or for the health and safety of workers. More specifically, the following aspects are monitored during visual inspections:

- Accumulation of debris near the inlet of the crossings, impeding the free flow of water at those locations;
- Bed erosion upstream and downstream of watercourse crossing structures;
- Scour under bridge abutments and abutment foundations; and
- Erosion along cutslopes and fillslopes of embankments (rill and gully erosion), etc.

Newly excavated channels are inspected on a regular basis and after significant rain events. Erosion signs along the channel flow are monitored and documented. Inspections are carried out during the spring when surficial ice moves towards the inlet of the diversion channels to ensure that no ice

blockage causes water buildup upstream of the channel, which could lead to subsequent erosion problems. It is important to develop a database to determine if adverse trends are occurring. If adverse trends are observed, then mitigation will be undertaken to prevent a major incident.

The frequency of water and turbidity sampling are in accordance with the requirements of the Type A Water License and MDMER. The frequency will be increased if required during the freshet season or during heavy rainfall events. Procedures for turbidity monitoring include:

- Collection of water at the site of sediment entrance (exposure), and at a reference site (i.e., in the same watercourse/waterbody in an area unaffected by the sedimentation [upstream, at least 50 m away where water does not appear to be impacted]).
- Analyze samples for turbidity using a field turbidity meter and compare the exposure sample to the reference sample.
- If the exposure sample results are higher than the reference then mitigation will be undertaken (i.e. installation of silt fencing, silt barrier booms, etc.) to prevent any impact to watercourses.

If Agnico Eagle is actively working in an area with elevated turbidity – the work will stop until the level of clarity returns to an acceptable level.

Monitoring will be documented with site photographs and inspection forms.

3.3 Mitigation Measures

The following mitigation measures could be used, if required, to reduce risks associated with erosion and sedimentation.

- Riprap or clean non-acid generating/non-metal leaching rockfill could be used to armor shorelines, bridge abutments, culverts inlets and outlets and toe berms;
- Ditches managing high volumes of water could be armored for erosion control and reduce the speed of water flow;
- Sedimentation basins could be constructed at sensitive locations to allow settlement of finer sediments;
- Check dams could be constructed in areas of sustained high levels of TSS to mitigate transport of TSS downstream;
- Ditches, culverts and other water crossing structures should be maintained free of debris to allow free flow of runoff water;
- Installation of erosion control material such as turbidity barriers, silt curtains or straw booms;
- Site-specific erosion issues may arise during the mine operation that require specific local corrective actions;
- In-stream construction during periods when streams are expected to be dry or frozen to the bottom (i.e., during winter or fall). Isolation methods will be used for work below the high water mark for streams with flowing water at the time of construction;

- Materials installed below the high water mark (i.e., riprap) will be cleaned prior to installation to avoid adding deleterious substances to watercourses. Where concrete is installed, it will be allowed to cure fully prior to installation;
- Riparian areas will be maintained whenever possible to minimize erosion and impacts to fish habitat, with vegetation removal limited to the width of the workspace footprint. Disturbed areas along the streambanks will be stabilized and allowed to re-vegetate upon completion of work to minimize future erosion;
- Debris and excess materials resulting from construction will be removed from the work site to prevent them reaching water bodies; and
- When using equipment that creates tracks on the surface, run the equipment slowly to create grooves running perpendicular the slope and not parallel to the slope. This type of texture on slopes can slow the speed of runoff and reduce the amount of erosion and sediment transported downhill. This method must also be combined with an additional method of catching sediment at the base of the slope, such as a silt fence, straw log, etc.

SECTION 4 • REFERENCES

Agnico Eagle Mines Ltd. (2016). Water Management Plan. In Accordance with Water License 2AM-MEL1631. Prepared by Agnico-Eagle Mines Limited - Meliadine Division, Version 2, March 2018.

Canadian Council of Ministers of the Environment. (1999). Canadian Water Quality Guidelines for the Protection of Aquatic Life - Total Particulate Matter. (Updated 2002).

Caux, P. Y., Moore, D. R., & MacDonald, D. (1997). Ambient water quality guidelines for turbidity, suspended particles and benthic sediments - technical appendix. Prepared for BC Ministry of Environment, Lands and Parks.

Fisheries and Oceans Canada. (1999). The Effects of Sediment on Fish and their Habitat. Research Document 99/139.

Government of Canada. (2002). Metal and Diamond Mining Effluent Regulations. SOR/2002-222. Minister of Justice of Canada. Current to February 26, 2020, last amended on June 25, 2019.

Lloyd, D. S., Koenings, J. P., & Laperriere, J. D. (1987). Effects of Turbidity in Fresh Waters of Alaska. North American Journal of Fisheries Management, 7(1), 18-33.

GNWT-DOT Erosion and Sediment Control Manual (GNWT 2017).

APPENDIX E • WATER QUALITY AND FLOW MONITORING PLAN



AGNICO EAGLE

Meliadine Division

Water Quality and Flow Monitoring Plan

**MARCH 2020
VERSION 2**

EXECUTIVE SUMMARY

The Water Quality and Flow Monitoring Plan (the Plan) has been prepared in accordance with the requirements of the Nunavut Water Board Type A water license 2AM-MEL1631. The Plan is one component of the *Aquatic Effects Management Program* (AEMP) and is closely associated with the *Water Management Plan* and the *Metal and Diamond Mining Effluent Regulations (MDMER)*.

Section 2 of this Plan includes an overview of the monitoring programs and mine development schedule. Section 3 provides specific details (including sampling locations and parameters to be measured) for the compliance monitoring program, along with general guidance for the event monitoring program. An adaptive management program is described for regulated discharge and non-regulated discharges in Section 3. Requirements of the flow monitoring program are described in Section 4, and an overview of the reporting requirements in Section 5. Section 6 provides overview of Quality Assurance / Quality Control practices.

IMPLEMENTATION SCHEDULE

As required by Water License 2AM-MEL1631, Part B, Item 10, the proposed implementation schedule for this Plan is outlined below.

This Plan will be implemented immediately (December 2018) subject to any modifications proposed by the NWB as a result of the review and approval process.

DISTRIBUTION LIST

Environmental Superintendent
Environmental Coordinators
Environmental Technicians

DOCUMENT CONTROL

Version	Date (YMD)	Section	Page	Revision
1	18/12/16	All	All	Comprehensive plan for Meliadine project. First version composed by Meliadine Environment Department.
2	20/03/15	All	All	Updated plan formatting and added information on QA/QC as Section 6. Previous Section 5.3.1 (SWTP sampling) moved to GWMP.

Prepared by:

Agnico Eagle Mines Limited - Meliadine Division

Table of Contents

EXECUTIVE SUMMARY.....	ii
ᑲᐱᑦ ᑲᐱᑦ ᑲᐱᑦ	iii
List of Figures.....	vii
List of Tables.....	vii
Section 1 • Introduction	1
Section 2 • Overview of Site Water Management Plan	2
Section 3 • Overview of Monitoring Programs.....	3
3.1 Compliance Monitoring Program (CM)	3
3.2 Event Monitoring Program (EM)	3
Section 4 • Overview of Mine Development Schedule	4
Section 5 • Monitoring Programs.....	5
5.1 Compliance Monitoring Program	5
5.1.1 General Sampling and Analysis Program.....	5
5.1.2 Compliance Monitoring Stations and Discharge Criteria	12
5.2 Event Monitoring.....	15
5.3 Adaptive Management Program	15
5.3.1 Adaptive Management Program for Regulated Discharge	16
5.3.2 Adaptive Management Program for Non-Regulated Discharge	19
Section 6 • Quality assurance/Quality control procedures	21
6.1 Quality Assurance	21
6.1.1 Field Staff Training and Operations.....	21
6.1.2 Laboratory	21
6.1.3 Office Operations	21
6.2 Quality Control.....	22
Section 7 • Flow Volumes	24
Section 8 • Reporting.....	25
8.1 Annual Reporting.....	25
8.2 Exceedance Reporting	25

Section 9 • References.....26

List of Figures

Figure 5.1: Sampling locations..... 7

Figure 5.2: Logic Diagram for Regulated Discharge 18

List of Tables

Table 5.1: Monitoring Program.....8

Table 5.2: Monitoring Parameters.....10

Table 5.3: Summary of Sampling Requirements for Each Analyte.....11

Table 5.4: TSS and pH Criteria at CM Stations MEL-D-1 through MEL-D-TBD.....12

Table 5.5: Effluent Criteria at CM Station MEL-SR-1 to MEL-SR-TBD.....13

Table 5.6: Effluent Criteria at CM Station MEL-14.....13

Table 5.7: Effluent Criteria at CM Station MEL-26.....14

Table 5.8: Effluent Criteria at CM Station MEL-25.....14

Table 5.9: Action Plan for Regulated Discharge.....17

SECTION 1 • INTRODUCTION

The Water Quality and Flow Monitoring Plan (the Plan) has been prepared in accordance with the requirements of the Nunavut Water Board Type A water license 2AM-MEL1631 (the License). The Plan is one component of the *Aquatic Effects Management Program* (AEMP) and is closely associated with the *Water Management Plan* and the *Metal and Diamond Mining Effluent Regulations (MDMER)*. The implementation and periodic updates to this Plan are the responsibility of the Meliadine Environment Department under the guidance of the Meliadine Environment Superintendent or designate.

The Plan summarizes the monitoring locations, sampling frequency, monitoring parameters, compliance discharge criteria and an adaptive management plan for water quality at the Meliadine Gold Project.

The purpose of this Water Quality and Flow Monitoring Plan is to establish the program that is to be implemented and followed by AEM's Meliadine environmental management team to monitor the performance of the waste and water management systems at the Meliadine Gold Project. The program includes:

- Verifying and validating the predicted water quality values with empirical measurements of the mine site water quality and flows;
- A comparison of measured water quality data to compliance requirements stipulated in the License; and
- A framework for adaptive management that allows the identification and rectification, where necessary, of unexpected trends or non-compliance in water quality and flows.

The Plan provides information on the locations of the monitoring stations at the various stages of mining. These monitoring locations are used to evaluate the performance of the mine waste and water management system.

The objectives of the monitoring program are:

1. To track the chemistry of the contact and non-contact water prior to and during discharge;
2. To assist in identifying if water treatment is required prior to discharge; and
3. To minimize the potential impacts of mining activities on the surrounding environment.

Additional locations outside the footprint of the mine (and outside the scope of this Plan) will be monitored under the *Meliadine Gold Project Aquatic Effects Management Program* (Golder 2016).

SECTION 2 • OVERVIEW OF SITE WATER MANAGEMENT PLAN

Details of overall water management are discussed in the Meliadine Water Management Plan (WMP) (Agnico Eagle, 2020) which is updated annually. A network of berms, dikes, containment ponds, channels, culverts and sumps are in place and maintained to facilitate water management (Section 3 of WMP).

As specified in the WMP, surface contact water is intercepted, diverted and contained within various containment ponds prior to evaporation or treatment. Water collected in CP3 and CP4 is discharged upstream of Culvert 2 where it flows to CP1. Water collected in CP5 is either treated by an RO treatment plant prior to discharging to CP1 or discharged to CP1 directly, depending on the in situ CP5 water quality. Water collected in the P-area is temporarily stored and then actively evaporated. At CP1, the water is treated for total suspended solids (TSS) at the EWTP and discharged through the diffuser located in Meliadine Lake. Water treated through the RO treatment plant at CP5 is moved to CP1 prior to treatment through the EWTP.

Contact water from the Underground Mine is collected in underground sumps, transported to a clarification system, and subsequently recirculated for use in various underground operations. Excess underground contact water is stored in temporarily inactive underground developments, and on surface in Saline Pond 1 (SP1) and Saline Pond 2 (SP2). Saline Pond 2 will be replaced by Saline Pond 4 (SP4) by Q2 2020 (further details found in WMP). Underground contact water that is not used for operations is treated at the Salt Water Treatment Plant (SWTP) or Saline Effluent Treatment Plant (SETP) for discharge.

As part of the strategy to manage excess groundwater infiltration of saline water within the underground portion of the mine, Agnico Eagle received approval from the Nunavut Impact Review Board to discharge saline water to sea (Melvin Bay, Rankin Inlet) with the amended Project Certificate on February 26, 2019.

During the mine closure, the water management infrastructure will remain in place until closure activities are completed and monitoring demonstrates that water quality is acceptable for discharge to the environment without treatment.

SECTION 3 • OVERVIEW OF MONITORING PROGRAMS

This Plan has been divided into two levels of monitoring to characterize the range of impacts between the sources of contact water in the individual mine facilities and the point of discharge or release to the receiving environment. The two levels of monitoring include:

1. Compliance Monitoring (CM); and
2. Event Monitoring (EM).

3.1 Compliance Monitoring Program (CM)

The CM sites are those stipulated in the License; these sites vary from contact water collection ponds, structures such as ditches, culverts prior to discharge to the receiving environment and local lakes surrounding the mine site. The requirements of the License, including water quality limits, will be applied at the applicable mine discharge points identified in the CM program.

The CM program provides a mechanism to assess water quality at specified sites, and to confirm and document compliance of discharge with regulatory requirements. As part of adaptive water management, these internal monitoring stations provide protection to the receiving water environment, provide data to predict pit re-flooding water quality and ensure exceedances of predicted or regulated levels are appropriately managed or mitigated to reduce impacts.

3.2 Event Monitoring Program (EM)

The EM sites result from unexpected events such as spills, accidents, and malfunctions. The response programs for such events are discussed in greater detail in the following four (4) documents:

- Meliadine Spill Contingency Plan (December 2019);
- Meliadine Emergency Response Plan (October 2018);
- Meliadine Freshet Action Plan (March 2020); and
- Meliadine Water Management Plan (March 2020).

Each accidental release will require mobilization of site equipment to stabilize the release, procedures to contain, neutralize, and dispose of the discharge, and recommendations for monitoring the site following the incident.

SECTION 4 • OVERVIEW OF MINE DEVELOPMENT SCHEDULE

The Mine Plan and key mine development activities, including mine waste management are currently used concurrently with the *Water Management Plan*.

The Mine Plan proposes one underground mine (Tiriganiaq Underground Mine) and two open pits (Tiriganiaq Open Pit 1 and Tiriganiaq Open Pit 2) for the development of the Tiriganiaq gold deposit.

The Mine is estimated to produce approximately 14.9 million tonnes (Mt) of ore, 31.8 Mt of waste rock, 7.4 Mt of overburden waste, and 14.9 Mt of tailings. The following phased approach is proposed for the development of the Tiriganiaq gold deposit;

- Phase 1: 3.5 years for Mine Construction. Construction began in 2015 and is estimated to be completed in Q2 of 2019 (Q4 Year -5 to Year Q2 -1);
- Phase 2: 8.5 years for Mine Operations, beginning in 2019 (Q2 Year -1 to Year 8);
- Phase 3: 3 years Mine Closure (Year 9 to Year 11); and;
- Phase 4: Post-Closure (Year 11 forward).

Mining facilities on surface will include a plant site and accommodation buildings, two ore stockpiles, a temporary overburden stockpile, a tailings storage facility (TSF), three waste rock storage facilities (WRSFs), a water management system that includes containment ponds, water diversion channels, retention dikes/berms, and a series of water treatment plants.

SECTION 5 • MONITORING PROGRAMS

The monitoring program is presented in three sections; requirements of the compliance monitoring program, an overview of the event monitoring program, and then details of the adaptive management program for monitoring results.

5.1 Compliance Monitoring Program

The CM program monitors the chemistry of four local lake surrounding the mine site (E3, G2, H1 and B5) as well as mine contact water collected and diverted at specified locations prior to release into the receiving water environment. The sampling is conducted in order to confirm and document compliance with regulatory requirements. The nature of water monitored within the CM program include:

- Non-contact water from local lakes;
- Mine contact water collected from drainage of different structures;
- Monitoring points located within the water management system prior to release into the receiving water environment; and
- Effluent released to Meliadine Lake and water within Meliadine Lake at the diffuser.

The CM sampling program has multiple monitoring stations across the project site, with sampling at different stages of the mine life. All of the CM stations, a description of their location, parameters to be monitored and sampling frequency are listed in Table 5.1. Specific details for the monitoring parameter groups are provided in Table 5.2. Agnico Eagle follows 5 groups of parameters as identified in the Type A Water License Schedule I, Table 1. Additionally, Agnico Eagle follows the analytical requirements and authorized limits of deleterious substances as identified in Schedule 3 and Schedule 4 of the MDMER (Government of Canada, 2002).

Figures 3.1 shows the approximate location of each of the sampling sites. The actual location of each sampling site is determined by access and safety considerations and are marked by a stake that defines the exact location of the collection point for sampling events with appropriate attached signage in English, Inuktitut and French.

GPS coordinates for all compliance monitoring stations were confirmed, as required in Part I, Item 6 of the NWB Type A water license.


5.1.1 General Sampling and Analysis Program

Samples are collected in clean laboratory-supplied containers and preserved as directed by the analytical laboratory. During all phases, samples are analyzed offsite at a CALA accredited commercial lab (ALS in Burnaby, BV Labs in Ottawa, AquaTox in Puslinch, H2Lab in Val d'Or, or Nautilus Environmental in Burnaby). Samples sent to commercial laboratories may change as the site matures and additional requirements occur. Sampling procedures are further detailed in Section 6 (Quality

Assurance/Quality Control Procedures) and in the Quality Assurance/Quality Control Plan (Agnico Eagle, 2019).

Table 5.3 summarizes the minimum sample volumes, container, preservation, and holding times for each analyte. This information is from the *USEPA Methods for Chemical Analysis of Water and Waste Water (EPA-600/4-79-020, 1983)*.

Figure 5.1: Sampling site locations



Q:\Edmonton\Engineering\E141\Projects\MELIADINE\2018 TSF & WRSF1\General Arrangement.dwg-2018-02-19 14:03:29

Table 5.1: Monitoring Program

Station	Description	Phase	Monitoring Parameters	Frequency
Mine Site				
MEL-D-1	Dewatering: Water transferred from lakes to Meliadine Lake during dewatering of lakes	Construction	As defined in the Water Management Plan referred to in Part D, Item 12	Prior to discharge and Weekly during discharge
			Volume (m3)	Daily during periods of discharge
MEL-SR-1 to TBD	Surface Runoff – runoff downstream of Construction areas at Meliadine Site and Itivia Site, Seeps in contact with the roads, earthworks and any Runoff and/or discharge from borrow pits and quarries	Construction, and Operation	As defined in the Water Management Plan referred to in Part D, Item 18 and Part I, Item 11	Prior to Construction, Weekly during Construction
			Group 1	Monthly during open water or when water is present upon completion
MEL-11	Water Intake from Meliadine Lake	Construction, Operation, and Closure	Full Suite	Monthly during periods of intake
			Volume (m3)	Daily during periods of intake
MEL-12	Water treatment plant (pre-treatment) coming from CP1, off the pipe and not in the pond	Construction (prior to release), Operations, and Closure	Group 1	Monthly during periods of discharge
MEL-03-01 (and AEMP Stations)	Mixing zone in Meliadine Lake, Station 1; and MDMER exposure stations for final discharge point within mixing zone	Construction (prior to release), Operations, and Closure	Full Suite, Group 3 (MDMER)	Monthly during periods of discharge
MEL-14	Water treatment plant from CP-1 (post-treatment), end of pipe (before offsite release) in the plant before release.	Construction (upon effluent release), Operations, and Closure	Full Suite, Group 3	Prior to discharge and weekly during periods of discharge



			Volume (m3)	Daily during periods of discharge
			Acute Lethality	Monthly during periods of discharge
MEL-15	Local lake E-3	Operations, and Closure	Group 2	Bi-annually during open water
MEL-16	Local Lake G2	Construction, Operations, and Closure	Group 2	Bi-annually during open water
MEL-17	Local Pond H1	Construction, Operations, and Closure	Group 2	Bi-annually during open water
MEL-18	Local Lake B5	Construction, Operations, and Closure	Group 2	Bi-annually during open water
MEL-19	CP-2 Collection of natural catchment drainage from the outer berm slopes of the Landfarm and industrial pad	Construction, Operations, and Closure	Group 1	Monthly during open water or when Water is present
MEL-20	CP-3 Collection of drainage from dry stacked tailings	Operations, and Closure	Group 1	Monthly during open water or when Water is present
MEL-21	CP-4 Collection of drainage from WRSF1	Operations, and Closure	Group 1	Monthly during open water or when Water is present
MEL-22	CP-5 Collection of drainage from WRSF1 and WRSF2	Construction, Operations, and Closure	Group 1	Monthly during open water or when Water is present
MEL-23	CP-6 Collection of drainage from WRSF3	Construction, Operations, and Closure	Group 1	Monthly during open water or when Water is present
MEL-24	Seepage from the Landfill between the landfill and Pond H3	Construction, Operations, and Closure	Group 1	Monthly during open water or when Water is present
MEL-25	Secondary containment area at the Itivia Site Fuel Storage and Containment Facility	Construction, Operation, Closure	Group 4, Volume (m3)	Prior to discharge or transfer of Effluent



MEL-26	Melvin Bay end of pipe (before offsite release) for treated saline effluent	Operations, and Closure	MDMER	As per MDMER requirements

Table 5.2: Monitoring Parameters

Group	Parameters
1	pH, turbidity, hardness, alkalinity, chloride, fluoride, sulphate, total dissolved solids (TDS), total suspended solids (TSS), total cyanide, ammonia nitrogen, nitrate, nitrite, phosphorus, orthophosphate, Total Metals (aluminum, arsenic, barium, cadmium, chromium, copper, iron, lead, manganese, mercury, molybdenum, nickel, selenium, silver, thallium, and zinc).
2	<p>Total and Dissolved Metals: aluminum, antimony, arsenic, barium, beryllium, boron, cadmium, chromium, copper, iron, lead, lithium, manganese, mercury, molybdenum, nickel, selenium, silver, strontium, thallium, tin, titanium, uranium, vanadium, and zinc.</p> <p>Nutrients: ammonia-nitrogen, total Kjeldahl nitrogen, nitrate-nitrogen, nitrite-nitrogen, orthophosphate, total phosphorus, total organic carbon, dissolved organic carbon, and reactive silica.</p> <p>Conventional Parameters: bicarbonate alkalinity, chloride, carbonate alkalinity, turbidity, conductivity, hardness, calcium, potassium, magnesium, sodium, sulphate, pH, total alkalinity, TDS, TSS, total cyanide, free cyanide, and weak acid dissociable (WAD) cyanide..</p>
3	<p>MDMER parameters: total cyanide, arsenic, copper, lead, nickel, zinc, radium-226, TSS, pH, total ammonia and temperature.</p> <p>MDMER additional requirements: Effluent volumes and flow rate of discharge, Acutely Lethality tests (Rainbow Trout and Daphnia magna) and environmental effects monitoring (EEM).</p>
4	Total arsenic, total copper, total lead, total nickel, TSS, ammonia, benzene, toluene, ethylbenzene, xylene, total petroleum hydrocarbons (TPH), and pH
Full Suite	Group 2, Total Petroleum Hydrocarbons, Turbidity. Non Acutely-lethal (Rainbow Trout and Daphnia magna) for discharge only.
Flow	Flow data-logger
Field measurements	Field pH, specific conductivity, dissolved oxygen, and temperature.

Table 5.3: Summary of Sampling Requirements for Each Analyte

Parameters	Matrix Holding Time				Type of Bottle	Preservative	Volume
	Drinking Water	Waste Water	Surface Water	Ground Water (1)			
Microbiology							
<i>Escherichia coli</i> , total coliforms, A.A.H.B	48h	48h	48h	48h	PPS	TS, E	250ml
Enterococcus	48h	48h	48h	48h	PPS	TS, E	250ml
Thermo tolerant coliforms (fecal)	48h	48h	48h	48h	PPS	TS, E	250ml
Inorganic Chemistry							
Absorbance UV, Transmittance UV				24h	P, T, V	N	125ml
Alkalinity, Acidity, Bicarbonates, Carbonates	14d	14d	14d	14d	P, T, V	N	250ml
Ammonia nitrogen (NH ₃ -NH ₄)	28d	28d	28d	28d	P, T, V	AS	125ml
Kjeldahl ammonia (NTK)		28d	28d	28d	P, T, V	AS	125ml
Anions (Cl, F, SO ₄)	28d	28d	28d	28d	P, T, V	N	250ml
Color, Free & total Chlorine	48h	48h	48h	48h	P, T, V	N	125ml
Conductivity	28d	28d	28d	28d	P, T, V	N	250ml
Cyanides total/available, Cyanides	14d	14d	14d	14d	P, T, V	NaOH	250ml
BOD ₅ /Carbonated BOD ₅ (2)		48h/4°	48h/4°		P, T, V	N	250ml
COD (chemical oxygen demand)		28d	28d		P, T, V	AS	125ml
Mercury (Hg)	28d	28d	28d	28d	P, T, V	AN	250ml
Total/dissolved metals (filtered on field)	180d	180d	180d	180d	P, T, V	AN	250ml
Dissolved Metals (filtered in the laboratory)	24h	24h	24h	24h	P, T, V	N	250ml
Total suspended solids & Volatile TSS		7d	7d	7d	P, T, V	N	500ml
NH ₃ or NH ₄		24h	24h	24h	P.T.V	N+AS	2/125ml
Nitrites (NO ₂), Nitrates (NO ₃), Turbidity	48h	48h	48h	48h	P, T, V	N	250ml
Nitrites-Nitrates (NO ₂ -NO ₃)	28d	28d	28d	28d	P, T, V	AS	250ml
O-Phosphates (O-PO ₄)	48h	48h	48h	48h	P, T, V	N	500ml
pH	24h	24h	24h	24h	P, T, V	N	125ml
Total Phosphorus (P-tot)	28d	28d	28d	28d	P, T, V	AS	125ml
Dissolved solids (TDS)		7d	7d	7d	P, T, V	N	250ml
Total solids		7d	7d	7d	P, T, V	N	250ml
Sulphides (H ₂ S) (3)	28d	28d	28d	28d	P, T, V	AcZn + NaOH	125ml
Thiosulfates	48h	48h	48h	48h	P, T, V	N	125ml
Radioactive & Organic Chemistry							
Fatty resin acids (S-T)	--	28d	28d	--	VA, VT	AS	1L
Congeners PCB (S-T)	28d	28d	28d	28d	VA, VT	N	1L
Chlorobenzene	28d	28d	28d	28d	2 Vial+1 blank	TSS	2/40ml
Total Organic Carbon (TOC)	28d	28d	28d	28d	P, T, V (B)	AC	100ml
Dissolved Organic Carbon (DOC)	48h	48h	48h	48h	P, T, V (B)	N	100ml
Total Inorganic Carbon (CIT)	48h	48h	48h	48h	P, T, V (B)	N	100ml
Phenolic compound (GC-MS)	28d	28d	28d	28d	VA, VT	AS	1L
Glyphosate (S-T)	14d	14d	14d	14d	P.T	N	500ml
PAH	28d	28d	28d	28d	VB	AS	1L
Oil & Greases (total and non-polar)	28d	28d	28d	28d	VA, VT	AS	1L

C10-C50 HP and/or Petroleum Product Identification	28d	28d	28d	28d	VA, VT	AS	1L
Phenol index	28d	28d	28d	28d	VA, VT	AS	500ml
Radium-226	180d	180d	180d	180d	P, T, V	AN	1L
VOC (MAH, CAH, THM, BTEX) (3)	28d	28d	28d	28d	2 Vial+1 blank	TSS	2/40ml

Type of bottle:

- P.S.V.T.: plastic bottle, bag or glass bottle with Teflon cap
- P, T: Plastic bottle or plastic bottle with Teflon cap
- P.T.V.: Plastic bottle or glass bottle with plastic or Teflon cap
- PPS: Sterile propyl ethylene bottle
- VA: Clear or amber glass with aluminium or Teflon seal
- VB: Amber glass (or clear glass covered with aluminium paper) aluminium seal of Teflon
- VT: Clear or amber glass bottle with Teflon seal

Preservative:

- AC: 0.1ml (100µl) of HCl per 100ml of sample
- AcZn: 0.2ml zinc acetate 2N per 100ml of sample and NaOH 10N to pH >9
- AN: HNO3 to pH <2
- AS: H2SO4 to pH <2
- E: 2.5ml EDTA 1.5% (p/v) per 100ml of sample if heavy metals are suspected
- ED: 0.1ml diamine ethylene 45 mg/l per 100 ml of sample
- EDTA: 1ml EDTA 0.25M per 100ml of sample
- N: No preservative
- NaOH: NaOH 10N to >12
- TS: Sodium thiosulfate final concentration in the sample of 0.1% (p/v)

5.1.2 Compliance Monitoring Stations and Discharge Criteria

Further details of the specific CM stations and discharge criteria stipulated under the License are provided below.

Dewatering Activities

All Waters from dewatering activities at Monitoring Program Stations MEL-D-1 through MEL-D-TBD shall be directed to Meliadine Lake and shall not exceed the quality limits presented in Table 3.4 as stipulated in Part D, Item 12 of the License.

Table 5.4: TSS and pH Criteria at CM Stations MEL-D-1 through MEL-D-TBD

Parameter	Maximum Concentration (mg/L)	Average Concentration of Any Grab Sample
TSS	15.0	30
pH	6.0 to 9.5	6.0 to 9.5

All surface runoff and/or discharge from drainage management systems, at the Monitoring Program Stations MEL-SR-1 to MEL-SR-TBD during the Construction/Operation of any facilities and infrastructure associated with this project, including laydown areas and All-weather Access Road, where flow may directly or indirectly enter a Water body, shall not exceed the Effluent quality limits presented in Table 5.5, as stipulated in Part D, Item 18 of the License.

Table 5.5: Effluent Criteria at CM Station MEL-SR-1 to MEL-SR-TBD

Parameter	Maximum Average Concentration	Maximum Concentration of Any Grab Sample
Total Suspended Solids (TSS) (mg/L)	50.0	100.0
Oil and Grease	No Visible Sheen	No Visible Sheen
pH	6.0 to 9.5	6.0 to 9.5

Site Water Collection System

Effluent discharged from CP1 at CM station MEL-14 shall be directed to Meliadine Lake through the Meliadine Lake Outfall Diffuser and shall not exceed the effluent quality limits presented in Table 5.6, as stipulated in Part F, Item 3 of the License.

Table 5.6: Effluent Criteria at CM Station MEL-14

Parameter	Maximum Average Concentration	Maximum Concentration of Any Grab Sample
pH	6.0 to 9.5	6.0 to 9.5
TSS (mg/L)	15	30
TDS (mg/L)	1400	1400
Total (T)-Al (mg/L)	2.0	3.0
T-As (mg/L)	0.3	0.6
T-CN (mg/L)	0.5	1
T-Cu (mg/L)	0.2	0.4
NH ₄ -N (mg/L)	14	18
T-Ni (mg/L)	0.5	1
T-Pb (mg/L)	0.2	0.4
T-P (mg/L)	2.0	4.0
T-Zn (mg/L)	0.4	0.8
Total Petroleum Hydrocarbons (TPH) (mg/L)	5	5

The Discharge of Effluent from the Final Discharge Point at Monitoring Program Station MEL-14 shall be demonstrated to be non-Acutely Lethal under the following test in accordance with the Schedule I of the License:

- a. Acute Lethality of Effluents to Rainbow Trout (as per Environment Canada's Environmental Protection Series Biological Test Method EPS/1/RM/13 July 1990, published by the Department of the Environment, as amended in December 2000, and as may be further amended from time to time.

Saline effluent discharged at CM station MEL-26 shall be directed to Melvin Bay through a submarine Pipeline and Diffuser and shall not exceed the effluent quality limits presented in Table 5.7, as stipulated in MDMER Schedule 4 (GC, 2002).

Table 5.7: Effluent Criteria at CM Station MEL-26

Parameter	Maximum Average Concentration	Maximum Concentration of Any Grab Sample
Arsenic (mg/L)	0.5	1.00
Copper (mg/L)	0.3	0.60
Cyanide (mg/L)	1.0	2.00
Lead (mg/L)	0.2	0.40
Nickel (mg/L)	0.5	1.00
Zinc (mg/L)	0.5	1.00
Total Suspended Solids (mg/L)	15.00	30.00
Radium 226 (Bq/L)	0.37	1.11

The Discharge of Effluent from the Final Discharge Point at Monitoring Program Station MEL-26 shall be demonstrated to be non-Acutely Lethal in accordance with MDMER Division 2, Item 14.2 (GC, MDMER), in which the testing shall be conducted in accordance with the procedures set out in section 5 or 6 of Reference Method EPS 1/RM/190.

Itivia Marshalling Area

Surface water runoff from the bulk fuel tank storage areas is collected within the tank's secondary containment enclosures that are equipped with an HDPE liner; these are designed to contain petroleum products released due to spill events. Water collected in the secondary containment enclosures at CM station MEL-25 is discharged to land in a controlled manner according to the Nunavut Water Board Type A water license # 2AM-MEL16331.

All effluent being discharged from the secondary containment enclosures at the Itivia marshalling facility shall not exceed the effluent quality limits presented in Table 5.8, as stipulated in Part F, Item 5 of the water license.

Table 5.8: Effluent Criteria at CM Station MEL-25

Parameter	Maximum Concentration	Average	Maximum Concentration of Any Grab Sample
pH	6.0 to 9.5		6.0 to 9.5
TSS (mg/L)	15.0		30.0
Benzene (ug/L)	370		370
Toluene (ug/l)	2		2
Ethylbenzene (ug/L)	90		90

Lead (mg/L)	0.1	0.1
Oil and Grease (mg/L)	5.0 and no visible sheen	5.0 and no visible sheen

Receiving Environment

Receiving water quality monitoring is discussed in the Aquatic Effects Management Program (AEMP) (Golder, 2016) and the Ocean Discharge Monitoring Plan (ODMP) (Agnico Eagle, 2020). Within the AEMP and ODMP are numerous monitoring programs: water quality, sediment quality, benthic invertebrate communities, and fish health and fish tissue chemistry. The Meliadine Lake and Melvin Bay monitoring programs were designed around the key aspects of Environmental Effects Monitoring (EEM) requirements under the Metal and Diamond Mining Effluent Regulations.

5.2 Event Monitoring

The Event Monitoring (EM) program addresses the site specific monitoring that is required following any accidental release. A “release” may be caused by:

- Spills, including unidentified seepage (Meliadine Spill Contingency Plan; December 2019); or
- Emergencies (Meliadine Emergency Response Plan; October 2018).

The EM program is designed to verify whether contamination of the surface soil and/or any nearby receiving environment and active zone has occurred as a result of an accidental release of a hazardous material or contaminated water. Verification is done through monitoring of surface runoff and nearby receiving environment during and following remedial activity. It is anticipated that due to the presence of permafrost beneath most of the mine footprint (active layer app 1.5m in depth), there will be minimal impact to groundwater from surface spills or accidental releases.

The EM plan is developed on a site specific basis subsequent to a spill or other incident, and considers the type of product spilled, the potential receptors and the potential for any remaining contamination after clean up. The plan is coordinated by the Environmental Department.

In the event of an accidental release, the water quality of any downstream receptor as well as an upstream reference (background) is sampled to determine severity of impact. Should the spill have happened over snow cover, as much contaminated snow will be removed as possible. Verification sampling would occur in the area after thaw to determine if the clean – up is complete or if further remediation is necessary. The specific parameters monitored as part of the EM program will depend on the nature of the spill, and will be determined for the specific material released.

The EM program for a particular spill will cease upon obtaining satisfactory analytical results from the potentially affected areas or as required by regulators.

5.3 Adaptive Management Program

Results of the water quality monitoring are reviewed by the Meliadine Environment Department. Chemical trends of constituents of interest are tracked for mine site monitoring and for the AEMP program. This allows for early detection of significant changes in water quality within the mine site prior to discharge. If

triggers and thresholds, such as in the AEMP program, are exceeded in the receiving environment action plans are then implemented to ensure that environmental protection objectives are met.

An adaptive management program has been designed for the Meliadine Gold Project to evaluate the monitoring data and provide a framework for action, if necessary. The program has two levels - a trigger level to compare the monitoring data against, and an action plan of mitigative measures for identified exceedances.

The adaptive management program is divided into two sections, one for parameters with regulated discharge criteria at specific monitoring locations, as specified in the License and by the Metal Diamond Mining Effluent Regulations (MDMER). The second section is for measured parameters for which no discharge limits have been identified in the License such as those in the AEMP or EEM.

5.3.1 Adaptive Management Program for Regulated Discharge

Action Plan

In the case of an exceedance of a License limit or MDMER discharge limit, an action plan will be implemented. The adaptive management program requires that if one or more of the key monitored parameters exceed the respective limits, a staged sequence of responses will follow. Table 5.9 summarizes the staged adaptive action plan for the CM program for regulated discharge. Figure 5.2 is a logic diagram showing the decision path for evaluating analytical results for regulated discharges.


In addition to the mitigative measures listed above, a number of other possible alternatives are available to reduce or treat contaminants. These mitigation measures include:

- Best management practices for sediment and erosion control would be employed to reduce TSS concentrations (i.e., flow control, sedimentation basin construction silt fencing, etc; see Sediment and Erosion Management Plan);
- Addition of a coagulant for the reduction of TSS in pond water;
- Use of geotextile or re-armoring of banks to filter and reduce TSS in pond/ditch water;
- Deployment of absorbent booms and/or barriers within ponds to isolate surface petroleum hydrocarbon films for removal and/or treatment;
- Adjustments to on-site sewage treatment for the reduction of BOD and E. coli concentrations;
- Addition of lime to increase a low pH value or reduce metal concentrations;
- Removal of the offending source rock or the prevention of surface waters coming into contact with the offending source rock in the case of ARD; and/or
- Implementation of the Freshet Action Plan to proactively identify any issues around areas of concern; conduct additional monitoring, and control and contain seepage or movement of TSS on site.

Table 5.9: Action Plan for Regulated Discharge

Example	Action Plan
Exceeds water discharge criteria or MDMER	<ol style="list-style-type: none"> 1. Suspension of discharge activities; 2. QA/QC review and analysis, and re-sample water at the particular location if necessary; 3. Notification of mine management (General Mine Manager or designate and Environment Superintendent, or designate) and the regulators: Nunavut Water Board, CIRNAC and ECCC inspectors, GN and the Kivalliq Inuit Association; 4. Investigation to identify possible source(s) and cause(s) of the exceedance; 5. Initiation of corrective actions or water treatment, and follow up monitoring; and 6. Resumption of discharge when concentrations are below the discharge criteria

Figure 5.2: Logic Diagram for Regulated Discharge



5.3.2 Adaptive Management Program for Non-Regulated Discharge

Aside from targeted monitoring studies (i.e. “Effects Assessment Studies”) such as those following construction, the AEMP is the main program aimed at measuring and assessing potential impacts of contaminants in the receiving aquatic environment that are not regulated under MDMER or NWB. This program combines with the Environmental Effects Monitoring (EEM) required under MDMER.

The program is designed to take an integrated, ecosystem-based approach that links mitigation and monitoring of physical/chemical effects to key ecological receptors in the receiving environment. It addresses key issues identified in the Meliadine EA (i.e., mining-related activities with the potential to affect water quality, fish habitat and fish populations). Monitoring results are intended to inform the “adaptive management” process”, supporting the early identification of potential problems and development of mitigation options to address them by comparing results to established threshold and trigger levels.

AEMP Action Level and Significance Threshold

The AEMP Response Framework links monitoring results to management actions, with the purpose of maintaining the assessment endpoints within acceptable ranges. It is a systematic approach for evaluating AEMP results and responding appropriately, such that potential unexpected effects are identified and mitigation is undertaken to reduce or reverse them, thereby preventing the occurrence of a significant adverse effect. This is accomplished by continually evaluating monitoring data and implementing follow-up actions (e.g., confirmation, further study, mitigation) at pre-defined levels of change in measurement endpoints (i.e., Action Levels). For purposes of this Response Framework, the following terms are used: effect, normal range, benchmark, Action Level, and Significance Threshold.

Action Level – Action Levels (Low, Moderate, and High) are pre-defined levels of environmental change that exceeds normal ranges or benchmarks, or results of statistical tests, or a combination of these. For example, exceedance of the normal range and approach of a benchmark by a water quality parameter in the near-field exposure area may be defined as the Low Action Level. A change that falls within the normal range of variability for the study area would not trigger an Action Level.

Significance Threshold – The Significance Threshold, for the purposes of an AEMP Response Framework, is a magnitude of change that would result in significant adverse effects. It is a clear statement of environmental change that must never be reached. The AEMP Response Framework is designed to prevent reaching the significance threshold for all assessment endpoints.

Action Levels

The proposed Action Levels are designed to provide an early warning indication of potential adverse effects to plankton and benthos (i.e., food for fish), to fish health, and to the assurance of normal ecological function (including water quality and sediment quality). The proposed Low Action Levels (Table 8-2 and 8-3) are designed such that changes of sufficient magnitude to trigger a Low Action Level response are reported, documented, investigated, and ultimately addressed (i.e., mitigation measures or operation

changes are implemented) before Significance Thresholds would ever be reached; if a Low Action Level is reached, Medium and High Action Levels (with response actions) are developed to provide further adaptive management guidance to the Mine to avoid reaching the Significance Thresholds. The type of management response taken after reaching an Action Level will depend on the type and magnitude of effect observed.

Further details on AEMP action levels and significance thresholds are provided in Golder (2016).

SECTION 6 • QUALITY ASSURANCE/QUALITY CONTROL PROCEDURES

Quality Assurance (QA) refers to plans or programs that encompass a wide range of internal and external management and technical practices designed to ensure the collection of data of known quality that matches the intended use of the data. Quality Control (QC) is a specific aspect of QA that refers to the internal techniques used to measure and assess data quality. Specific QA and QC procedures that will be followed during compliance-related sampling are described in Section 6.1 and 6.2 and are further detailed in the Quality Assurance/Quality Control Plan (Agnico Eagle, 2019).

6.1 Quality Assurance

Quality assurance protocols are diligently followed so data are of known, acceptable, and defensible quality. There are three areas of internal and external management, which are described in the following three sections.

6.1.1 Field Staff Training and Operations

To make certain that field data collected are of known, acceptable, and defensible quality, field staff are trained to be proficient in standardized field sampling procedures, data recording, and equipment operations applicable to the monitoring program. All field work will be completed according to specified instructions and established technical procedures for standard sample collection, preservation, handling, storage, and shipping protocols. Thus, minimizing risk of operational errors.

6.1.2 Laboratory

To make sure that high quality data are generated, external CALA accredited laboratories have been selected for sample analysis. Accreditation programs are utilized by the laboratories so that performance evaluation assessments are conducted routinely for laboratory procedures, methods, and internal quality control.

The assay lab at the Mine site is not an accredited laboratory but will be used periodically for “real-time” results for some parameters like pH, total suspended solids, and Weak Acid Dissociable Cyanide. These results are for observational purposes and do not meet the standards of an accredited laboratory.

6.1.3 Office Operations

A data management system is utilized so that an organized consistent system of data control, data analysis, and filing will be applied to the monitoring program. Relevant elements will include, but are not limited to the following:

- All required samples are collected;
- sampling stations are clearly identified, and GPS coordinates collected and stored;
- chain-of-custody and analytical request forms are completed correctly (as per Agnico Eagle 2019);

- proper labelling and documentation procedures are followed, and samples will be delivered to the appropriate locations in a timely manner;
- laboratory data will be promptly reviewed once they are received to validate data quality;
- appropriate logic checks will be completed to ensure the accuracy of the calculations.

6.2 Quality Control

The QC component consists of applicable field and sample handling procedures, and the preparation and submission of two types of QC samples to the various laboratories involved in the program. The QC samples include blanks (e.g., travel, field, equipment) and duplicate/split samples.

Sample bottle preparation, field measurement and sampling handling QC procedures include the following:

- New laboratory supplied containers are used for sample collection. The bottles are either polyethylene plastic or glass, dependent on the specific parameter being analyzed.
- Sample bottles are kept in a clean environment, capped at all times, and stored in clean shipping containers. Samplers keep their hands clean, wear gloves, and refrain from eating or smoking while sampling.
- All bottles are identified with station number and date of collection.
- Where sampling equipment must be reused at multiple sampling locations, sampling equipment is cleaned appropriately between locations.
- Temperature, pH, and specific conductivity are measured in the field using hand held meters such as HACH test kit – 2100 Q Portal Turbidimeter (turbidity), Oakton PCS35 Meter (pH and conductivity), and Eureka Manta II (pH, dissolved oxygen and conductivity). The instruments are calibrated before each sample event to ensure optimal performance and record of the calibration are kept in a Calibration log. Maintenance procedures will be followed as set out by the supplier's operation manual.
- Samples are cooled to between 4 °C and 10°C as soon as possible after collection, and maintained at approximately 4 °C in a refrigerator until shipping. Care is taken when packaging samples for transport to the laboratory to maintain the appropriate temperature (between 4°C and 10°C) and minimize the possibility of rupture. Where appropriate, samples are treated with laboratory-provided preservatives to minimize physical, chemical, biological processes that may alter the chemistry of the sample between sample collection and analysis.
- Samples are shipped to the laboratory as soon as reasonably possible to minimize sample hold times. If for any reason, samples do not reach the laboratory within the maximum sample hold time for individual parameters, the results of the specific parameters will be qualified, or the samples will not be analysed for the specific parameters.
- Chain of custody sample submission forms are completed by field sampling staff and submitted with the samples to the laboratory. Furthermore, an electronic copy is emailed to the laboratory upon shipping and a second electronic copy is maintained at the Mine Site for reference.

- Only staff with the appropriate training in the applicable sampling techniques conduct water sampling.

Quality control procedures implemented consist of the preparation and submission of QA/QC samples, such as field blanks, trip blanks, and duplicate water samples. These are defined as follows:

- **Field Blank:** A sample prepared in the field using laboratory-provided deionized water to fill a set of sample containers, which is then submitted to the laboratory for the same analysis as the field water samples. Field blanks are used to detect potential sample contamination during collection, shipping and analysis.
- **Travel Blank:** A sample prepared and preserved at the analytical laboratory prior to the sampling trip using laboratory-provided deionized water. The sample remains unopened throughout the duration of the sampling trip. Travel blanks are used to detect potential sample contamination during transport and storage.
- **Duplicate Sample:** Two samples collected from a sampling location using identical sampling procedures. They are labelled, preserved individually and submitted for identical analyses. Duplicate samples are used to assess variability in water quality at the sampling site. Duplicates are collected and submitted for analyses at approximately 10% of sampling locations. For smaller batches of samples (less than 10), at least one duplicate will be collected and submitted for analysis. Upon receipt of analytical results, the field/trip blank and duplicate analyses are verified for potential contamination and accuracy, respectively. Results are interpreted, and recommended actions are taken if necessary.

SECTION 7 • FLOW VOLUMES

Where applicable, flow volumes within the mine footprint will be measured daily during periods of discharge. Flow volume measurements will be conducted using volumetric flow meters attached to applicable pumps. For applicable permanent pumping arrangements, such as fresh water pumping systems, flows will be measured using permanent in line flow meters. For periodic batch discharges, such as secondary containment sumps, portable flow meters or calculated pump time and capacity methods will be used.

Detailed pump records are maintained including date, pond/sump number, receiving location of pumped water, pump ID, duration of pumping, and total volume pumped. The average flow rates, total discharge per event and total cumulative discharge will be reported annually.

The monitoring locations for water flow volumes, in accordance with Part I, Item 9, and Table 2 of the Water License, include:

- The volume of fresh Water obtained from Meliadine Lake at Monitoring Program Station MEL-11;
- The volume of fresh Water transferred to the Meliadine Lake during lakes' dewatering activities;
- The volume of fresh Water obtained along the road and Meliadine River for dust suppression activities;
- The volume of Effluent discharged from Final Discharge Point at Monitoring Program Station MEL-14;
- The volume of reclaim Water obtained from CP1;
- The volume of Effluent discharged onto tundra at Monitoring Program Station MEL-25 or transferred to CP1 from the Itivia Site Fuel Storage and Containment Facility; and
- The volume of Effluent and Fresh Water transferred to the pits during pits' flooding.

SECTION 8 • REPORTING

Reporting of water quality results is to be conducted on two levels a) monthly and annually with the results of the monitoring program and per MDMER requirements and b) in response to exceedances.

8.1 Annual Reporting

An annual report is to be submitted to the NWB, KIA, Department of Fisheries and Oceans, Crown-Indigenous Relations and Northern Affairs Canada, Nunavut Impact Review Board, Government of Nunavut, and other interested parties by March 31st of the following year. The report is to summarize the following:

- Monitoring results for each sampling station during the year and for the life of mine (construction to end of closure); activities during the year at each station; and any exceedances at stations, the action plan applied to the exceedance, and the results of the action plan;
- Annual seep water chemistry results; including location of the samples, sources of the water collected, and results of chemical analyses of the samples;
- Receiving water monitoring results;
- Spills and any accidental releases; event monitoring activities conducted following containment, remediation, and reclamation; and the results of EM program, any exceedance in EM results, and the action plan following the exceedance;
- Measured flow volumes;
- Effluent flow rates, volumes and calculated chemical loadings following the requirements of MDMER; and
- Results of QA/QC analytical data.

8.2 Exceedance Reporting

Any measured concentration at a CM station exceeding a regulated discharge criterion stipulated in the License or MDMER will be reported to the NWB and Environment Canada and Climate Change upon receipt of the analysis. In addition, results of the action plan will be reported and, where necessary, mitigation options identified within 90 days after receipt of the analyses.

Exceedances in the concentration of a parameter in receiving water will be reported as specified in the AEMP and EEM – MDMER accordingly.

SECTION 9 • REFERENCES

Agnico Eagle. 2019. Meliadine Gold Project Quality Assurance/Quality Control Plan. Version 3. 6513-QQY-01. March 2019.

Agnico Eagle. 2020. Meliadine Gold Project Water Management Plan. Version 9. 6513-MPS-11. March 2020.

Environmental Protection Agency (EPA). 1983. Methods for Chemical Analysis of Water and Wastes. EPA/600/4-79/020. March 1983.

Golder Associates Ltd. 2016. Aquatic Effects Monitoring Program (AEMP) Design Plan. Version 1. June 2016. 6513-REP-03.

Government of Canada. (2002). Metal and Diamond Mining Effluent Regulations. SOR/2002-222. Minister of Justice of Canada. Current to February 26, 2020, last amended on June 25, 2019.