

Appendix 2

Meadowbank KVPL08D280 2022 Mine Plan



AGNICO EAGLE

MEADOWBANK GOLD PROJECT

**Production Lease KVPL08D280
2022 Mine Plan**

January 2022

EXECUTIVE SUMMARY

Condition 5.09 of Production Lease KVPL08D280 for the Meadowbank Gold Project states:

On or before January 1st in each year of the Term, Agnico Eagle shall deliver to KIA its annual Mine Plan for the next calendar year, detailing at least the following:

- (i) a description of the activities and work that Agnico Eagle proposes to perform in that year on the Leased Land, together with a listing of major equipment to be brought onto the Leased Land; and*
- (ii) a description of the topographical features and any natural or manmade features, structures, works and waters that may be affected.*

This document presents the 2022 Annual Mine Plan for the Meadowbank Gold Project.

The Meadowbank gold mine began the operation phase of the project in February 2010, and thus, is entering its twelfth year of operations. In addition to routine activities throughout the 2022 season, several secondary construction/modification projects will be undertaken near the main mine site area. Tailings will be mainly deposited in the pit (Portage Pit A and the Portage Pit E). If necessary, tailings deposition may occur in Portage Pit A, Goose Pit and in the North and South Cell to optimize the landform.

Environmental monitoring (wildlife, aquatic effects, groundwater, noise and air) will continue through 2022 in support of all operational undertakings at the Meadowbank site as required by the NWB Type A Water License 2AM-MEA1530 Amendment No. 4, NIRB Project Certificate No.004, DFO authorizations and MDMER regulations.

TABLE OF CONTENT

SECTION 1 •	INTRODUCTION	6
SECTION 2 •	2022 PLANNED EXPLORATION ACTIVITIES.....	7
SECTION 3 •	2022 PLANNED CONSTRUCTION ACTIVITIES.....	8
3.1	Dike construction and tailings management	8
SECTION 4 •	2022 PLANNED OPERATION ACTIVITIES	9
4.1	Mining Plan.....	9
4.1.1	Portage Pit	9
4.1.2	Goose Pit	9
4.1.3	Vault Pit	9
4.1.4	Phaser and BB Phaser Pit.....	9
4.2	Waste Rock Management Plan.....	9
4.3	Equipment	10
SECTION 5 •	2022 PLANNED ENVIRONMENTAL MONITORING.....	25
5.1	Wildlife Monitoring	25
5.1.1	Terrestrial Advisory Group	25
5.1.2	Harvest Study	25
5.1.3	Habitat mapping.....	25
5.1.4	Breeding Bird Plot Surveys.....	25
5.1.5	Raptor Nest Surveys.....	26
5.1.6	Caribou Satellite-Collaring Program	26
5.1.7	Checklist Surveys and Wildlife Logs.....	26
5.1.8	AWAR and Mine-Site Road Surveys	26
5.1.9	Screening Level Risk Assessment	27
5.2	Aquatic Effects Monitoring Program.....	27
5.2.1	Core Receiving Environment Monitoring (CREMP)	27
5.2.2	Metal and Diamond Mining Effluent Regulations (MDMER) Monitoring	27
5.2.3	Water Quality and Flow Monitoring	28
5.2.4	Habitat Compensation Monitoring Program	28
5.2.5	Seepage Water from Waste Rock Storage Facility	31
5.2.6	Assay Road Seepage.....	31
5.2.7	Central Dike Seepage.....	31
5.2.8	Blast Monitoring	31
5.3	Groundwater Monitoring Program	32
5.4	Noise Monitoring Program.....	32
5.5	Air Monitoring Program	32
SECTION 6 •	LOGISTICS.....	33

SECTION 7 •	2022 PROGRESSIVE RECLAMATION PLAN	34
--------------------	--	-----------

LIST OF TABLES

Table 4-1 Equipment at Meadowbank and Whale Tail in 2022	10
--	----

LIST OF FIGURES

Figure 1: Meadowbank Mine Site 2022 Sampling Locations	29
Figure 2 : Vault 2022 Sampling Locations	30

SECTION 1 • INTRODUCTION

The Meadowbank gold mine began the operation phase of the project in February 2010, and thus, is entering its thirteenth year of operations. In addition to routine activities throughout the 2022 season, several secondary construction/modification projects will be undertaken near the main mine site area. Tailings will be deposited in Portage Pit A and Portage Pit E. If required, tailings deposition may occur in the South Cell and the North Cell to optimize the landform.

The following sections outline the exploration, construction, operation, and environmental activities planned for 2022 at the Meadowbank Gold Project, conducted in accordance with Production Lease KVPL08D280.

SECTION 2 • 2022 PLANNED EXPLORATION ACTIVITIES

The 2022 exploration program for the Meadowbank Project area will be conducted by the Meadowbank Geology Department of Agnico Eagle Mines Ltd within the Production Lease KVPL08D280 in 2022.

- Exploration activities:
 - o Exploration drilling outside of the defined historic ore reserves & resources of Goose, Portage, and Vault deposits; and
 - o Geotechnical and hydrogeological drilling.

SECTION 3 • 2022 PLANNED CONSTRUCTION ACTIVITIES

Construction activities at the Meadowbank mine are mainly completed. There are several secondary projects and modifications to existing infrastructure that will continue in 2022, including progressive reclamation of the site.

- the following construction activities:
 - o HPGR building (completion);
 - o ABF garage move (East Dike to FGL); and
 - o Construction, maintenance and modification of operation buildings
- potential construction activities:
 - o Addition of Leach tank;
 - o 3M liters fuel tank at Meadowbank;
 - o Airstrip work (widening, raising, building moves) due to new Transport Canada regulations; and
 - o De-energizing of old buildings for fuel optimization (fountain tire building, environment office, etc.)

3.1 DIKE CONSTRUCTION AND TAILINGS MANAGEMENT

Tailings will be deposited in the Portage Pits. Some tailings deposition might occur in the South Cell and the North Cell using the existing infrastructure to optimize the landform. Dike construction and water management activities will include the following:

- In-pit deposition. Portage Pit E will be the main area used, with Pit A and Goose Pit being available as contingency;
- Transfer of water from Goose Pit and Portage Pit E to Portage Pit A;
- Reclaim of water from Portage Pit A and Portage Pit E;
- Continue using the North Cell and South cell for tailings deposition to optimise landform (if deemed necessary);
- Minor remediation work at the North Cell of the Tailings Storage Facility; and
- Capping with NPAG a portion of the North tailings cell based on availability of equipment and material.

SECTION 4 • 2022 PLANNED OPERATION ACTIVITIES

4.1 MINING PLAN

No mining activity is planned to occur in 2022 at Meadowbank under the current LOM.

4.1.1 Portage Pit

The Ultimate Phase of Portage Pit was completed in 2019 therefore no production/mining is planned in 2022 under the current LOM.

4.1.2 Goose Pit

Goose pit was depleted in 2014, therefore no production/mining is planned in 2022 under the current LOM.

4.1.3 Vault Pit

Vault pit was depleted in 2019, therefore no production/mining is planned in 2022 under the current LOM.

4.1.4 Phaser and BB Phaser Pit

Phaser pit was depleted in 2018, therefore no production/mining is planned in 2022 under the current LOM.

BB Phaser pit was completely depleted in 2019, therefore no production/mining is planned in 2022 under the current LOM

4.2 WASTE ROCK MANAGEMENT PLAN

As no mining is planned to occur in Meadowbank in 2022 there is no waste rock planned to be managed.

The final capping of the landfill within the WRSF may be completed in 2022.

4.3 EQUIPMENT

Table 4-1 lists the major equipment's that will be used or brought at Meadowbank and Whale Tail sites in 2022. Some of this equipment will be shared between the two sites.

Two Long-Haul truck will be added to the fleet in 2022 to follow the underground mine start-up.

Table 4-1 Equipment at Meadowbank and Whale Tail in 2022

Manufacturer	Unit Number	Description
HONDA	61ATV01	HONDA ATV
HONDA	61ATV02	HONDA ATV
HONDA	61ATV03	HONDA ATV
HONDA	61ATV04	HONDA ATV
HONDA	61ATV05	HONDA ATV
CAN AM	61ATV06	BRP OUTLANDER ATV 4X4
SHERP	61ATV07	SHERP ATV
CATERPILLAR	61BAC03	BACKOE CATERPILLAR 307
CATERPILLAR	61BAC04	BACKOE CATERPILLAR 330D
CATERPILLAR	61BAC07	BACKOE CATERPILLAR 345DL
CATERPILLAR	61BAC09	BACKOE 390DL CATERPILLAR
TEREX	61BAC10	BACKOE TEREX O&K RH120-E
TEREX	61BAC11	BACKOE BUCYRUS RH120-E
CATERPILLAR	61BAC13	BACKOE CAT6030
CATERPILLAR	61BAC14	BACKOE CAT 6020B
CATERPILLAR	61BAC15	BACKOE CAT 6015B
KUBOTA	61BAC16	KUBOTA MINI-SHOVEL
CATERPILLAR	61BAC17	BACKOE CATERPILLAR 336
CATERPILLAR	61BAC18	BACKOE CAT 6015B
CATERPILLAR	61BAC19	BACKOE CAT 390DL
LEGEND	61BOA01	LEGEND OUTBOARD BOAT
MACLEAN	61BOL01	BOLTER MACLEAN MEM-975
MACLEAN	61BOL02	BOLTER MACLEAN MEM-975
MACLEAN	61BOL03	BOLTER MACLEAN MEM-975
INTERNATIONAL	61BUS01	BUS YELLOW BLUE BIRD
FORD MOTOR COMPANY	61BUS02	MINIBUS BLUE BIRD
FORD MOTOR COMPANY	61BUS03	MINIBUS BLUE BIRD
FORD MOTOR COMPANY	61BUS04	BAKER LAKE PASSANGER VAN E350
FORD MOTOR COMPANY	61BUS05	BUS RED BLUE BIRD
FORD MOTOR COMPANY	61BUS06	BAKER LAKE MINI BUS
INTERNATIONAL	61BUS08	BLUE BIRD BUS

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

INTERNATIONAL	61BUS09	BUS YELLOW BLUE BIRD
INTERNATIONAL	61BUS10	USED INTERNATIONAL BUS
INTERNATIONAL	61BUS11	BLUE BIRD BUS
INTERNATIONAL	61BUS12	BLUE BIRD BUS
CHEVROLET	61BUS13	EXPRESS 4500 CHEVY BUS
INTERNATIONAL	61BUS14	BLUE BIRD BUS
INTERNATIONAL	61BUS15	BLUE BIRD BUS
	61BUS16	BLUE BIRD BUS
HYSTER	61CLD01	CONTAINER HANDLER HYSTER RS46
HYSTER	61CLD02	CONTAINER HANDLER HYSTER RS46
HYSTER	61CLD03	CONTAINER HANDLER HYSTER RS46
CATERPILLAR	61CPT01	CATERPILLAR COMPACTOR CS76
CATERPILLAR	61CPT02	CATERPILLAR COMPACTOR CS563
CATERPILLAR	61DOZ01	DOZER D8T CATERPILLAR
CATERPILLAR	61DOZ02	DOZER D9T CATERPILLAR
CATERPILLAR	61DOZ05	DOZER D9T CATERPILLAR
CATERPILLAR	61DOZ06	DOZER D9T CATERPILLAR
CATERPILLAR	61DOZ07	DOZER D9T CATERPILLAR
CATERPILLAR	61DOZ08	DOZER 834H CATERPILLAR
CATERPILLAR	61DOZ09	DOZER D6T CATERPILLAR
CATERPILLAR	61DOZ10	DOZER D6 20VP CATERPILLAR
CATERPILLAR	61DOZ11	DOZER D10T CATERPILLAR
CATERPILLAR	61DOZ12	DOZER D10T CATERPILLAR
HYSTER	61FKL02	FORK LIFT HYSTER RH35
CATERPILLAR	61FKL03	FORK LIFT WAREHOUSE CAT
CATERPILLAR	61FKL05	MILL FORK LIFT CAT
CATERPILLAR	61FKL06	TRUCK SHOP FORKLIFT CAT DP40KL
RAYMOND	61FKL07	RAYMOND LIFT 740DR32IT
RAYMOND	61FKL08	RAYMOND LIFT ETR40TT
CATERPILLAR	61FKL09	TRUCK SHOP FORKLIFT HYSTER
CATERPILLAR	61FKL10	ZOOM BOOM TL1255C CAT
CATERPILLAR	61FKL11	FORK LIFT R80 CAT
YALE	61FKL12	YALE FORK LIFT GDP155VX
JUNGHEINRICH	61FKL13	FORKLIFT ETR335DA
JUNGHEINRICH	61FKL14	FORKLIFT DP70N1
CATERPILLAR	61FKL15	FORKLIFT 2ET4000 CAT
CATERPILLAR	61FKL16	FORKLIFT EP4000 CATERPILLAR
CATERPILLAR	61FKL17	FORKLIFT DP40N1 CAT
CATERPILLAR	61FKL18	FORKLIFT DP70N CAT

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

CATERPILLAR	61GEN08	CATERPILLAR 3508 GENSET
CUMMINS	61GEN09	CUMMINS GEN SET 6CT, TWIN
CUMMINS	61GEN10	CUMMINS GEN SET 6CT, TWIN
CATERPILLAR	61GEN13	CATERPILLAR GENSET 200KW D200P
CATERPILLAR	61GEN16	CATERPILLAR GENSET 30KW D30-8
CATERPILLAR	61GEN37	JOHN DEERE MODEL 6081AF001
CATERPILLAR	61GRA01	MOTOR GRADER 16H CAT
CATERPILLAR	61GRA02	MOTOR GRADER 160H CAT
CATERPILLAR	61GRA03	MOTOR GRADER 16M CAT
CATERPILLAR	61GRA04	MOTOR GRADER 16M CAT
CATERPILLAR	61GRA06	CATERPILLAR GRADER 16M
CATERPILLAR	61GRA07	CATERPILLAR GRADER 14M
CATERPILLAR	61GRA08	GRADER CAT UG20M
CATERPILLAR	61GRA09	CATERPILLAR GRADER 14M
CATERPILLAR	61GRA10	CATERPILLAR GRADER 14M
CATERPILLAR	61GRA11	CATERPILLAR GRADER 14M
TRAMAC	61HAM01	HYDRAULIC BREAKER HAMMER
TRAMAC	61HAM02	HYDRAULIC BREAKER HAMMER
TRAMAC	61HAM03	HYDRAULIC BREAKER HAMMER
CATERPILLAR	61HTR01	HAUL TRUCK 100T CATERPILLAR
CATERPILLAR	61HTR02	HAUL TRUCK 100T CATERPILLAR
CATERPILLAR	61HTR03	HAUL TRUCK 100T CATERPILLAR
CATERPILLAR	61HTR04	HAUL TRUCK 100T CATERPILLAR
CATERPILLAR	61HTR05	HAUL TRUCK 100T CATERPILLAR
CATERPILLAR	61HTR06	HAUL TRUCK 100T CATERPILLAR
CATERPILLAR	61HTR07	HAUL TRUCK 100T CATERPILLAR
CATERPILLAR	61HTR08	HAUL TRUCK 100T CATERPILLAR
CATERPILLAR	61HTR09	HAUL TRUCK 50T CATERPILLAR
CATERPILLAR	61HTR11	HAUL TRUCK 777F CATERPILLAR
CATERPILLAR	61HTR12	HAUL TRUCK 777F CATERPILLAR
CATERPILLAR	61HTR14	HAUL TRUCK 777F CATERPILLAR
CATERPILLAR	61HTR15	WATER TRUCK 773D CATERPILLAR
CATERPILLAR	61HTR16	HAUL TRUCK 777F CATERPILLAR
CATERPILLAR	61HTR17	HAUL TRUCK 777F CATERPILLAR
CATERPILLAR	61HTR20	HAUL TRUCK 150T CATERPILLAR
CATERPILLAR	61HTR21	HAUL TRUCK 150T CATERPILLAR
CATERPILLAR	61HTR22	HAUL TRUCK 150T CATERPILLAR
CATERPILLAR	61HTR23	HAUL TRUCK 150T CAT 785D
CATERPILLAR	61HTR24	HAUL TRUCK 150T CAT 785D

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

CATERPILLAR	61HTR25	HAUL TRUCK 150T CAT 785D
CATERPILLAR	61HTR26	HAUL TRUCK 150T CAT 785C
CATERPILLAR	61HTR28	HAUL TRUCK 150T CAT 785C
CATERPILLAR	61HTR29	HAUL TRUCK 150T CAT 785D 2011
CATERPILLAR	61HTR30	HAUL TRUCK 150T CAT 785D 2011
CATERPILLAR	61HTR31	HAUL TRUCK 150T CAT 785D
CATERPILLAR	61HTR32	HAUL TRUCK 150T CAT 785D
CATERPILLAR	61HTR33	HAUL TRUCK 150T CAT 785D
CATERPILLAR	61HTR34	HAUL TRUCK 150T CAT 785D
CATERPILLAR	61HTR35	U/G TRUCK AD30 CAT
CATERPILLAR	61HTR36	U/G TRUCK CAT AD30
CATERPILLAR	61HTR37	U/G TRUCK CAT AD30
CATERPILLAR	61HTR38	U/G TRUCK CAT AD30
SANDVIK	61HTR41	U/G TRUCK SANDVIK TH551I
SANDVIK	61HTR42	U/G TRUCK SANDVIK TH551I
CATERPILLAR	61HTR43	HAUL TRUCK 150T CAT 785D
CATERPILLAR	61HTR44	HAUL TRUCK 150T CAT 785D
SANDVIK	61HTR45	U/G TRUCK SANDVIK TH551I
HONDA	61HYD01	ERT HONDA HYDRAULIC UNIT
HONDA	61HYD02	FIRE TRUCK HONDA HYDR UNIT
ATLAS COPCO	61JUM01	JUMBO DRILL 281
SANDVIK	61JUM02	JUMBO DRILL DD421
SANDVIK	61JUM03	JUMBO DRILL DD421I
INGERSOLL RAND	61LGT02	INGERSOLL RAND L20 TOWER LIGHT
INGERSOLL RAND	61LGT03	INGERSOLL RAND L20 TOWER LIGHT
INGERSOLL RAND	61LGT04	INGERSOLL RAND L20 TOWER LIGHT
INGERSOLL RAND	61LGT05	INGERSOLL RAND L20 TOWER LIGHT
INGERSOLL RAND	61LGT06	INGERSOLL RAND L20 TOWER LIGHT
INGERSOLL RAND	61LGT07	INGERSOLL RAND L20 TOWER LIGHT
WACKER NEUSON	61LGT14	LGT WACKER LTC4L
KENWORTH	61LHT01	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT02	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT03	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT04	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT05	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT06	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT08	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT09	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT10	KENWORTH TRUCK C500 6X6

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

KENWORTH	61LHT11	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT12	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT13	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT14	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT15	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT16	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT17	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT18	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT19	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT20	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT21	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT22	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT23	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT24	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT25	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT26	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT27	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT28	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT29	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT30	KENWORTH TRUCK C500 6X6
KENWORTH	61LHT31	KENWORTH TRUCK C500 6X6
CATERPILLAR	61LOA01	LOADER IT14G CAT
CATERPILLAR	61LOA02	LOADER IT14G CAT
CATERPILLAR	61LOA03	LOADER 992G CATERPILLAR
CATERPILLAR	61LOA04	LOADER 992G CATERPILLAR
CATERPILLAR	61LOA05	LOADER 420E IT CAT (PEPINE)
CATERPILLAR	61LOA06	LOADER 966H CATERPILLAR-AMARUQ
JOHN DEERE	61LOA08	LOADER TC44H JOHN DEERE
CATERPILLAR	61LOA09	LOADER 966H CATERPILLAR
CATERPILLAR	61LOA10	LOADER 980H CATERPILLAR
CATERPILLAR	61LOA11	LOADER 420E CATERPILLAR-AMARUQ
CATERPILLAR	61LOA12	LOADER 980H CATERPILLAR
CATERPILLAR	61LOA13	WHEEL LOADER 992K CATERPILLAR
KOMATSU	61LOA14	TIRE HANDLER LOADER
CATERPILLAR	61LOA15	LOADER 980K CATERPILLAR
CATERPILLAR	61LOA16	LOADER IT14G CATERPILLAR
CATERPILLAR	61LOA18	LOADER 966H CATERPILLAR
CATERPILLAR	61LOA19	LOADER 980K CATERPILLAR
CATERPILLAR	61LOA20	LOADER CAT 420FIT

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

CATERPILLAR	61LOA21	LOADER 918M CATERPILLAR
CATERPILLAR	61LOA22	LOADER 930G CATERPILLAR
CATERPILLAR	61LOA23	LOADER 924K CATERPILLAR
CATERPILLAR	61LOA24	LOADER 420F IT CATERPILLAR
CATERPILLAR	61LOA25	STEMMING LOADER 914M CAT
CATERPILLAR	61LOA26	LOADER 988K HL CATERPILLAR
CATERPILLAR	61LOA27	LOADER 988K HL CATERPILLAR
CATERPILLAR	61LOA28	LOADER 914M CATERPILLAR
CATERPILLAR	61LOA29	LOADER 980M CATERPILLAR
CATERPILLAR	61LOA30	LOADER 980M CATERPILLAR
MANITOWOC	61MCR01	CRANE 120T MANITOWOC
TEREX	61MCR02	CRANE 80T TEREX
GROVE	61MCR03	CRANE 35T GROVE
INTERNATIONAL	61MCR05	25T INTERNATIONAL BOOM TRUCK
	61MCR06	CRANE 200T AMERICAN
LINKBELT	61MCR08	CRANE 300T LINK BELT
	61MFT01	MOBILE FUEL TANKER TRAILER
	61MFT02	MOBILE FUEL TANKER TRUCK
FORD MOTOR COMPANY	61PCK01	PICK UP F350 (MILL)
FORD MOTOR COMPANY	61PCK03	PICK UP F350 (MILL MNTCE)
FORD MOTOR COMPANY	61PCK04	PICK UP F350 (PROCESS PLANT)
FORD MOTOR COMPANY	61PCK05	PICK UP F350 (BLASTER)
FORD MOTOR COMPANY	61PCK06	PICK UP F350 (POWER PLANT)
FORD MOTOR COMPANY	61PCK08	PICK UP F350 (MILL MNTCE)
FORD MOTOR COMPANY	61PCK09	PICK UP F350 (ENGINEERING)
FORD MOTOR COMPANY	61PCK10	PICK UP F350 (DEWATERING)
FORD MOTOR COMPANY	61PCK100	PICK-UP F250
FORD MOTOR COMPANY	61PCK101	PICK-UP F250
FORD MOTOR COMPANY	61PCK102	PICK-UP F250
FORD MOTOR COMPANY	61PCK103	PICK-UP F250
FORD MOTOR COMPANY	61PCK104	PICK-UP F250
FORD MOTOR COMPANY	61PCK105	ACE SERVICE TRUCK #ACE106
FORD MOTOR COMPANY	61PCK106	SANVIK SERVICE TRUCK
FORD MOTOR COMPANY	61PCK107	PICK-UP F250
FORD MOTOR COMPANY	61PCK108	PICK-UP F250
FORD MOTOR COMPANY	61PCK109	PICK-UP F250
FORD MOTOR COMPANY	61PCK11	PICK UP F350
FORD MOTOR COMPANY	61PCK110	PICK-UP F250
FORD MOTOR COMPANY	61PCK111	PICK-UP F250

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

FORD MOTOR COMPANY	61PCK112	PICK-UP F250
FORD MOTOR COMPANY	61PCK113	PICK-UP F250
FORD MOTOR COMPANY	61PCK114	PICK-UP F250
FORD MOTOR COMPANY	61PCK115	PICK-UP F250
FORD MOTOR COMPANY	61PCK116	PICK-UP F250
FORD MOTOR COMPANY	61PCK117	PICK-UP F250
FORD MOTOR COMPANY	61PCK118	PICK-UP F250
FORD MOTOR COMPANY	61PCK119	PICK-UP F250
FORD MOTOR COMPANY	61PCK12	PICK UP F350 (WAREHOUSE)
FORD MOTOR COMPANY	61PCK120	PICK-UP F250
FORD MOTOR COMPANY	61PCK121	PICK-UP F250
FORD MOTOR COMPANY	61PCK122	PICK-UP F250
FORD MOTOR COMPANY	61PCK123	PICK-UP F350
FORD MOTOR COMPANY	61PCK124	PICK-UP F350
FORD MOTOR COMPANY	61PCK125	PICK-UP F350
FORD MOTOR COMPANY	61PCK126	PICK-UP F350
FORD MOTOR COMPANY	61PCK127	PICK-UP F350
FORD MOTOR COMPANY	61PCK128	PICK-UP F550
FORD MOTOR COMPANY	61PCK129	PICK-UP F550
FORD MOTOR COMPANY	61PCK130	PICK-UP F250 TOROMONT
FORD MOTOR COMPANY	61PCK14	EXPEDITION XLT MOB.MNTCE SUP.
FORD MOTOR COMPANY	61PCK15	PICK UP F350 (MOB.MNTCE CRANE)
FORD MOTOR COMPANY	61PCK16	PICK UP F350 (BLASTER)
FORD MOTOR COMPANY	61PCK17	PICK UP F350 WAREHOUSE
FORD MOTOR COMPANY	61PCK18	PICK UP F350 (GEOLOGY)
FORD MOTOR COMPANY	61PCK19	PICK UP F250 (MOBILE MNTCE)
FORD MOTOR COMPANY	61PCK20	PICK UP F250 (ENVIRONMENT)
FORD MOTOR COMPANY	61PCK22	PICK UP F250 (MINE RESUCE)
FORD MOTOR COMPANY	61PCK23	PICK UP F250 (ELECT MILL)
FORD MOTOR COMPANY	61PCK24	PICK UP F250 MINE HELP/BIT SHO
FORD MOTOR COMPANY	61PCK25	PICK UP F250 MINE HELP/BIT SHO
FORD MOTOR COMPANY	61PCK26	PICK UP F250 (SITE SERV FIELD)
FORD MOTOR COMPANY	61PCK27	PICK UP F250 (SITE SERVICE)
FORD MOTOR COMPANY	61PCK28	PICK UP F250 (DYKE SUPER.)
FORD MOTOR COMPANY	61PCK30	PICK UP F250 DIKES /DEWATERING
FORD MOTOR COMPANY	61PCK31	PICK UP F250 (MILL)
FORD MOTOR COMPANY	61PCK32	PICK UP F250 (ELECT. DEPT.)
FORD MOTOR COMPANY	61PCK33	PICK UP F250 (ENGINEERING)
FORD MOTOR COMPANY	61PCK34	PICK UP F250 SECURITY ON SITE

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

FORD MOTOR COMPANY	61PCK35	PICK UP F250 (ROAD CREW)
FORD MOTOR COMPANY	61PCK36	PICK UP F250 (ROAD CREW)
FORD MOTOR COMPANY	61PCK37	PICK UP F250 (EXPLORATION)
FORD MOTOR COMPANY	61PCK38	PICK UP F250 (EXPLORATION)
FORD MOTOR COMPANY	61PCK39	PICK UP E350 AMBULANCE
FORD MOTOR COMPANY	61PCK40	PICK UP (IT GREY RENTAL)
FORD MOTOR COMPANY	61PCK41	PICK UP F250 (P.A BOSSE)
FORD MOTOR COMPANY	61PCK42	PICK UP F250 (FIELD TEAM LEAD)
FORD MOTOR COMPANY	61PCK43	PICK UP F350 (CONSTRUCTION)
FORD MOTOR COMPANY	61PCK45	PCK F350 2011 (BLASTER PICK)
FORD MOTOR COMPANY	61PCK46	PCK F250 2011 GEOLOGY
FORD MOTOR COMPANY	61PCK47	PCK F250 2011 PIT PROD. SUP.
FORD MOTOR COMPANY	61PCK51	PCK F250 2012 (S.S FIELD SERV)
FORD MOTOR COMPANY	61PCK52	PCK F450 2011 (WAREHOUSE)
FORD MOTOR COMPANY	61PCK53	PICK UP F250 (PROCESS PLANT)
FORD MOTOR COMPANY	61PCK54	PICK UP F250 (ENGINEERING)
FORD MOTOR COMPANY	61PCK55	PICK UP F250 (SURVEY)
FORD MOTOR COMPANY	61PCK56	PICK UP F250 (GEOLOGY)
FORD MOTOR COMPANY	61PCK57	PICK UP F250 (ROAD CREW)
FORD MOTOR COMPANY	61PCK58	PICK UP F250 - EXPLORATION
FORD MOTOR COMPANY	61PCK59	PICK UP F250 ELEC. SUPERINTEND
FORD MOTOR COMPANY	61PCK60	PICK UP F250 (G.F DYKE)
FORD MOTOR COMPANY	61PCK61	PICK UP F250 (SITE SERVICE)
FORD MOTOR COMPANY	61PCK62	PICK UP F250 (MINE G.F)
FORD MOTOR COMPANY	61PCK63	PICK UP F250 (A. HAMEL)
FORD MOTOR COMPANY	61PCK64	FORD EXPEDITION (AIR STRIP)
FORD MOTOR COMPANY	61PCK65	PICK UP F-350 2008 (WAREHOUSE)
FORD MOTOR COMPANY	61PCK66	PICK UP F-550 (MOBILE)
FORD MOTOR COMPANY	61PCK67	PICK UP F250 TRAINING/ KITCHEN
FORD MOTOR COMPANY	61PCK69	PICK UP F250 TRAINING MINE DEP
FORD MOTOR COMPANY	61PCK70	PICK UP F250 FIELD SITE SERVIC
FORD MOTOR COMPANY	61PCK71	PICK UP F250 (GEOLOGY)
FORD MOTOR COMPANY	61PCK72	PICK UP F250 (TO REPLACE)
FORD MOTOR COMPANY	61PCK73	PICK UP F250 - EXPLORATION
FORD MOTOR COMPANY	61PCK74	PICK UP F250 (VAULT)
FORD MOTOR COMPANY	61PCK75	PICK UP F450 BIT TRUCK (VAULT)
FORD MOTOR COMPANY	61PCK76	PICK UP F250 MTNCE SUPERVISOR
FORD MOTOR COMPANY	61PCK77	PICK-UP F250 - EXPLORATION
FORD MOTOR COMPANY	61PCK78	PICK-UP F250 MINE SUPERINTEND

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

FORD MOTOR COMPANY	61PCK79	PICK-UP F250 MNTCE SUPERINTEND
FORD MOTOR COMPANY	61PCK80	F450 KITCHEN CUBE
FORD MOTOR COMPANY	61PCK81	F350 ERT VEHICULE
FORD MOTOR COMPANY	61PCK82	PICK UP F250 AMARUQ
FORD MOTOR COMPANY	61PCK83	PICK UP F250 AMARUQ
FORD MOTOR COMPANY	61PCK84	PICK UP F250 AMARUQ
FORD MOTOR COMPANY	61PCK85	PICK UP F250 AMARUQ
FORD MOTOR COMPANY	61PCK86	PICK UP F250 AMARUQ
FORD MOTOR COMPANY	61PCK87	PICK UP F250 AMARUQ
FORD MOTOR COMPANY	61PCK89	PICK-UP F250 - EXPLORATION
FORD MOTOR COMPANY	61PCK90	PICK UP F350 FOUNTAIN TIRE
FORD MOTOR COMPANY	61PCK91	PICK-UP F250
FORD MOTOR COMPANY	61PCK92	PICK-UP F250
FORD MOTOR COMPANY	61PCK93	PICK-UP F250
FORD MOTOR COMPANY	61PCK94	PICK-UP F250
FORD MOTOR COMPANY	61PCK95	PICK-UP F250
FORD MOTOR COMPANY	61PCK96	FOUNTAIN TIRE SERVICE TRUCK
FORD MOTOR COMPANY	61PCK97	PICK-UP F250
FORD MOTOR COMPANY	61PCK98	PICK-UP F250
FORD MOTOR COMPANY	61PCK99	PICK-UP F250
	61PCO03	ANFO LOADER/BLAST HOLE CHARGER
ATLAS COPCO	61RBD01	ROTARY BLAST DRILL 6" ATLAS
ATLAS COPCO	61RBD02	ROTARY BLAST DRILL 6" ATLAS
ATLAS COPCO	61RBD03	ROTARY BLAST DRILL 6" ATLAS
ATLAS COPCO	61RBD04	ROTARY BLAST DRILL 6" ATLAS
ATLAS COPCO	61RBD06	DML DRILL 6" ATLAS
ATLAS COPCO	61RBD07	DML DRILL 6" ATLAS
ATLAS COPCO	61RBD08	DML DRILL 6" ATLAS
ATLAS COPCO	61RBD09	DML DRILL 6" EPIROC
SANDVIK	61RBD10	SANDVICK LEOPARD DI650I
SANDVIK	61RBD11	PEDESTAL DRILL DI650I
	61SBL01	SNOWBLOWER FOR LOADER 966H
	61SBL02	SNOWBLOWER FOR LOADER 966H
	61SBL03	SNOWBLOWER T85-R52
	61SBL04	SNOWBLOWER T85-R52
	61SCI05	SCISOR LIFT GENIE GS3232
	61SCI06	GENIE S85
	61SCI07	MAN LIFT GENIE Z-45/25
	61SCI08	MAN LIFT GENIE Z-45/25

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

	61SCI10	GENIE S85 (OLD 61REN07)
	61SCI11	GENIE S85 - AMARUQ
	61SCI12	GENIE S85
	61SCI13	GENIE S125
	61SCI14	GENIE S125
	61SCI15	SCISSOR LIFT GENIE 32'
	61SCI16	SCISSOR LIFT GENIE 32'
MACLEAN	61SCI19	SCISSOR LIFT MACLEAN SL3
MACLEAN	61SCI20	SCISSOR LIFT MACLEAN SL3
	61SCI21	SCISSOR LIFT GENIE 34'
	61SCI22	SCISSOR LIFT GENIE 62'
	61SCI23	SCISSOR LIFT GENIE 45'
GENIE BOOM	61SCI24	MANLIFT GENIE Z80
JLG	61SCI25	MANLIFT JLG 1200
MACLEAN	61SCI26	SCISSOR LIFT MACLEAN SL3
MACLEAN	61SCI27	SCISSOR LIFT MACLEAN SL3
MACLEAN	61SCI28	SCISSOR LIFT MACLEAN SL3
GENIE BOOM	61SCI29	MAN LIFT GENIE Z45FE
CATERPILLAR	61SCO01	SCOOP R1700G CAT
CATERPILLAR	61SCO02	SCOOP R1700G CAT
SANDVIK	61SCO03	SCOOP SANDVIK LH517I
SANDVIK	61SCO04	SCOOP SANDVIK LH517I
SANDVIK	61SCO05	SCOOP SANDVIK LH517I
CATERPILLAR	61SCO06	SCOOP R1300 CAT
SANDVIK	61SCO07	SCOOP SANDVIK LH517I
SANDVIK	61SCO08	SCOOP SANDVIK LH517I
CATERPILLAR	61SKD01	SKID STEER 262C CATERPILLAR
CATERPILLAR	61SKD02	SKID STEER 753 CATERPILLAR
CATERPILLAR	61SKD03	SKID STEER 262C CATERPILLAR
CATERPILLAR	61SKD04	SKID STEER 262C CAT
	61SKD06	SKID STEER S70
VOLVO	61SKD07	SKID STEER VOLVO
CATERPILLAR	61SKD08	SKID STEER 297C CAT
CATERPILLAR	61SKD09	SKID STEER 232D CAT
CATERPILLAR	61SKD10	SKID STEER 232D CAT
CATERPILLAR	61SKD11	SKID STEER 262D3 CAT
ARTIC CAT	61SNC01	SNOWCAT EMERGENCY VEHICLE
ARTIC CAT	61SNO01	SNOW MOBILE
ARTIC CAT	61SNO02	SNOW MOBILE

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

SKI DOO	61SNO03	SKI DOO SCANDIC
BOMBARDIER	61SNO04	SNOW MOBILE
BOMBARDIER	61SNO05	SNOW MOBILE
BOMBARDIER	61SNO06	SNOW MOBILE 600ACE
	61TPA01	ZOOM BOOM GENIE GTH844
	61TPA02	ZOOM BOOM GENIE GTH844
HYSTER	61TPA03	HYSTER CONTAINER HANDLER
INGERSOLL RAND	61TPA04	IR ZOOM BOOM 1056C (OLD REN16)
INGERSOLL RAND	61TPA05	TELEHANDLER VR1056D (OLD REN15)
CATERPILLAR	61TPA06	TELEHANDLER TL1055D CAT
CATERPILLAR	61TPA07	ZOOM BOOM GENIE GTH844
	61TPA09	TELEHANDLER LANTIS 828
	61TPA10	ZOOM BOOM GENIE GTH1056
MANITOU	61TPA11	TELEHANDLER MANITOU MTL625
WALKIE	61TPA12	ELECTRIC WALKIE PALLET
CATERPILLAR	61TPA13	TELEHANDLER CAT TL1055D
CATERPILLAR	61TPA14	TELEHANDLER CAT TH514D
CATERPILLAR	61TPA15	TELEHANDLER CAT TH514D
CATERPILLAR	61TPA16	TELEHANDLER CAT TH514D
CATERPILLAR	61TPA17	TELEHANDLER TH255C CAT
CATERPILLAR	61TPA18	TELEHANDLER XTREME XR2042-C
KUBOTA	61TRA01	TRACTOR M5-111CAB
KUBOTA	61TRA02	TRACTOR M5-111CAB
KUBOTA	61TRA03	TRACTOR M5-111CAB
KUBOTA	61TRA04	TRACTOR KUBOTA M5-111CAB
KUBOTA	61TRA05	TRACTOR KUBOTA M5-111CAB
KUBOTA	61TRA06	TRACTOR KUBOTA M5-111CAB
KUBOTA	61TRA07	TRACTOR KUBOTA M5-111CAB
KUBOTA	61TRA08	TRACTOR KUBOTA M5-111CAB
	61TRA08TOOL	TRACTOR 08 TOOLS UG
JOHN DEERE	61TRA09	TRACTOR JOHN DEER 6110M CAB
JOHN DEERE	61TRA10	TRACTOR JOHN DEER 6110M CAB
KENWORTH	61TRK01	KENWORTH WATER TRUCK 4000 GL
KENWORTH	61TRK05	KENWORTH TRUCK (3AXLE TRACTOR)
FORD MOTOR COMPANY	61TRK07	WATER DELIVERY TRUCK FORD
FORD MOTOR COMPANY	61TRK08	SEPTIC TRUCK FORD
MACK	61TRK11	CEMENT TRUCK MAC - AMARUQ
STERLING (TRUCK)	61TRK12	1 AXLE SERVICE TRUCK
KENWORTH	61TRK16	KENWORTH TRUCK

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

KENWORTH	61TRK17	KENWORTH TRUCK
KENWORTH	61TRK18	GARBAGE TRUCK KENWORTH
FORD MOTOR COMPANY	61TRK19	WELDING TRUCK
STERLING (TRUCK)	61TRK21	FUEL TRUCK
INTERNATIONAL BUSINESS MACHINE	61TRK22	SNOW PLOW WITH WING&SANDER
INTERNATIONAL BUSINESS MACHINE	61TRK23	SNOW PLOW WITH WING&SANDER
GENERAL MOTORS CORPORATION	61TRK24	STEAMER TRUCK
INTERNATIONAL BUSINESS MACHINE	61TRK31	MECHANICAL SERVICE TRUCK
GENERAL MOTORS CORPORATION	61TRK32	GMC AIR PLANE FUEL TANKER
KENWORTH	61TRK33	CAT LUBE TRUCK T300
STERLING (TRUCK)	61TRK34	STERLING SERVICE TRUCK
FORD MOTOR COMPANY	61TRK38	FORD SERVICE TRUCK
	61TRK39	LUBE TRUCK
MACK	61TRK41	PUMP TRUCK MACK
KENWORTH	61TRK42	FUEL TRUCK
KENWORTH	61TRK43	WATER TRUCK
KENWORTH	61TRK44	SERVICE TRUCK
KENWORTH	61TRK45	LUBE TRUCK
KENWORTH	61TRK46	FIRE TRUCK
KENWORTH	61TRK47	DRAMIS TRUCK C500 10X10
KENWORTH	61TRK49	SAND TRUCK T800
KENWORTH	61TRK50	MECHANICAL T800 SERVICE TRUCK
MACLEAN	61TRK51	BOOM TRUCK MACLEAN BT3
FREGHTLINER	61TRK52	SEWAGE VACUUM TRUCK
	61TRK53	TOROMONT SERVICE TRUCK F-46
STERLING (TRUCK)	61TRK54	TOROMONT SERVICE TRUCK F-47
FREGHTLINER	61TRK55	AMARUQ FIRE TRUCK
WESTERN STAR	61TRK56	WESTERN STAR TRUCK
WESTERN STAR	61TRK57	WESTERN STAR TRUCK
PETERBUILT	61TRK58	PETERBUILT 367 TRUCK
WESTERN STAR	61TRK59	WESTERN STAR TRUCK
MACLEAN	61TRK60	EMULSION CHARGER EC3
KENWORTH	61TRK61	WATER TRUCK T800
KENWORTH	61TRK62	ROLL OFF TRUCK T800
KENWORTH	61TRK64	ASSET NUMBER AVAILABLE
MACLEAN	61TRK65	CASSETTE CARRIER MACLEAN CS3
MACLEAN	61TRK66	CASSETTE CARRIER MACLEAN CS3
MACLEAN	61TRK67	TRANSMIXER MACLEAN TM3
STERLING (TRUCK)	61TRK68	TOROMONT SERVICE TRUCK F-48

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

POLAR	61TRK69	POLAR AIRCRAFT DEICER
KENWORTH	61TRK70	FUEL TRUCK
KENWORTH	61TRK71	FUEL TRUCK
KENWORTH	61TRK72	WATER TRUCK
KENWORTH	61TRK73	LUBE TRUCK
FORD MOTOR COMPANY	61TRK74	SERVICE TRUCK 11M3
MACLEAN	61TRK75	CONCRETE TRUCK AG3
KENWORTH	61TRK76	MECHANICAL SERVICE TRUCK
KENWORTH	61TRK77	MECHANICAL SERVICE TRUCK
	61TRL01	BEDARD TANKER TRAILER
	61TRL03	BELLY DUMP TRAILER
	61TRL04	LOW BED TRAILER
	61TRL05	LOW BED TRAILER
	61TRL08	DOUBLE DROP LOW BOY
	61TRL09	FIRE TRAILER SKID W/ PUMP
TEMISKO	61TRL101	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL102	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL103	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL104	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL105	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL106	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL107	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL108	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL109	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL110	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL111	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL112	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL113	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL114	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL115	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL116	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL117	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL118	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL119	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL120	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL121	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL122	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL123	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL124	SIDE DUMP B-TRAIN TRAILER LEAD

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

TEMISKO	61TRL125	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL126	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL127	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL128	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL129	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL130	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL131	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL132	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL133	SIDE DUMP B-TRAIN TRAILER LEAD
TEMISKO	61TRL201	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL202	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL203	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL204	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL205	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL206	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL207	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL208	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL209	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL210	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL211	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL212	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL213	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL214	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL215	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL216	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL217	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL218	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL219	SIDE DUMP B-TRAIN TRAILER REAR
KUBOTA	61TRL22	STEAM-PRESSURE WASH TRAILER
TEMISKO	61TRL220	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL221	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL222	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL223	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL224	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL225	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL226	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL227	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL228	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL229	SIDE DUMP B-TRAIN TRAILER REAR

Production Lease KVPL08D280
Meadowbank Project 2022 Mine Plan

	61TRL23	STEAM-PRESSURE WASHER TRAILER
TEMISKO	61TRL230	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL231	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL232	SIDE DUMP B-TRAIN TRAILER REAR
TEMISKO	61TRL233	SIDE DUMP B-TRAIN TRAILER REAR
	61TRL24	EXTENSIBLE TRAILER MANAC
	61TRL26	SPLEIPNER
	61TRL27	MOBILE FUEL TANKER JET-A
	61TRL31	14' ENCLOSED TRAILER
	61TRL44	16' ENCLOSED TRAILER
TEMISKO	61TRL45	130T OFF ROAD LOW BOY
	61TRL62	HI BED TRAILER
	61TRL63	TELESCOPIC SEMI-TRAILER
	61TRL64	STEAM-PRESSURE TRAILER
	61TRL65	STEAM-PRESSURE TRAILER
	61TRL66	ARTIC FUEL TRAILER FLEET
LEGEND	61TRL67	LEGEND BOAT TRAILOR
KAWASAKI	61VSE01	KAWASKI MULE
KAWASAKI	61VSE02	KAWASKI MULE
KAWASAKI	61VSE05	KAWASKI MULE (SITE SERVICES)
KAWASAKI	61VSE06	KAWASKI MULE
KUBOTA	61VSE08	KUBOTA MULE RTV1100
KUBOTA	61VSE12	KUBOTA MULE RTV1100
KUBOTA	61VSE13	KUBOTA MULE RTV1100
TOYOTA	61VSE14	LANDCRUISER HZJ79
TOYOTA	61VSE15	LANDCRUISER HZJ79
TOYOTA	61VSE18	LANDCRUISER HZJ79
TOYOTA	61VSE20	LANDCRUISER TOYOTA HZJ79
TOYOTA	61VSE21	LANDCRUISER TOYOTA HZJ79
TOYOTA	61VSE22	LANDCRUISER TOYOTA HZJ79
TOYOTA	61VSE23	LANDCRUISER TOYOTA HZJ79
TOYOTA	61VSE24	LANDCRUISER TOYOTA HZJ79
TOYOTA	61VSE25	LANDCRUISER TOYOTA HZJ79

SECTION 5 • 2022 PLANNED ENVIRONMENTAL MONITORING

The studies discussed below may continue to be impacted by restrictions related to COVID-19 and therefore may require adjustment throughout 2022.

5.1 WILDLIFE MONITORING

All wildlife monitoring is conducted in accordance with the Terrestrial Ecosystem Management Plan (TEMP) and discussions with the Terrestrial Advisory Group (TAG).

5.1.1 Terrestrial Advisory Group

As part of the Terrestrial Advisory Group (TAG), meeting to discuss Project's mitigation, monitoring, and adaptive management measures related to the protection of wildlife will continue to be held in 2022.

5.1.2 Harvest Study

The Hunter Harvest Study (HHS), through regular visits, has contributed to developing a strong relationship with local harvesters, the HTO and GN Department of Environment (DOE). The purpose of the HHS is to monitor and document the spatial distribution, seasonal patterns, and harvest rates of hunter kills and angler catches within the Meadowbank Local Study Area (LSA). Hunter Harvest Study will continue in 2022.

5.1.3 Habitat mapping

The habitat mapping monitoring program was developed to describe the overall area of different Ecological Land Classification (ELC) units lost due to mine-related activities at three primary locations: Main and Vault sites (which together encompass the mine site), and the AWAR. The primary objective of the habitat mapping monitoring program is to confirm that estimated habitat losses associated with mine site and AWAR construction have not exceeded the threshold limits identified in the TEMP plus approved extensions. Habitat mapping was last completed in 2019, the next program is to be conducted in 2022.

5.1.4 Breeding Bird Plot Surveys

The breeding bird PRISM plot monitoring program was designed to evaluate potential project-related changes in breeding bird species abundance, richness and diversity over time and is one component of the larger monitoring strategy to evaluate the success of mitigation measures to minimize the amount of vegetation that is removed or degraded by the project.

A comprehensive analysis of the data from 2003 to 2015 was completed in 2020 to validate the need for future PRISM plot monitoring and replacing the monitoring with an ECCC recommended program. The statistical analysis did not find any significant effect of mine-related infrastructure and activity on bird abundance, diversity, and community composition. The absence of effect supports replacing the

PRISM plot monitoring program with an ECCC recommended program. The new monitoring program would better contribute to national and regional monitoring efforts.

The new program would consist of 48 PRISM plots, GIS-randomly selected by ECCC within the Meadowbank and Whale Tail areas to be surveyed between 2021-2031. In addition, a Breeding Bird Survey (BBS) route would be established along the Meadowbank AWAR and the Whale Tail Haul Road. Survey are to be every 3 years as a minimum. PRISM and BBS survey are schedule for 2022.

5.1.5 Raptor Nest Surveys

The raptor nest survey monitoring program has been designed to confirm that mine-related activities do not result in inadvertent negative effects on nesting raptors. Agnico Eagle will survey historical sites along the AWAR and periodically visit the nests to determine site occupancy in conjunction with AWAR road survey. Agnico Eagle is working closely with Alastair Franke (Arctic Raptors Inc.) to assist in managing and mitigating any potential disturbance to raptors and possible nest sites.

5.1.6 Caribou Satellite-Collaring Program

Agnico Eagle is assisting the GN in a Caribou satellite-collaring program within the Meadowbank Regional Study Area (RSA). Information on the status and location of various herds that use the RSA at different times of the year is an important component of on-going monitoring and management efforts at the mine site and along the AWAR. The collaring program was initiated in May 2008 with subsequent deployments over the years.

In collaboration with the GN DOE Wildlife branch, Agnico Eagle agreed, in 2013, to the Memorandum of Understanding (MOU) to contribute to the regional ungulate monitoring program. A new MOU is currently under discussion with the GN. This collaring data will be used to assist Agnico Eagle in anticipating large herds passing near mine development and contribute to appropriate management decisions.

5.1.7 Checklist Surveys and Wildlife Logs

At the mine site, noteworthy wildlife sightings are recorded in an on-site wildlife log, which is tabulated at the end of each year and included in the annual wildlife monitoring summary report. Meadowbank employees are also encouraged to record wildlife sightings on a daily basis. A monthly wildlife report is sent to the GN DOE and KivIA.

5.1.8 AWAR and Mine-Site Road Surveys

The AWAR and Mine-Site road surveys monitoring program has been designed to evaluate sensory disturbance to wildlife, particularly Caribou and Muskox, utilizing habitats adjacent to the road. Roadkill information and large Caribou herds are also documented to facilitate the implementation of adaptive management strategies. The terrain on both sides of the road (to a maximum horizontal distance of 1 km) is surveyed as the vehicle progresses at a maximum speed of 30 km/hr. For each

sighting, the vehicle is safely parked in a road pullout and UTM coordinates are recorded along with estimated distance of animals from the road, habitat type and direction of movement.

The AWAR survey monitoring program will continue on an annual basis.

5.1.9 Screening Level Risk Assessment

As a requirement for the Meadowbank Gold site's Environmental Health Monitoring Plan (NIRB - Condition 67), Agnico Eagle collected field data in 2014 in support of a Screening Level Risk Assessment (SLRA) and submitted a report with the 2014 annual report. It follows the baseline SLRA completed by Azimuth Consulting Group Inc. in 2006, 2011, 2014 and 2017 reports completed by Baxter Consulting. It provided an updated evaluation of soil and vegetation tissue chemistry as well as an assessment of risk to resident birds, mammals and a conservative estimate of potential impacts to local harvesters due to consumption of wildlife. Sampling was completed for this program in 2021 and the results will be reported as part of the 2021 Annual Report. The next sampling campaign is planned for 2024.

5.2 AQUATIC EFFECTS MONITORING PROGRAM

5.2.1 Core Receiving Environment Monitoring (CREMP)

The CREMP has been implemented every year since 2006, with some modifications (e.g., station additions, parameter deletions/additions, sampling frequency and intensity), to improve the program and to comply with regulatory requirements (e.g., the NWB Type A Water License). This monitoring program will continue throughout the operations and closure phases of the mine project as per the approved CREMP Monitoring Plan.

5.2.2 Metal and Diamond Mining Effluent Regulations (MDMER) Monitoring

In 2022, Meadowbank Site will have one discharge point subject to MDMER regulations: East Dike Seepage, discharging into Second Portage Lake. Consequently, Agnico Eagle is monitoring this discharge in accordance with the MDMER (and Water License) requirements. This includes weekly sampling, quarterly toxicity testing, and monitoring water quality in the release and control areas of Second Portage Lake (with Third Portage South Basin as a reference). Furthermore, in 2014, Agnico Eagle completed the Biological Monitoring Study Cycle 2 in Third Portage Lake as per MDMER Schedule 5 Part 2. In 2017, Agnico Eagle completed the Biological Monitoring Study Cycle 3 in Wally Lake as no more water was discharging from the Portage Attenuation Pond since November 2014, as the former South Cell Attenuation Pond became tailings storage facility in Q4 2014. The Biological Monitoring Study Cycle 4 was completed in 2020 and the Interpretive Report was submitted in July 2021. This program is regulated by Environment and Climate Change Canada and is designed specifically to evaluate the effects of effluent discharge on the receiving environment. No Biological Monitoring study scheduled for 2022.

5.2.3 Water Quality and Flow Monitoring

All water sampling conducted at the mine site and along the Awar designed to monitor the performance of the waste and water management systems for the project fall into this category. In 2022, Agnico Eagle will continue to monitor the performance at the sewage treatment plant, in-pit tailings deposition, and reclaim tailings reclaim pond, Vault attenuation pond, pit sumps, seeps, bulk fuel storage facilities, freshwater usage volumes, water quality along the Awar, and all other monitoring requirements stipulated in NWB Type A water license 2AM-MEA1530. See Figure 1 and Figure 2 for all the 2022 water monitoring stations at Meadowbank Mine Site and Vault.

5.2.4 Habitat Compensation Monitoring Program

The habitat compensation monitoring program will continue in 2022 as per the approved Habitat Compensation Monitoring Plan. Results of this program will be provided as part of the 2022 Annual Report.

Figure 1: Meadowbank Mine Site 2022 Sampling Locations



Figure 2 : Vault 2022 Sampling Locations



5.2.5 Seepage Water from Waste Rock Storage Facility

The KivIA requested that Agnico continue monitoring until there is a 5-year period of non-detect cyanide results. The monitoring from 2014-2018 indicated that yearly average for CN levels does not exceed the CCME guideline, the MDMER or Water License limit for effluent discharge into the environment for NP2, NP1 and downstream lakes, Dogleg and Second Portage. Thus, based on the analysis of the previous result, Agnico Eagle suspended the current program in 2019 and only collects samples in NP-2 and WRSF sump during open water season. In 2022, water quality monitoring sample will be taken in the WRSF seepage sump and receiving environment described above.

Agnico Eagle's work plan in 2022 will continue to closely follow the Freshet and Incident Action Plan which will include the active pumping and monitoring (location, quantity and quality) of the water from WEP1, WEP2 and ST-16 sump (which is pumped to the North Cell TSF). During the ice period, a weekly visual inspection will be done. Agnico Eagle will also continue to monitor the tailings and waste rock freeze back in accordance with Part I, Item 9 of the Type A Water License.

5.2.6 Assay Road Seepage

Monitoring and mitigation of the Assay Road Seepage will continue in 2022. All seepage water during the freshet and until the freeze up will be contained (as in the past) in the original sump and trench and pumped back to the mill. Based on shallow groundwater well monitoring downstream of the interception trench, all the water was contained and did not reach TPL. Agnico Eagle will also follow in 2022 the Freshet and Incident Action Plan which will include the active pumping of the water back to the mill, groundwater monitoring and continued sampling of Third Portage Lake.

5.2.7 Central Dike Seepage

Monitoring of the Central Dike seepage will continue in 2022. The seepage is located within the mining footprint, away from the receiving environment and is confined directly downstream of the dike. In 2022, Agnico Eagle will continue to collect water in ST-S-5 and pump it back into Goose Pit, Portage Pit A, or Portage Pit E. Monthly sampling will continue as per the requirements of the NWB Water License.

5.2.8 Blast Monitoring

Given the cessation of mining activities at Meadowbank, the blast monitoring program is not expected to be required. If blasts are needed, the monitoring program will be restarted. The program will monitor blasting peak particle velocity and overpressure in the receiving environment and ensure that Agnico Eagle uses the specific charge weight/delay/set back necessary to meet DFO requirements, and to ensure the stability of the dikes and mines site infrastructure.

5.3 GROUNDWATER MONITORING PROGRAM

The groundwater monitoring will continue in 2022. As in the past, the groundwater monitoring program will be conducted in the summer and / or the fall. Sampling of the active wells will continue in 2022. Results will be provided in the annual report.

5.4 NOISE MONITORING PROGRAM

The noise monitoring will continue in 2022 with sampling twice a year at the five monitoring locations established at the mine site. Results will be provided in the annual report.

5.5 AIR MONITORING PROGRAM

Agnico Eagle has conducted annual dustfall and air quality monitoring around the Meadowbank site since 2011. Two (2) passive NO₂ samplers and four (4) dustfall collectors were installed on site in November 2011, with the first result received in December 2011. This air monitoring will continue on a monthly basis in 2022. Since 2013, Agnico Eagle also conducted dustfall monitoring along selected areas of the AWAR in response to NIRB, HTO and community concerns. This will continue in 2022. Results will be provided in the annual report.

SECTION 6 • LOGISTICS

Fuel, bulk goods and construction materials will be transported to site overland via the All Weather Access Road. Charter flights carrying cargo and personnel will be routed directly to the mine site via the Meadowbank airstrip.

SECTION 7 • 2022 PROGRESSIVE RECLAMATION PLAN

Agnico Eagle will follow and comply with the approved Interim Closure and Reclamation Plan.